
# DATABOOK

Price 25 cents



### POCKET DATABOOK

## RAYTHEON RADIO RECEIVING TUBES

## RAYTHEON PRODUCTION CORPORATION

55 Chapel Street Newton, Mass. 420 Lexington Ave. New York, N. Y. 445 Lake Shore Drive Chicago, Ill. 555 Howard St. San Francisco, Cal. 415 Peachtree St., NE Atlanta, Ga.

### Copyright 1957

bу

### RAYTHEON PRODUCTION CORPORATION

Newton, Mass.

It is the responsibility of the user to determine whether any commercial use of the data or circuits presented in this booklet constitutes infringement of any patent, and no liability or obligation of any kind is assumed by Raytheon with respect to such use.

Each tube sold by Raytheon is licensed only to the extent of the notice which appears on the carton containing the tube.

FIRST EDITION Third Printing June, 1938 Form R-632A

### FOREWORD

This DATA BOOK has been prepared by the Raytheon Production Corporation to furnish in compact form the chief technical data on the complete line of radio broadcast receiving tubes. In addition to the maximum ratings and values of essential characteristics there are given in this booklet the more important characteristic and operating curves for each active tube. The information given by these curves may well be even more valuable and useful than the ratings and nominal characteristics. This information has not heretofore been generally available in convenient and readily accessible form, Much of it has previously been obtainable only by a limited number of receiver design engineers. Data are given on all tubes that have been at all widely used in the past in receivers and amplifiers that are still handled in the trade as replacements; also on all types that are being used in new receivers including all new types announcedup to the end of 1937.

To make this booklet of maximum usefulness an introductory section has been included which gives brief descriptions of the various classes of tubes and how they operate; definitions of the various tube characteristics and terms and explanations of how these quantities may be determined from the characteristic curves; simple circuit diagrams showing the essentials of the various sections of a modern radio receiver, including the newer features, and convenient charts for determining the proper values of certain tube circuit constants and operating voltages.

For completeness there have been included the essential data on Raytheon resistor tubes and panel lamps for radio receivers.

This booklet has been designed for the use of design engineers, radio dealers, servicemen and members and customers of the radio industry generally. Much thought and labor has been devoted to its preparation. It is our hope that it will prove really useful and at the same time acquaint you with Raytheon tubes and Raytheon Engineering Service.

### TABLE OF CONTENTS

	PAGE
TUBE ELEMENTS	5
TUBE CLASSIFICATION BY STRUCTURE	5
TUBE CLASSIFICATION BY FUNCTION	6
FUNDAMENTAL CHARACTERISTICS OF RADIO TUBES	7
TUBE APPLICATION AND CIRCUITS	9
RECOMMENDED OPERATING PRACTICES	19
CONVERSION CURVES	22
RESISTANCE COUPLED AMPLIFIER DESIGN CURVES	23
TUBE TESTING	26
RAYTHEON RECEIVING TUBE LIST	<b>2</b> 8
RAYTHEON SPECIAL RECEIVING TUBES	31
INTERCHANGEABLE TUBE TYPES	32
RAYTHEON RESISTANCE TUBES	33
RAYTHEON PANEL LAMPS	34
RATINGS AND CHARACTERISTICS OF RAYTHEON RECEIVING TUE	BES

### TUBE ELEMENTS

A radio tube, or vacuum tube, is a vacuum device in which electric current flows, as a stream of electrons, through the evacuated space from one electrode to another. A HIGH VACUUM TUBE is one in which the degree of vacuum is so high that the characteristics of the tube are not affected by gas conization. Most radio receiving tubes are of this class. A GAS TUBE is one which has a gas filling, usually at relatively low pressure, and in which gas ionization is essential to the normal operation of the tube. Types 32 and 0246 are examples of this class.

CATHODE The cathode is the electrode which supplies the electrons necessary for the operation of the tube. In general the cathode must be heated to obtain sufficient emission of electrons. A FILAMENTARY CATHODE is in the form of a wire or ribbon through which heating current flows and is sometimes called a "directly heated" cathode. In some of the earlier receiving tubes, such as the 199 and the 201A, the cathode is a filament of thoriated tungsten and is normally operated at a temperature of approximately 1700°C. In more recent types, such as the 26, 45, and 1A4, the cathode is a wire or ribbon of nickel or nickel alloy coated with the oxides of barium and strontium and is normally operated at 600° to 800°C. A UNI-PO-TENTIAL, or "indirectly heated", cathode consists of a metal sleeve, usually nickel, which encloses an insulated filament, or heater, through which heating current flows. The cathode sleeve is generally coated with the oxides of barium and strontium and is operated normally at 600° to 800°C.

PLATE The plate, or anode, is the electron collector element of a tube and is normally the one to which the main portion of the electron stream flows. It is usually in the form of a cylinder of thin metal and may be circular, oval or rectangular in cross-section. In some tubes the plate is carbonized to increase its heat radiating ability.

GRID A grid is an auxiliary electrode placed between the cathode and the plate. It usually consists of a spiral of wire fastened at each turn to one or more, usually two, longitudinal support wires. In cross-section, the outline of a grid may be circular, oval or rectangular. The grid spiral is usually of uniform pitch, but some tubes employ VARIABLE MU GRIDS in which the turns are not uniformly spaced. In a few cases the grid consists merely of two vertical wires or strips of motal. The grids in a multi-grid tube are commonly referred to by numbers indicating their position radially with respect to the cathode, number 1 grid being adjacent to the cathode, frids are also referred to by numbers indicating their function. A COUTROL GRID, or input grid, is one to which an input signal voltage is applied and which modulates the main electron stream in accordance with the input signal. A STACE CHARGE GRID is a grid placed in the electron stream and positively charged to partially neutralize the space charge effect caused by the cloud of electrons surrounding the cathode. Besides accelerating the electrons toward the plate, a screen grid and the plate and operated at a positive de voltage with respect to the cathode. Besides accelerating the electrons toward the plate, a screen grid and the plate and connected to a point of low de- potential to prevent the passage of low velocity secondary electrons originating either at the plate and the control grid. A SUPPRESSOR GRID is a grid placed between the screen grid and the plate and connected to a spoint of low de- potential to prevent the passage of low velocity secondary electrons originating either at the plate on a the screen grid. In some tubes it is connected internally to the cathode and in others it is connected to a separate base pin. In some pentagrid tubes, such as the type 6A7, the number two grid, which serves as the anode for the oscillator section, it called the Alfold GRID. The term Alloged GRIDS refer to a pair of adjacent grids having the same number of

### TUBE CLASSIFICATION BY STRUCTURE

Radio tubes may be classified according to the number of elements or electrodes they contain.

A DIODE is the simplest form of tube and contains two elements, a cathode and a plate. Types 01 and 1223 are examples of this class.

A TRIODE or three element tube, contains a cathode, a grid and a plate, as for example, types 27 and 2A3.

A TETRODE is a four element tube having a cathode, two grids and a plate. The name SCREEN GRID TUBE is sometimes used for a tetrode, such as the type 24A, in which the outer grid is operated as a screen grid. One type of tetrode is a EEAL POWER TUBE in which the electrode are so spaced that the electron stream is confined to relatively narrow paths, or beams, and sufficient space charge is built up between the screen grid and the plate oprevent any appreciable flow of secondary electrons between them. The electron beams are produced by the use of aligned grids and deflector plates particilly surrounding the coreen grid support rods and connected electrically to the cathode. The 6L6 and 3V3G are beam power tubes.

A PENTODE is a five element tube which contains a cathode, three grids and a plate, types 7% and 42, for example.

- A HEXODE is a six element tube containing a cathode, a plate and four other electrodes.
- A HEPTODE is a seven element tube having a cathode, a plate and five other electrodes, usually grids. PENTAGRID is another term applied to this type of tube. Types 6A7 and 6L7 are in this classification.
- A MULTIPLE UNIT TUBE is one containing two or more sets of electrodes, or units, in the same envelope. In some types a single cathode, common to both units, is used; in others separate cathodes are used. Each unit can usually be operated as if it were a separate tube in its own envelope. A two unit tube is often referred to as a DUO-or DUPLEX- TUBE.
- A DUO-DIODE is a duplex tube containing two diode units, as a type 80 or a 6H6.
- A DUO-DIODE TRIODE is a duplex tube containing a duo-diode unit and a triode unit, as a type 75.
- A DUO-DIODE PENTODE is a duplex tube containing a duo-diode unit and a pentode unit, as a type 6B7.
- A DIODE-PENTODE is a duplex tube containing a diode unit and a pentode unit, as a type 12A7 or a 25A7G.
- A TRIODE-PENTODE is a duplex tube containing a triode unit, and a pentode unit, as a type  $6F7_{\bullet}$
- A TRIODE-HEPTODE is a duplex tube containing a triode unit and a heptode unit.
- A TWIN TUBE is a duplex tube containing duplicate units, types 6A6 and le7G, for example.

### TUBE CLASSIFICATION BY FUNCTION

Tubes may be further classified according to their uses or functions in a circuit.

- A RECTIFIER TUBE usually a diode or a twin diode, is one used in obtaining a direct current or voltage from an alternating current supply.
- A HALF-WAVE RECTIFIER TUBE is one used in a half-wave rectifier circuit and in which current flows only during alternate half-cycles of the ac supply voltage. A half-wave rectifier tube is usually a diode such as a type 81 or a 1223. However, a triode like the type 37 or other multi-electrode tube may be used by connecting the grid or grids to the plate to form a diode
- A FULL-WAVE RECTIFIER TUBE is a twin diode used in a full-wave rectifier circuit in which the two diodes are so connected that current flows through one diode during one half-cycle and through the other diode on the alternate half-cycle of the a-c supply voltage. Two separate diodes may be used instead of a twin diode in a full-wave circuit.
- A VOLTAGE DOUBLER TUBE is a twin diode tube having separate cathodes insulated from each other so that the two sections may be connected in series in a voltage doubler circuit. Although a twin diode tube is usually used in this circuit, two separate diodes may be used to accomplish the same result.
- AN AMPLIFIER TUBE is one used to amplify a voltage applied by the input circuit between two electrodes, a control grid and the cathode. An amplified voltage appears in the output circuit, usually the plate circuit and a portion of this voltage is developed across the load impedance.
- A VOLTAGE AMPLIFIER TUBE is an amplifier tube used to supply an amplified voltage to another tube which may be another voltage amplifier tube, a power amplifier tube or a detector tube.
- A POWER AMPLIFIER TUBE is an amplifier tube used to develop a relatively large amount of power, as contrasted to voltage, in the output circuit and may be a triode, a tetrode, or a pentode.
- A REMOTE CUTOFF AMPLIFIER TUBE is one that requires a relatively high negative bias on the control grid to reduce the plate current and transconductance to zero or to very low values. Relatively large signal voltages may be applied to tubes of this class without producing serious cross modulation or modulation distortion. Most remote cutoff tubes are made with a variable-mu control grid.
- A DETECTOR TUBE is one used to separate the low frequency component of a modulated signal from the high frequency carrier of radio or intermediate frequency. Various types of tubes, diodes, triodes, and pentodes may be employed as detectors.
- AN OSCILLATOR TUBE is an amplifier tube operated in a suitable circuit to produce a-o power when supplied with d-o power. Triodes such as types 76 and 6J5G, are commonly used as oscillators in superheterodyne receivers.

A MIXER TUBE is one in which two applied voltages of different frequency are combined, or mixed, to produce beat frequency voltages which are equal to the sum and difference of the applied frequencies, in the output circuit.

A CONVERTER TUBE is a special form of mixer tube in which one of the two combining voltages is produced by self-oscillations in the tube itself. The 6A7 is one of the tubes designed specially for converter service but other multi-grid types, such as the type 77, have been used.

AN ELECTRON RAY TUNING INDICATOR TUEE is a tube in which an electron beam a fluorescent screen, or target. The shape and size of this luminous area vary in accordance with the voltage applied to the control grid of the tube, giving a visual indication of the changes in the control grid of the tube, ally this tube is a duo-triode, one section functioning as a d-c amplifier and supplying an amplified d-o voltage to the control electrode of the target section. The 6E5 is an example of a tuning indicator tube.

### FUNDAMENTAL CHARACTERISTICS OF RADIO TUBES

A radio tube, as a circuit element, exhibits some electrical characteristics, such as resistance and capacitance, which are similar to those of other circuit elements and, in addition, it has other characteristics which are unique. Since the current flowing between two electrodes is not directly proportional to the d-c voltage between the electrodes is not directly proportional to the d-c voltage between them. For this reason, the a-c or variational characteristics depend on the d-c voltages applied between the elements and are not the same for large amplitudes as for small. Therefore, the characteristics of a tube, as a circuit element, are commonly expressed in terms of their values for a-c current and voltage of very small amplitudes, and with specified values of d-c voltage applied to the various electrodes. It is necessary to distinguish between the d-c voltages applied to the various electrodes. Which determine only the operating conditions, and the a-c voltages which are being amplified. The cathode is susually considered as the zero or reference point of voltage and the voltage between the cathode and any other electrode is designated as the voltage of that electrode, as for example, PLATE VOLTAGE, SCREEN-GRID VOLTAGE, and GRID VOLTAGE. The d-c voltage on the control grid is commonly called the GRID BIAS.

RECITITERS In a radio tube, the electrons originating at the cathode are attracted to any electrode which is at a positive potential with respect to the cathode and repelled from any electrode which is at a negative potential. Diode rectifier tubes depend on this fact for their operation, as plate current can flow only during the half-cycle when the plate is positive. The important characteristic of a rectifier tube is the STATIC FLAME CHARACTERISTIC, a curve showing the relation between the d-c plate voltage and current. Typical diode plate characteristic curves may be found in the rating and characteristic data section under any rectifier tube type, for instance, the type Sl. At low plate voltages the plate current increases approximately as the 3/2 power of the plate voltage. At higher plate voltages the plate current approaches the total electron emission of the cathode, which is the maximum value of plate current obtainable at a certain cathode temperature. A derived characteristic is the relation between the d-c output current and voltage in a typical rectifier circuit. Typical curves may be found in the rating and characteristic data section under any rectifier types, such as the type Sl. Since the values shown by the curves are dependent on the circuit constants, transformer resistance and reactance and smoothing filter characteristics, they should be used only to indicate the tube performance under certain arbitrary, but usually typical, operating conditions.

cal, operating conditions.

AMPLIFIERS In amplifier tubes, the amplification depends on the fact that a small voltage applied to the control gridhas the same effect on the plate current as a much larger voltage applied to the plate. A measure of this amplifying effect is the AMPLIFICATION FACTOR, μ or mu, which indicates the relative effectiveness of the grid voltage versus the plate voltage in controlling the plate current. It is equal to the quotient of a small change in plate voltage divided by the compensating change in grid voltage encessary to maintain the plate current constant. THE TRANSCOIDLOM-ANCE or MUTUAL CONDUCTANCE, Gm, of a tube is a factor indicating the magnitude of the controlling effect of the control grid voltage on the plate current, and is expressed in micromhos which are equivalent to micromaperes per volt. It is equal to the quotient of a small change in plate current divided by the change in grid voltage producing it, when all other elements voltages are constant and there is no external impedance in the plate circuit. The PLATE RESISTANCE, Rp, of a tube is the effective internal a-o resistance between the plate and cathode. It is expressed in chms and is expressed in the quotient of a small change in plate voltage of thicked by the accompanying change in plate current, with constant voltages on the other elements and no external impedance in the plate circuit, Amplification factor, transconductance and plate resistance are connected by the relation Gr=1/Rp, thence any one of these quantities may be found if the other vol are known. In multi-grid tubes there may be several values of amplification factor and transconductance, depending on which element is used as the control grid and which element as the plate transconductance, or grid #1 to plate transconductance or grid #1 to plate transconductance.

An amplifier tube may be considered as an a-c generator whose generated e.m.f., or open-circuit voltage is the product of the amplification factor,  $\mu$ , and the a-c grid voltage, Eg. The voltage, Hg, appears in the plate circuit in series with the plate resistance, Rp, which corresponds to the internal resistance of the generator. The transconductance is the short-circuit a-c current per unit of a-c grid voltage.

The VOLTAGE AMPLIFICATION or VOLTAGE GAIN is the amplification obtained from a tube in connection with its associated circuit, and is equal to the quotient of the a-c voltage,  $E_L$ , developed across the load resistance,  $R_L$ , divided by the a-c grid voltage,  $E_g$ . Since the a-c voltage generated in the output circuit of a tube is in series with the plate resistance, the a-c voltage developed across the load resistance depends on the relative values of  $R_D$  and  $R_L$ . The voltage amplification is given by the following formulas:

VOLTAGE GAIN = 
$$\frac{\angle IR_L}{R_P + R_L} = \frac{G_m R_P R_L}{R_P + R_L}$$
 (1)

TRIODES The static plate characteristic curves of a triode are similar to those of a diode, except that a family of curves is usually given, each curve corresponding to some arbitrarily chosen value of grid bias. Typical triode plate characteristic curves may be found in the rating and characteristic data section, for instance, under the types 6F5, 76, or 607. The other family of curves under the types 6F5 and 6Q7 shows the same information in another form, the relation between the d-c grid voltage, or bias and the d-c plate current for several values of d-c plate voltage. The amplification factor may be determined from the plate family of curves byfinding the plate voltage, at constant plate current, corresponding to two values of grid bias. The amplification factor is then equal to the quotient of the change in plate voltage divided by the change in grid voltage. The transconductance is equal to the slope of the plate current vs. grid voltage curve at any point where its value is desired. The transconductance may also be determined from the plate family of curves by finding the change in plate current, at constant plate voltage, corresponding to a change in grid bias. The transconductance, in micromhos, is then equal to the change in plate current in microamperes divided by the change in grid voltage. The plate current in microamperes divided by the change in grid voltage. The plate current in microamperes divided by the change in grid voltage. The plate current in microamperes divided by the change in grid voltage. The cateristics of a tube may be determined approximately from the static characteristic curves. In determining amplification factor, transconductance and plate resistance from the static characteristic curves, greater accuracy will be obtained if the increments read from the curves are as small as can be read conveniently.


TETRODES The plate current vs. control grid voltage curves of a tetrode are similar to those of a triode, but the plate current vs.plate voltage curves are quite different, as may be seen by referring to the plate characteristic curves of a typical tetrode, such as the type 244. At values of plate voltage higher than the screen grid voltage, where a tetrode is usually operated, the plate current curves are relatively flat, indicating high values of plate resistance and amplification factor. In this region the value of plate current depends more on the value of correng grid voltage than on the value of d-c plate voltage. At plate voltages lower than the screen grid voltage the values of plate current are unstable due to the effects of SECONDARY EMISSION. When the plate, or any other electrode, is more than about 12 volts positive the electrons which strike it cause it to emit secondary electrons. These electrons may be pulled back to the plate, or, if there is another electrode nearby at a higher-d-c potential, they may be drawn away from the plate to the higher potential electrode. In the region of the plate current characteristics where the plate is at a low d-c potential, the secondary electrons are drawn to the screen grid, decreasing the plate current son increasing the screen current correspondingly. In the operating region where the plate is at a higher potential than the screen grid, the plate ourrent is increased and screen current decreesed by secondary electrons from the screen grid. The amount of secondary emission is largely dependent on the surface condition of the electrodes and usually varies widely in different tubes. Tetrodes are ordinarily not operated under conditions which pormit the plate voltage to fall below the screen grid voltage unless the design of the electrodes is such that scendary emission is largely eleminated. In beam power output tubes, which are tetrodes, the effects of secondary emission are largely eliminated and the characteristics resemble those of pentodes.


Because of the electrostatic shielding effect of the screen grid, the control grid to plate capacitance of tetrodes is very much lower than that of triodes. Tetrodes designed for use in high frequency stages usually contain additional shields placed outside of the electron stream in such a way that the grid to plate capacitance is still further reduced. This feature makes tetrodes more suitable than triodes for use in amplifying r-f or i-f frequencies where large grid to plate capacitances would tend to cause oscillation or instability. The high smplification factor and plate resistance of tetrodes permit high gain and selectivity with the tuned circuits cridinarily used at high frequencies. The high amplification factor also permits high gain in resistance coupled audio frequency amplifiers.

PENTODES The plate current vs. plate voltage curves of a pentode resemble those of a tetrode with the important exception that there is no abrupt dip in the curres at the point where the plate voltage equals the screen grid voltage. Refer to the plate characteristic curves of types 606, 42, etc., in the rating and characteristic data section for typical pentode curves. This improvement in characteristic sesults from the effect of the suppressor grid, #3 grid, which prevents the passage of secondary electrons between the plate and the screen grid. The plate current curves are flatter than in corresponding types of tetrodes, hence the plate resistance and amplification factor are correspondingly higher. Pentodes may be used for the same service as tetrodes and have the seme advantages of low grid to plate capacitance and high amplification factor and plate recistance. In addition, since the plate current curves are smooth over a wide range of plate voltage, pentodes can be operated as power amplifiers at large amplitudes of a-c voltage and current.

MIXER OR CONVERTER TUBES An important characteristic of a mixer or conwhich is equal to the quotient of the beat frequency, or 1-f, component of the plate current divided by the r-f signal voltage on the control grid, with no impedence in the plate circuit and constant d-c voltages on all the electrodes. In converter circuit calculations, conversion transconductance corresponds to transconductance in single frequency amplifier circuits. The TRANSLATION GAIN of a mixer stage is analogous to the voltage gain of an amplifier stage, and is the ratio of the 1-f output voltage appearing across the plate load impedance, to the r-f signal voltage applied to the control grid. Its value depends on the circuit constants as well as on the mixer tube characteristics and operating conditions. The CONVERSION PLATE RESISTANCE of a mixer tube is the effective plate resistance to the beat frequency, or 1-f, component of the plate current and corresponds to the plate resistance of an amplifier tube. A pentagrid converter tube is ordinarily operated as if it consisted of two sections, each having its own control grid, both grids simultaneously controlling the plate current in accordance with the separate grid voltages. The curves in Fig. 1 and Fig. 2 show the effect of the inner number 1 and the outer number 4 control grid voltages respectively on the plate current and on the current to grid number 2 which serves as the snode of the inner section. The negative relation between the voltage on the outer control gridand the anded current of the inner section, shown in Fig. 2, is typical of pentagrid tubes. Each section has the characteristics of amplification factor, plate resistance and transconductance, the values depending on the d-c voltages applied to the electrodes of both sections. sections.

TUNING INDICATORS For typical tuning indicator characteristic curves refer to the type GES in the rating and characteristic data section. The curve of shadow angle vs.grid bias is the most important as it shows the range of grid voltage necessary to completely control the pattern on the fluorescent target.






TUBE APPLICATION AND CIRCUITS

RECTIFIERS In the application of rectifier tubes care should be taken that the published maximum ratings are not exceeded. Rectifier tubes are rated for MAXIMUM A-C PLATE VOLTAGE, the maximum RMS value of a-c voltage that should be applied to the plate of the tube and for MAXIMUM D-C OUT-PUT CURRENT, the highest value of a-c plate current, averaged over one a-c cycle, at which the tube should be operated. They are also rated for MAXIMUM PRAK PLATE CURRENT, the maximum instantaneous peak value of plate current that should be permitted to flow through the tube and for MAXIMUM INVERSE PEAK VOLTAGE which is the maximum instantaneous peak value of plate voltage that should be applied to the tube during the half-cycle when the plate is negative and no current is flowing to the plate. THE VOLTAGE DROP venture read voltage which is the maximum instantaneous peak value of plate voltage that should be applied to the tube during the half-cycle when the plate is negative and no current is flowing to the plate. THE VOLTAGE DROP is the d-o plate voltage corresponding to some specified value of d-o plate current, usually equal to the maximum d-o output current per plate.

half-wave rectifier circuit A typical is shown in Fig. 3 and a typical full-wave rectifier circuit in Fig. 4. A condenser input filter is shown in each condensor input tiller a shown in con-circuit. If C1 were omitted the filter would be a choke input filter. With condensor input the d-c output voltage will be higher and the regulation over working range poorer the than choke input. Increasing the capacity of C1 will increase the d-c output voltage, but will also increase the peak plate current and the inverse peak volt-Some filter age applied to the tube. age applied to the tube. Some filter circuits employ two chokes in series, as shown in Fig. 4, to further reduce the hum voltage. In some cases the plate supply for the output stage is taken from the first choke and the rest of the tubes supplied through both chokes. This allows a smaller choke with a lower current rating to be used for Lg, and improves the regulation of the output voltage.

### TYPICAL HALF WAVE RECTIFIER CIRCUIT



### TYPICAL FULL WAVE RECTIFIER CIRCUIT





Fig. 5 shows a voltage doubler circuit such as is sometimes used in receivers operating directly from the a-c line without a power transformer. The doutput voltage will be somewhat less than twice the value which would be obtained with a half-wave rectifier. Its value depends on the capacity of condensers, Cl, and on the d-c output current, as shown by the curves for the 2525 tube.


AMPLIFTERS Two general types of amplifiers are used in radio receivers, high frequency amplifiers for radio and intermediate frequencies and low frequency amplifiers for audio frequencies. High frequency amplifiers are usually transformer coupled and may be used over a range of frequencies as in a tuned r-f receiver, or at a single frequency as in the 1-f amplifier of a


TYPICAL VOLTAGE DOUBLER CIRCUIT



quencies. High frequency amplifiers are usually transformer coupled and may be used over a range of frequencies as in a tuned r-f receiver, or at a single frequency as in the i-f amplifier of a superheterodyne receiver. Pentode or tetrode tubes are commonly used in high frequency as plifiers because of their low grid to plate capacitance and high values of transconductance and plate resistance. Fig.6 and Fig.7 show typical high frequency amplifier circuits such as are used in a tuned r-f receiver and in a superheterodyne receiver.


### TYPICAL TUNED R-F AMPLIFIER AND DETECTOR CIRCUIT






Low frequency amplifiers may be transformer coupled or resistance coupled. Transformer coupling is usually used with low-mu triodes and resistance coupling with high-mu triodes, tetrodes or pentodes. Fig. 8 shows a typical resistance coupled a-f amplifier stage using a triode and Fig. 9 shows a pentode resistance coupled a-f stage. The values of resistors and condensers used in these circuits may be found by referring to the Resistance Coupled Amplifier Design Curves on page 23.

### TYPICAL RESISTANCE COUPLED A-F AMPLIFIER CIRCUITS




An amplifier stage may use one tube, or two tubes connected in parallel or in push-pull. In a push-pull amplifier stage the two tubes are connected in such a way that the two grid circuits are effectively in series and the two plate circuits likewise. Equal signal voltages 100° out of phase, are amplied to the two grids by a center-tapped transformer or by a phase inverter circuit. The a-c plate currents and voltages are combined in the output circuit to give approximately twice the power output obtainable from a single tube operating under the same conditions, and the second and other even order harmonics cancel out. Fig. 10 shows a typical push-pull power amplifier stage transformer coupled to a driver stage. Transformer coupling is used where power is supplied to the push-pull grids as in Class AB or Class B operation. Either transformer or place inverter input may be used where the output stage requires no driving power.

### TYPICAL PUSH-PULL POWER AMPLIFIER-CLASS AB2



A PHASE INVERTER circuit is shown in Fig. 11. The signal voltage for triode R is obtained from the tap, P, on the resistor, Rg, in the output circuit of the other triode. This tap should be adjusted so that the signal voltage applied to triode R is equal to the input signal on the grid of triode L. For example, if the voltage gain of triode L is 25, the tap, P, should be adjusted to supply 1/25 of the voltage across Rg to the grid of triode R.



Amplifier stages are classified with respect to the tube operating conditions and the relation between the grid bias and the maximum normal value of a-c signal voltage, which determine the fraction of the a-c cycle during which plate current flows. In a CLASS A amplifier stage, the plate current flows during the complete a-c cycle, the grid bias usually being fixed at approximately one-healf of the cutoff bias (the grid bias necessary to reduce the plate current to practically zero). Ordinarily, the maximum normal peak value of the a-c voltage is approximately equal to the grid bias and no grid current flows during any portion of the cycle but this is not a necessary condition for Class A operation. The subscript I las in Class A. necessary condition for Class A operation. The subscript 1, as in Class Ap is sometimes used to indicate that no grid current flows during any part c the input cycle.

Fig. 12 shows the section of the plate current vs. plate voltage family of a triode operated as a CLASSA amplifier. The LOAD LINE represents the relation between the instantaneous values tion between the instantaneous values of grid voltage, plate voltage and plate current during a cycle at full rated signal level. Its slope is numerically equal to the reciprocal of the effective a-c impedance in the external plate circuit. Since this impedance is chiefly resistive, it is commonly referred to as the LOAD RESISTANCE, Rg. The operating point, 0, indicates the The operating point, 0, indicates the static values of plate voltage, Eq., and current, Iq, with no signal. The load line terminates at plate current curves corresponding to the maximum and minimum instantaneous values of grid voltage age at full rated signal, the swing in grid voltage being the same in either direction from the operating point, 0. The difference between the plate voltage at the operating point and at eithor end of the load line equals approximately the peak value of the a-c output voltage will be 0.707 times the peak voltage obtained from the curves. The power output may then be calculated

200 TYPICAL TRIODE PLATE CHAR 160 . A OPERATION 120 K RRENT-480

POWER OUTPUT = 
$$\frac{\left(\mathcal{E}_{RMS}\right)^{2}}{\mathcal{R}_{L}} = \frac{\left[0.707\left(\mathcal{E}_{max} - \mathcal{E}_{o}\right)\right]^{2}}{\mathcal{R}_{L}} = \frac{\left[0.707\left(\mathcal{E}_{o} - \mathcal{E}_{min}\right)\right]^{2}}{\mathcal{R}_{L}}$$
(2)

A more accurate formula which includes both halves of the cycle is:

$$POWER\ OUTPUT = \frac{(E_{max} - E_{min})(I_{max} - I_{min})}{8}$$
 (3)

The values of Emax, Emin, Imax, and Imin, are read from the curves as shown in Fig. 12. If the values of Emax, and Emin are expressed in volts, the values of  $I_{\rm max}$ , and  $I_{\rm min}$  should be expressed in amperes to give the power output in watts.

The second harmonic distortion, expressed in percent, may be calculated from the formula:

$$2\text{ND. HARMONIC} = \frac{I_{max} + I_{min}}{2} - I_{o} \times 100 \tag{4}$$

Io is the value of d-c plate current at the operating point and is read from the curves. All the values of current in equation (4) should be expressed in the same units, milliamperes or amperes. Fig. 13 shows typical variations of power output, plate current and harmonic distortion with signal input voltage for a triode operated as a Class A amplifier. The power output varies approximately as the square of the input voltage and the distortion is low and is chiefly second harmonic.

20

10

n

PLATE CURRENT-MA.

The PLATE EFFICIENCY is the percentage ratio of the power output to the product of the secrete d-c plate voltage and d-c plate current at full signal.

PLATE EFFICIENCY (%) = 
$$\frac{P0}{E_P I_P} \times 100$$

In a Class A triode smplifier the plate efficiency is relatively low, 15% to 25%.

(5)

The POWER SE SITIVITY is the ratio of the power output to the square of the input simply voltage,  $E_{\sigma \bullet}$ 

POWER SENSITIVITY = 
$$\frac{PO}{E_6^2}$$
 (6)


10

SIGNAL - RMS VOLTS

FIG. 13

The power sensitivity of a Class A triode amplifier is also relatively low.

The method of calculating the approximate power output and distortion for a pentode or a tetrode, operated as a Class A amplifier, is similar to that for triedes. Fir, 14 shows a family of plate characteristic curves for a typical perbode Class A amplifier. The power output may be calculated approximately from the formula:



$$PO = \frac{[I_{max}. I_{min} + 1.41(I_{x}.I_{y})]^{2} \frac{E_{max}. E_{min}}{I_{max}. I_{min}}}{32}$$
 (7)

The values are read from the curves at the points indicated in Fig. 14. The values of  $I_{\rm X}$  and  $I_{\rm Y}$  are determined by the intersections of the load line with the plate current curves corresponding to grid biases of 0.295  $E_{\rm ZO}$  and 1.707

the glate current curves corresponding to grid biases of 0.205 Ego and 1.707

Ego respectively, where Ego is the value of the grid bias at the operating point, 0.


The second harmonic distortion, expressed in percent, may be calculated from the formula:


$$2 \text{ND. HARMONIC} = \frac{I_{max} + I_{min} - 2I_o}{I_{max} - I_{min} + 1.4I(I_X - I_Y)} \times 100 \tag{8}$$

The third harmonic distortion, in percent, is given by the formula:

$$3RD. HARMONIC = \frac{I_{max} - I_{min} - 1.4I(I_X - I_Y)}{I_{max} - I_{min} + 1.4I(I_X - I_Y)} \times 100$$
 (9)


Fig. 15 shows the variation of power output, plate current, screen current and distortion with signal input voltage and Fig. 16 shows the variation of the same quantities with load resistance for a typical pentode class A Amplifier. A pentode is normally operated with a load resistance of approximately the value at which the second harmonic is a minimum. In some cases, the load resistance is adjusted for a lower value of third harmonic and the second harmonic is balancing amount of second harmonic in a preceding stage. Beam power tubes are frequently operated with lower values of load resistance than are pentodes to reduce the odd harmonic distortion. A Class A pentode amplifier generally has higher plate efficiency, 35% to 45%, and higher powers onesitivity than a Class A triode. The distortion is also generally higher and consists mostly of third and higher odd order harmonics.





In a chass B amplifier stage two tubes or the two sections of a twin tube are used in a push-pull circuit. The grid bias is fixed at approximately the cutoff value and plate current flows in each plate circuit on alternate half-cycles of signal voltage when the grid is positive. Since the grid of a class B tube is swinging positive during a considerable portion of the cycle, grid current usually flows for part of the cycle. This grid voltage In a CLASS B amplifier stage two tubes or the two sections of a twin tube

part of the cycle. This grid voltage and current represent power which must be supplied by the preceding tube called the DRIVER TUBE. The power output of the driver tube is often the limiting factor in determining the power output of a Class E stage. Since the average value of the plate current of a Class R stage varies considered by with a considered to the considered value of the plate current of a Class B stage varies considerably with signal voltage, the plate voltage supply should have good regulation to prevent excessive decrease in d-o plate voltage and limitation of output as the signal voltage are is relead age is raised.



TYPICAL TRIODE

PLATE CHAR

Fig. 17 shows the section of the plate current vs.plate voltage family of a tri-ode used as a Class B amplifier. In


ode used as a Class Bamplifier. In o Class B operation the plate current of one tube is practically cutoff during each alternate half-cycle and contributes very little to the power output. The power output from the two tubes may be calculated approximately from the plate family of one tube and is equal to the sum of the power outputs represented by the extensions of the load line on either side of the operating point of the contribution. point,0.

$$PO = \frac{(E_o - E_{min})(I_{max} - I_o)}{2} + \frac{(E_{max} - E_o)(I_o - I_{min})}{2}$$
(10)


Since the plate current of one tube is practically outoff during each alternate half-cycle, formula (10) may be reduced to a further approximation:

$$PO = \frac{(E_0 - E_{min.}) I_{max.}}{2} \qquad (II)$$

The actual power output is somewhat higher than that shown by these relations because of the effects of the third and other odd harmonics. Fig.18 shows typical variations of power output, plate current and distortion with signal input voltage for a class. A prolifical current and distortion with signal in-put voltage for a Class B Amplifier. The distortion is chiefly third and other odd harmonics. The plate effi-ciency, 50% to 65%, and the power sen-sitivity at full power output are both relatively high.



A CLASS AB amplifier stage is one which operates under conditions intermediate between Class A and Class B. The grid bias is fixed at a value between that between operation and outoff and Class A for plate current flows in each plate cir-cuit for less than one complete cycle but for more than one half-cycle of but for more than one half-cycle of the signal voltage. If the normal maximum peak value of the signal voltage does not exceed the grid bias and no grid current flows during any part of the input cycle, the amplifier may be designated as Class AB1. If grid current flows during any portion of the input cycle the amplifier may be designated as Class AB2, Fig. 19 shows the section of the plate voltage plate current family of a triode used as a Class AB2 Amplifier. The power output from two



family of a triode used as a class and 0 MV 200 MV 400 MV Amplifier. The power output from two tubes may be computed approximately from the plate family of one tube in the same manner as for Class B operation. The characteristics of power output, plate current, plate efficiency and plate current fluctuations with signal and driving power are intermediate between those of Class A and Class B operation. ation.

Power output pentodes or tetrodes may be used as Class B or Class AB Amplifiers, and the approximate power output may be computed from the plate current vs. plate voltage curves in the same way as in the case of triodes.


In a CLASS C amplifier the grid bias is fixed at a value greater than the cutoff value and the plate current flows during less than one half-cycle. Class C amplifiers are not used in radio receivers, although an OSCILLATOR may be considered as a special type of Class C amplifier in which the input voltage is derived from the output voltage by means of circuit coupling.


A CLASS BC amplifier stage is one which operates under conditions intermediate between Class B and Class C and is not used in radio receivers.


DETECTOR AND AUTOMATIC


Detectors are used in radio receivers

DETECTOR AND AUTOMATIC Detectors are used in radio receivers to separate VOLUME CONTROL CIRCUITS the audio frequency component of the modulated signal from the high frequency carrier or to change the carrier frequency. In superheterodyne receivers, the first detector is important characteristic of a detector tube is the relation between the r-f signal input voltage and the resultant a-f or i-f output voltage. This relation is shown for a typical diode in Fig. 20, for a triode operated as a grid leak detector in Fig. 21 and for a biased triode detector in Fig. 22.










In a grid leak detector circuit, Fig. 23, the r-f signal is rectified in the grid-cathode circuit which acts as a diode detector. The a-f voltage across the grid leak and condenser is amplified by the tube and the amplified voltage appears in the plate circuit. The r-f signal is also amplified by the tube and an r-f filter should be inserted in the output circuit to prevent the high frequency from reaching the a-f amplifier. Increasing the resistance of the grid leak increases the sensitivity to weak signals, but tends to introduce instability and distortion with large signals.


In a biased detector circuit, Fig. 24, a high negative bias is applied to the grid and the no-signal plate current is practically zero. The rectification practically zero. The rectificat takes place in the plate circuit due the fact that more plate current flows on the positive helf-cycles of the sig-nal voltage than on the negative half-cycles. Both a-f and r-f voltages apcycles. Both and and rel voltages appear in the plate circuit and an ref filter should be used to by-pass the ref component. A biased detector normally draws no grid current and there-fore does not decrease the sensitivity and selectivity of the input circuit

detectors are commonly used be-of their ready adaptation to de-Diode detectors are cause of their ready adaptation to detection and control circuits. A diode detector circuit, shown in Fig. 25, functions as a half-wave rectifier and the a-f voltage appears across the load resistor, R1, which is by-passed forr-f by condenser C1. The by-pass condenser C1 charges up to a voltage approximately equal to the peak voltage of the signal and maintains a d-o voltage proportional to the carrier amplifude across the load resistor, R1, Since diode detectors are operated at very small currents, the operating characteristics of all types are practically the same. cause

Automatic volume control, AVC, may be obtained by applying the d-c voltage developed across the diode load resistor, as a negative bias, to the control grids of the r-fandi-famplifier tubes in the receiver so that their gain increases or decreases as the r-f signal decreases or increases, A typical circuit is shown in Fig. 25. The filter Rg - Og is introduced to prevent the AVC voltage from varying at audio frequencies and to prevent high frequency voltage from being fed back to the r-f or i-f amplifier tubes.

### TYPICAL BIASED DETECTOR






In diede detector circuits certain precautions should be taken to insure linearity and low distortion with high percentage modulation. The r-f signal voltage applied to the diede should be approximately 10 volts, and the ratio of the a-c impedance to the d-c resistance in the diede circuit should be as high as possible. The a-c impedance is usually less than the d-c resistance in the diede circuit due to the shunting effect of the AVO network and the grid leak of the following audio amplifier tube. Therefore, the grid leak and AVO filter resistors should be as high as allowable in the grid circuits of the a-f and r-f amplifier tubes, and the diede lead resistor should not be too high. The a-o/d-c impedance ratio may be improved by feeding the a-f amplifier and the AVO network from a tap on the diede lead resistor, as shown in Fig. 7. While this connection reduces the sensitivity, it increases the a-o/d-o impedance ratio appreciably.

7. While this connection row impedance ratio appreciably. ano/d-o impedance ratio appreciably.
The r-f by-pass condenser across the diode load resistor should not be too large as this will cause loss of gain and distortion at the higher audio frequencies.


it is desirable for the cas**es** AVC action to be delayed until nal reaches a certain pred s a certain predetermined in order that the received the sigstrength, in order that the receiver may receive weak signals with maximum A circuit which accom-is called a delayed AVC, sensitivity.
plishes this or DAVC circuitand is shown in Fig. 86 Diode, Dr., is used as a detector t supply a-f voltage to the a-f ampli Diode, Dr., is used as a detector to supply a-f voltage to the a-f amplifier and diode, DR, is used to supply delayed AVC voltage. The amount of delay depends on the voltage on the cathode of DR. For example, if the cathode of DR is returned to a point 3 volts above ground, no current can flow through DR until the signal strength increases sufficiently to cause more than 3 volts R3, and the AVC action is delayed until the signal 3 volts peak.

TYPICAL DIODE DETECTOR CIRCUIT WITH DELAYED AVC



to be developed across R<sub>3</sub>, and one 3 volts peak. reaches approximately CONVERTER AND MIXER CIRCUITS In a superheterodyne receiver, a frequency converter stage is used to convert the incoming r-f signal to the i-f frequency. Two tubes may be used, one as the oscillator and the other as the mixer, or first detector, or both functions may be combined in a single converter tube such as a type 6A7 or a 6A9G. Fig. 27 shows a typical frequency converter circuit using a pentagrid mixer tube and a separate oscillator. A typical pentagrid converter circuit using a single tube is shown in the circuit of Fig. 7.

TYPICAL FREQUENCY CONVERTER CIRCUIT USING SEPARATE OSCILLATOR



volume EXPANDER CIRCUIT In the recording of phonograph records or in broadcasting, particularly of music having a large
volume range such as symphony orchestra selections, the volume range is compressed so that the soft passages are louder and the loud passages are softer than in the original music. This compression is necessary to keep the
soft passages above the background noise level of the equipment and to prevent the loud passages from overcutting the grooves on the record or over
modulating the carrier. More natural reproduction of such music may be obtained by the use of a volume expander amplifier which amplifies the loud
passages more than the soft passages and thus increases the volume range.
Fig. 28 shows a circuit for a volume expander amplifier using a type 6L7 or
6L7C pentagrid tube.

VOLUME EXPANDER CIRCUIT




FIG. 28

The operation of the circuit is as follows: The gain of the 6L7 audio amplifier depends on the bias on number 3 grid. The input signal is applied to the number 1 grid of the 6L7 and also to the grid of the 6C5. The amplified signal from the 6C5 is rectified by the 6H6 or 6H6G and the d-c output voltage applied, as a positive bias, to the number 3 grid of the 6L7 so that the gain increases and decreases with the amplitude of the signal. The position of tap, P, determines the initial bias on grid number 3 of the 6L7 and should be adjusted so that the no-signal plate current of the 6L7 is 0.15 milliamperes. The input signal on the grid of the 6L7 should not exceed one volt peak in order to prevent excessive distortion. If it is desired to delay the expander action until the input signal reaches a certain level, a negative bias may be applied to the plates of the 6H6 or 6H6G rectifier tubes.

AUTOMATIC FREQUENCY

CONTROL CIRCUITS

a superheterodyne receiver, is one which automatically controls the oscillator frequency in such a manner that the intermediate frequency is maintained at the frequency to which the i-f amplifter is tuned. Thus, a receiver equipped with AFC automatically corrects inaccuracies in manual tuning and compensates for oscillator drift. An AFC circuit consists of a frequency discriminator circuit and a control circuit. The discriminator detects changes in intermediate frequency and supplies above values, the polarity of which depends on the direction of the cuit. plies a d-c voltage, the polarity of which depends on the directi frequency change, to the control circuit which changes the oscill quency and returns the intermediate frequency to the proper value. depends on the direction of the ich changes the oscillator fre-

### FREQUENCY DISCRIMINATOR CIRCUIT FOR AFC.





Fig. 20 shows a frequency discriminator circuit. The primary,L1, is tuned to the intermediate frequency of the receiver and loosely coupled to the secondaries, L2 and L3, which are tuned to frequencies spaced equally above and below the intermediate frequency. The voltages across L2 and L5 are applied to a duo-diode rectifier as shown. The d-c output voltage of this rectifier is the AFC voltage and is equal to the difference between the voltages developed by each diode. When the i-f signal is on the center frequency the voltages applied to the diodes are equal, the d-c output voltages are equal and no resultant AFC voltage is developed. If the i-f frequency changes toward the resonant frequency of L2, more voltage will be applied to diode, DL, than to the other diode, DL will develop more a-c voltage than DR, and the resultant AFC voltage will be negative with respect to ground. In like resultant AFC voltage will be positive with respect to ground.



Another discriminator circuit which does not depend on side circuits, tuned above and below the intermediate frequency, for its operation is shown in Fig. 30. In this circuit the primary L<sub>1</sub>, and the secondary, L<sub>2</sub> are both tuned to the intermediate frequency of the receiver and are loosely coupled. The operation of the circuit depends on the fact that at the resonant frequency the primary voltage, E<sub>D</sub>, and the secondary voltage, E<sub>S</sub>, are 90° out of phase and on the fact that the phase angle varies as the frequency changes. The circuit is arranged so that the voltage, E<sub>L</sub>, applied to one diode is the vector sum of the primary voltage and one-half of the secondary voltage, and the voltage, E<sub>D</sub>, applied to the other diode is the vector sum of the primary voltage and the teller half of the secondary voltage. As in Fig. 29, the resultant AFC voltage is the difference between the d-c voltages developed by each diode. Vector diagram, A, in Fig. 30 shows the phase relations of the several voltages when the applied voltage is at the resonant frequency. Since the voltages when the applied voltage is at the resonant frequency. Since the voltages when the applied voltage is at the resonant frequency, Since the voltages when the applied voltage is at the voltages changes in frequency, the place relations may be as shown in vector diagram, B. The voltage, E<sub>D</sub>, applied to diode D<sub>R</sub>, will be greater than the voltage, E<sub>L</sub>, applied to the circuit and D<sub>L</sub> and the resultant AFC voltage will be positive with respect to ground. If the frequency changes in the opposite direction, E<sub>L</sub> will be greater than E<sub>L</sub> and the resultant AFC voltage will be negative with respect to ground.

### CONTROL CIRCUIT FOR AFC




Fig. 31 shows a control circuit which controls the oscillator frequency in accordance with the d-c voltage developed by the discriminator. The plate of the centrol tube is coupled to the oscillator tank coil and a voltage approximately 90° out of phase with the voltage across the tank coil is applied to the grid. In Fig. 31 this out of phase voltage is obtained from condenser, C1, which is in series with resistor, R1, across the tank coil. In practice the resistance of R1 is made much greator than the reactance of C1 and the current through C1 is practically in phase with the voltage across the tank coil. The voltage across C1 is therefore practically 90° out of phase with the tank coil voltage. The plate circuit of the control tube then acts like an inductance across the tank coil. The value of this effective inductance depends on the bias on the grid of the control tube. She the bias of the control tube is determined by the AFC voltage generated by the discriminator, the control tube tends to maintain the oscillator at the proper frequency.

### RECOMMENDED OPERATING PRACTICES

FILAMENT AND HEATER VOLTAGE

Radio receiving tubes are designed to operate satisfactorily with moderate variations in heater or filament voltage from the rated values. However, for best performance and life the rated values should be maintained as closely as possible. At excessively high values of heater or filament voltage there is danger of heating the first grid to the point where it emits a sufficient number of electrons to interfere with the proper functioning of the tube and in accoperated receivers the hum introduced from the acc heater supply is likely to be greatly increased. Furthermore, the rate of evaporation of active material from the cathode is greatly accelerated with corresponding reduction in tube life. At excessively low heater or filament voltages the electron emission from the cathode may be reduced to the point where the tube characteristics and the receiver performance are seriously affected. In the case of tubes in which a relatively large current is drawn from the cathode, particularly power amplifier and rectifier tubes, operation under such conditions is apt to result in serious damage to the tube and early

It is now standard practice to design a-c operated receivers for a line voltage of 117 volts and the filament and heater transformers should be designed to supply exactly the rated voltages to the heaters and filaments with this line voltage. If this is the case, the performance and life of the tubes will not be seriously affected by the normal fluctuations in line voltage, if these are not more than ten percent. The best practice is to have the receiver power transformer supplied with taps so that the voltages may be held within 5% of the normal value. When the filaments or heaters are operated in series the total voltage does not divide exactly equally among the various tube filaments or heaters due to small variations in heater resistance. In this case the bad effects of large variations in line voltage are exaggorated. It is important that receivers having the heaters connected in series be designed to supply exactly the rated value of current to the heaters or filaments at the standard line voltage of 117 volts.

The tubes used in automobile receivers are designed to give satisfactory life and performance with the heater voltage fluctuating between 5.5 and 8.0 volts as in normal automobile operation and the connections should be arranged to maintain the heater voltage at all times within this range.

In home receivers where the heater or filament current is supplied directly from two-volt or six-volt storage batteries the variation in filament voltage will normally not be excessive. However, precautions should be taken against excessive voltage drop in the filament supply connections and against abnormal battery voltages such as might occur during battery charging or when the battery is discharged.

For best results, the filament voltage applied to two-volt tubes should be within the range of 1.5 to 2.2 volts. Operation at a voltage of 2.3 volts for a short period is permissible. The tubes are generally operative at voltages as low as 1.7 volts but with reduced sensitivity and output.

The two-volt-tube receivers designed for use with aircells are equipped with the proper series resistor for maintaining the suitable range during the life of the battery. With many two-volt-tube receivers for use with three-volt dry batteries or dry packs there are provided ballast tubes which tend to hold the filament current at the proper value. It is essential that these ballast tubes be rated for the same value of current as the total filament current of the receivers with which they are used. As the characteristics of the ballast tube are apt to undergo a permanent change during life, it is advisable to replace it whenever the filament battery is replaced.

Some two-volt-tube receivers now employ a type of resistor tube which may be used with a storage battery, aircell or drycell supply. (See "KB" resistor tubes at end of rating and characteristic data section).

Some two-volt-tube receivers are designed to operate with the filament voltage supplied directly from a 4.5 volt dry battery or dry pack, the two-volt tubes being used in pairs with the filaments in series. The range of filament voltage is somewhat greater in this case than in the preceding case but better battery economy is obtained.

TUBE MOUNTING The common and safest practice is to meant tubes in a vertical position. However, it is also generally permissible to mount them in a horizontal position. When filament type tubes are mounted horizontally they should be turned so that the plane of the filament is vertical, to avoid the chance of the filament sagging sufficiently to touch the grid or the plate.

Provision should be made for free circulation of air around the tubes. This applies particularly to the rectifier and power output tubes which must dissipte considerable power. Too close confinement increases the chance of grid emission or loss of vacuum due to electrolysis of the glass between the sealed in leads at high glass temperatures.

Modern tubes, particularly those of the heater type, are capable of withstanding relatively severe vibration for short periods without damage. If they are subjected to severe vibration continuously a gradual wearing away of the insulated heater coating or of the mica spacer is liable to occur and premature failure of the tube may result. Where the receiver is likely to be subjected to severe vibration a cushioned mounting should be provided for the receiver chassis and means should be employed to prevent or damp out resonant vibrations of the chassis and tubes.

MICROPHONICS Microphonic howling, when due to a tube, is caused by mechanical feedback from the speaker to the tube either through the air or through the chassis. Tubes which are followed by high audio frequency gain are most susceptible. Heater type tubes are much less microphonic then filament types and ordinarily give no trouble except under extense conditions. In filament types, particularly the two-volt types, the filament may be set into vibration at its resonant frequency by extremely small impulses of the same frequency. In present day tubes improved methods of filament support are used to reduce this tendency and to camp out oscillations of the filament, but if the audio frequency gain in the receiver is high, special precautions must be taken in the receiver reduce mechanical feedback. The most sensitive tube should not be mounted close to the speaker; the speaker should not be rigidly connected to cabinet or chassis; the chassis should have a cushioned mounting in the cabinet and resonant vibrations in the chassis should be avoided or damped out.

Ordinary precautions against tube microphonics are usually sufficient for audio frequency gains up to about 100 db. with heater type tubes and up to about 50 db. with two-volt tubes. Gains exceeding these values usually require special precautions against tube microphonics and hum. Hicrophonic troubles may originate in the converter or even in the 1-f amplifier tubes through audio frequency modulation of the carrier or of the 1-f frequency, even when the gain in the audio frequency stages, is not especially high. Similar precautions should be used to avoid this type of microphonic effect.

HUM In modern a-c operated receivers filament type tubes are used only as plate-supply rectifiers or as output tubes. Filters are provided to eliminate the hum voltage developed in the rectifier section by the a-c supply. The voltage gain in the output stage is usually low and the hum is not noticeable if the simple precautions are taken of connecting the grid and plate return leads to the mid-point of the filament transformer secondary and of having this point well by-passed to the chassis. The heater type tubes used in all the other positions are so designed that, under favorable circuit conditions, only very small hum voltages are introduced into the audio and radio frequency directive by the a-c heater voltage and current. For minimum hum the ground connection to the heaters should be made to the center point of the heater winding. If hum is present, it is usually caused by improper filtering or is introduced by some circuit element other than the tubes.

However, under some conditions, a troublesome amount of hum may originate in the tubes. The second detector tube or the first audio amplifier tube is most likely to give trouble because it is followed by the maximum audio gain, Hum may also originate in the mixer or in the 1-f amplifier tubes, due to 60 cycle modulation of the r-f or i-f carrier.

The most common cause of hum in a tube is a minute leakage current between the heater and the cathode, which by flowing through some high resistance circuit element, such as the cathode resistor, develops a small voltage which is amplified by the succeeding audio frequency stages. To reduce hum from this source the cathode resistor should be by-passed and the cathode should be made negative with respect to the heater.

Other circuit precautions include the proper shielding of the tubes and component parts to prevent both electrostatic and electromagnetic coupling between them, and the arrangement of the wiring in such a way that leads followed by high audio frequency gains are not looped around the filament supply wires and are kept as far as possible from any leads carrying alternating currents.

Hum is sometimes introduced by the direct action of a strong 60 cycle magnetic field on the tubes. This occurs when the tubes are placed too close to the power transformer or the filter choke and the chassis should be laid out to avoid this possibility.

GRID CIRCUIT RESISTORS In present day receivers grid circuit resistors of relatively high values are commonly used, for instance, in resistance coupled amplifier stages, in the diode detector stage and in automatic volume control and other automatic control networks. As a result, a grid current of as little as a few microamperes may cause serious reduction in the grid bias due to the voltage drop in these resistors. This condition may lead to reduced sensitivity, instability or even to serious overheating and damage to the tubes or other circuit elements. Circuits in which a common resistor is inserted in the grid return lead of two or more tubes are particularly susceptible to loss of bias due to grid current.

The tubes are always checked for grid current during final testing in the factory and are held to a limit of not more than one or two microamperes. The average value is a small fraction of a microampere. However, when a tube The average value is a small fraction of a microsupere, However, when a tube is operated in a receiver, a higher value of grid current may appear due to a minute evolution of gas from the perts or to a minute amount of erretic electrical leakage across on inculator or to a small amount of thermal electron emission from the grid. The grid current due to gas usually tends to decrease rapidly as the receiver is operated. The current due to grid emission appears only after the tube has become heated to its maximum operating temperature and is aggravated by any conditions tending to overheat tube, such as insufficient prevision for air circulation, high line voltage, excessive plate voltage or insufficient grid bias.

The best pressution against trouble from this source is the avoidance of circuits which depend for their operation on extremely high values of grid resistors. A second pressution is to obtain the grid bine by means of the voltage drop in a cathodo, or self-bias, resistor rather than to use a fixed bias. With self-bias any tendency toward the loss of bias due to grid current is partially compensated for by an increase in the self-bias because of the resultant increase in plate current. A further precaution is the avoidance of encessive plate and screen grid voltages and currents by making sure that the tubes are operated well within their maximum ratings even at the highest line voltages. A fair amount of regulation in the screen and plate voltage supplies is also helpful in this respect.

As a general rule, the grid resistor for a single tube, exclusive of the output tube, should not erosed three megonms and a maximum of one megonm woul be preferable. Where a resistor is comman to the grid circuit of two or here tubes the value of the resistor should not exceed these values divided by the number of tubes whose grid current flows through it. The above rule applies in the case of self-bias.

In the case of fixed-bias, the maximum value of the grid resistor never erosed one regolm and this value should be reduced in inverse proportion to the number of tubes for whose grid current it forms a path. In applying these rules it should be noted that they refer to the total resistance in the grid circuit including the sum of all series resistors such as are used in some control circuits.

In the case of output tubes, a maximum value for the grid resistor is commonly givon with the tube rating. In general, a value of one megohm is the maximum safe value for tubes of low output ratings up to 3 or 4 watts and 1/10 to 1/4 megohm for tubes of higher output ratings.


PRECAUTIONS AGAINST BLOCKING DUE TO SECONDARY EMISSION When a sufficient-

due to the resultant excessive plate current.

PREGAUTIONS AGAINST ELOCATING DUE TO SECONDARY EMISSION When a sufficiently high positive
voltage is applied momentarily to a control grid there is an emission of
secondary electrons from this grid to the screen grid or to the plate. Under some conditions this current may exceed the flow of electrons from the
cathode to the control grid so that there is a net flow of electrons into
the grid through the external grid circuit. If this circuit includes a very
high resistance the resultant voltage drop may be sufficient to maintain
the grid at a positive motential in spite of an externally applied negative
crid blas. When the grid becomes "locked" positive in this manner the tube
is blocked and incorpative and may be permanently damaged by overheating
due to the regulation excessive miste our ent.


In most tubes the secondary emission characteristic of the control grid is low enough so that this trouble will occur only under abnormal conditions. A frequent cause of trouble is a defective wave change switch that applies a high positive d-c voltage to the grid momentarily during switching. Surges sufficiently high may reach the r-f amplifier tubes or the converter tube to cause blocking under certain circuit conditions. Sufficient surge is also sometimes developed in the output tube, when the set is turned on, to cause blocking under had circuit conditions. cause blocking under bad circuit conditions.

To avoid trouble of this kindit is advisable to use as low values of resistance as is possible in the grid circuits of the tubes that may be subjected to surge, particularly the tubes mentioned above. The switches should be designed and adjusted to reduce grid current surges to a minimum. The circuits should be arranged to provide high damping for surges. This can frequently be accomplished by taking advantage of the damping effect of the grid current flow when a grid is thrown slightly positive. This alone will protect a tube against small surges.



Added damping for an r-f amplifier or a converter tube may be obtained by coupling its grid circuit to the grid circuit of an i-f amplifier tube, as shown in Fig. 32, so that a surge reaching the grid of the r-f amplifier or the converter tube is partially dissipated by causing grid current to flow in the i-f amplifier tube.

It is also possible to connect a diode to the r-f amplifier or converter tube grid circuit in such a way that a surge will be diesepated by causing current to flow through the diode. Fig. 33 shows a diode connected to the grid circuit of a converter tube to prevent blocking due to secondary emission.



### CONVERSION CURVES

The following curves, Figs. 34, 35 and 36, may be used to find the approximate operating conditions for power amplifier triodes, tetrodes and pentodes at other than the published operating conditions.

Fig. 34 should be used for triodes operated at other than the published plate voltage and for tetrodes and pentodes operated at other than the published plate and screen voltages. For example, suppose it is desired to operate a pentode power amplifier at a plate and screen voltage 20% lower than the published values. The percent change from the published operating conditions may be read at the intersections of the curves with the -20% ordinate. Thus, for a 20% decrease in plate and screen voltages, the grid bias should be decreased 20% or the bias resistor increased 12%, the load resistance should be increased 12%, the plate and screen current will be decreased 27% and the power output will decrease 40%. Values for triodes may be determined from the curves in the same manner.




Fig. 35 should be used for tetrodes and pentodes where only the plate voltage is changed and the values are read from the curves in the same way as in Fig. 34.





Fig. 36 should be used for tetrodes and pentodes where only the screen voltage is changed and the values are read from the curves as in the previous figures. Tetrodes and pentodes should not be operated with the screen voltage appreciably higher than the plate voltage.

When choosing new operating conditions for any tube the published maximum ratings should not be exceeded.



### RESISTANCE-COUPLED AMPLIFIER DESIGN CURVES

The curves in Figs.38 to 43 give circuit design data for use with the heater type tubes commonly used in resistance-coupled amplifiers. The curves show the proper value of cathode resistor,  $R_0$ , for use with several values of plate resistor,  $R_1$ , at plate supply voltages from 90 to 300 volts. The values of output voltage,  $R_0$ , (peak volts) at maximum signal and the voltage gain, VG, are also shown by the curves.

Typical circuit diagrams for triode and pentode resistance coupled amplifiers may be found on page 11.

The value of the coupling condenser,C, depends on the value of  $R_g$ , the grid resistor for the following tube and for approximately 75 percent of the high frequency response at 60 cycles the value will be:

$$C = \frac{0.003}{R_{\odot}} \qquad C = \mu f \qquad R_{\rm G} = MEGOHMS$$

The curves were plotted using a value of  $R_{\rm g}$  = 2  $R_{\rm L}$  in all cases.

For the condition,  $R_g = R_L$ , creaped 15%. the value of Ro from the curves should be de-

For the condition, Rg = 4 RL, the value of Rc from the curves should be increased 10%.

The value of  $R_{\rm g}$  should not exceed the maximum value allowable in the grid circuit of the following tube.

may be found from


The proper value for the cathode by-pass condenser,  $\mathbf{C}_0$  , the relation:


$$C_c = \frac{7000}{R_c}$$
  $C_c = \mu f$   $R_c = 0 HMS$ 

The value of the screen by-pass condenser should be at least 0.05 to 0.1 uf.

In phase inverter circuits, such as the one shown in Fig. 11 on page 12, where a common cathode resistor is used the value of the resistor should be one-half that read from the curves for a single tube and the cathode by-pass condenser should be omitted.

The curves in Figs.44, 45 and 46 apply to two-volt tubes and are similar to those in the previous figures, except that values of grid bias instead of cathode resistor are shown.





### TUBE TESTING

All tubes are put through a mechanical and electrical test in the factory as one of the last operations. They are individually checked for such items as short circuits, open circuits, grid current, electron emission from the cathode, tube noise and certain operating characteristics such as plate current, transconductance or power output. The original design has previously been completely tested for all important operating characteristics. The individual factory tests insure that each tube is of good quality so far as factory processing is concerned and that it conforms to the original design within standard tolerances, as indicated by one or more key characteristics. At frequent, regular intervals sample tubes are selected at random from the production and are tested in the laboratory for all important characteristics. Random samples of regular production tubes are also life tested at approximately maximum rated voltages and the characteristics are measured after various periods of operation to determine the quality and the degree of constancy of the characteristics during life.

The test equipment required for this factory and laboratory testing is elaborate and expensive and one test set can readily accommodate only a few tube types out of the two hundred that are now on the market. Obviously, it is neither practical nor necessary, for the tube dealer or even for the set menufacturer to make as complete a test of tubes as is done by the tube manufacturer. However, a small percentage of defects develop during shipment and handling and most dealers find it advantageous to check each tube, when sold, as an insurance that it is operative and to check the condition of tubes that have been in service. Various types of relatively simple tube testing equipment have been developed for the dealer's use. In most cases this simple equipment will not give an accurate measurement of a tube's operating characteristics or of its ability to perform satisfactorily in any particular receiver. The simplest will at least tell whether or not a tube is operative, and the more elaborate will give an approximate indication of the value of some major characteristic.


Since a radio tube cannot perform properly without a copious supply of electrons from the cathode, a test that will measure or at least give a comparative indication of the electron emission can be used as a rough check on the operating condition of a tube and of its ability to perform up to the normal standard for its type. In the common form of emission type tube checker a fixed value of a-c voltage is applied between the cathode and the nearest grid (usually with the other elements connected to this grid)through a fixed resistor and a d-c ourrent indicating meter. Provisions are, of course, made for applying rated heater or filament voltage to the tube and for making the proper electrode connections for each tube type. In addition, facilities are often included for testing for short circuits, open filaments and often for electrical leakage between the elements.

The Radio Manufacturer's Association has recommended, in the interests of standardization, certain values of circuit constants that should be used in this type of tube checking equipment. The RMA recommends that tubes be tested under the following conditions:

- 1. Rated Filament or Heater Voltage
- 2. Fixed Emission Voltage of 30 volts
- Total effective series impedance of testing circuits should be varied as follows:
  - (a) High value for diodes, exclusive of power rectifiers 5000 ohms
  - (b) Medium value for battery tubes of limited emission-1000 ohms
  - (c) Low value for remaining types 200 ohms
- 4. A pointer type of indicating meter is recommended as the most reliable device for indicating tube characteristics.
- The regulation of the system should not exceed ± 5% with the range of loads for which the tester is designed.
- 6. The short circuit or leakage test circuit should not respond to a resistance greater than 250,000 chms.
- The RMA recommended circuit is shown in Fig. 47.

To establish limits for an emission type tube tester it is necessary to read a number of tubes of each type to be tested, and determine the average readings for good tubes of each type. Due to minor differences in design, tubes of the same type but of different manufacture may give different readings in tube testers, and still perform equally well in a receiver. In general, the end of the useful life of power amplifier tubes is indicated by a reading 50% below the average for good tubes of the same type, and of voltage amplifier tubes and rectifier tubes by readings 35% and 20% below average respectively.

Other types of tube checkers are designed to give a rough check on some other tube operating characteristic, such as plate current, transconductance or power output. Accurate Measurement of these characteristics requires sensitive measuring equipment and accurately measured element voltages for a large range and variety of test conditions and tube connections. All of these Items are increasingly expensive to obtain as the degree of accuracy is increased.



TYPE NO.	STRUCTURE	CATHODE	USE
00A 01A 0Z4 0Z4G	Triode Triode Twin Diode Twin Diode	5.0 volt Filament 5.0 volt Filament Cold Cold	
1A4 1A6 1B4/951 1B5/255 1C6 1C7G 1D5G 1D7G 1E50 1E7G 1F4 1F6 1F6 1F7G 1G5G 1H4G 1H5G 1J5G 1J6G	Tetrode Heptode Pentode Duo-Diode Triode Heptode Heptode Heptode Heptode Heptode Pentode Pentode Pentode Pentode Pentode Pentode Puo-Diode Pentode Duo-Diode Pentode Triode Duo-Diode Triode Pentode Triode Triode Triode Triode Twin Triode Diode	2.0 volt Filament 3.0 volt Filament 4.0 volt Filament 5.0 volt Filament 6.3 volt Filament	Frequency Converte Detector or Amplifie Detector Amplifie Frequency Converte: Frequency Converte: Frequency Converte: Detector or Amplifie Power Amplifie Power Amplifie Detector Amplifie
2A3 2A3H 2A5 2A6 2A7 2B7	Triode Triode Pentode Duo-Diode Triode Heptode Duo-Diode Pentode	2.5 volt Filament 2.5 volt Heater 2.5 volt Heater 2.5 volt Heater 2.5 volt Heater 2.5 volt Heater	Power Amplifie Power Amplifie Power Amplifie Detector Amplifie Frequency Converte Detector Amplifie
5T 4 5U 4G 5V 4G 5W 4 5W 4G 5X 4G 5Y 3G 5Y 3G 5Y 3G 5Z 3	Twin Diode	5.0 volt Filament 5.0 volt Filament	Full Wave Rectifier
6A3/LA 6A4/LA 6A5G 6A6 6A7 6A8 6A86 6A85 6A65G 6B60 6B7 6B8G 6C5G 6C6 6C6G 6C6G 6C6G 6C6G 6C7 6F6G 6F7 6F6G 6F7 6F6G 6F7	Triode Pentode Triode Triode Triode Triode Heptode Heptode Heptode Leptode Cathode Ray Triode Triode Duo-Diode Pentode Duo-Diode Pentode Duo-Diode Pentode Triode Triode Triode Triode Triode Triode Triode Triode Pentode Los Pentode Triode Triode Triode Triode Triode Pentode Triode Pentode Triode Pentode	6.5 volt Filament 6.3 volt Filament 6.3 volt Heater 6.5 volt Filament 6.5 volt Heater 6.6 volt Heater 6.7 volt Heater 6.8 volt Heater 6.9 volt Heater 6.9 volt Heater 6.9 volt Heater 6.9 volt Heater	Power Amplifier Power Amplifier Power Amplifier Power Amplifier Power Amplifier Frequency Converter Frequency Converter Frequency Converter Frequency Converter Tuning Indicator Power Amplifier Power Amplifier Detector Amplifier Detector Amplifier Detector Amplifier Detector or Amplifier Detector or Amplifier Detector or Amplifier Frequency Converter Tuning Indicator Fower Amplifier Amplifier or Phase Inverter Amplifier Power Amplifier Amplifier Amplifier Amplifier Power Amplifier Amplifier Power Amplifier Amplifier Power Amplifier Frequency Converter Detector Amplifier Tuning Indicator Power Amplifier Amplifier Amplifier Amplifier Amplifier Potector or Amplifier Power Amplifier Amplifier Amplifier Power Amplifier Remote Cutoff Amplifier
6L5G 6L6 6L6G 6L7 6L7G	Triode Tetrode Tetrode Heptode Heptode	6.3 volt Heater 6.3 volt Heater 6.3 volt Heater 6.3 volt Heater 6.3 volt Heater	Detector or Amplifier Power Amplifier Power Amplifier Mixer or Amplifier Mixer or Amplifier


6N5 6N6G 6N6MG 6N7 6N7G 6P7G 6Q7 6Q7 6Q7 6E75 6E75 6E76/6Q6G 6U5 6U76 6V6 6V6 6V6 6V7G 6W5G 6X5 6X5G 6X5G 6Y7G 6Z7G 6Z7G 6Z7G	Cathode Ray Duo-Triode Duo-Triode Twin Triode Twin Triode Trin Triode Trinde Pentode Duo-Diode Triode Duo-Diode Triode Duo-Diode Triode Duo-Diode Triode Pentode Cathode Ray Duo-Diode Triode Pentode Tetrode Tetrode Tetrode Tetrode Tetrode Tetrode Twin Diode Twin Diode Twin Diode Twin Diode Twin Triode Twin Triode Twin Triode Twin Triode Twin Triode Twin Triode Twin Diode	3.3 volt Heater 6.3 volt Heater	Tuning Indicator Power Amplifier Fower Amplifier Power Amplifier Power Amplifier Power Amplifier Amplifier or Converter Detector Amplifier Detector Amplifier Detector Amplifier Tuning Indicator Detector Amplifier Tuning Indicator Remote Cutoff Amplifier Funning Indicator Power Amplifier Power Amplifier Power Amplifier Full Wave Rectifier Full Wave Rectifier Full Wave Rectifier Power Amplifier Power Amplifier Fower Amplifier Full Wave Rectifier Full Wave Rectifier Full Wave Rectifier Full Wave Rectifier Fower Amplifier Power Amplifier Fower Amplifier Fower Amplifier Fower Amplifier Full Wave Rectifier
10 12A 12A5 12A7 12Z3 15 19 20 22 24A	Triode Triode Pentode Pentode Diode Pentode Diode Pentode Twin Triode Triode Tetrode Tetrode	7.5 volt Filament 5.0 volt Filament 12.6/6.3 v. Heate 12.6 volt Heater 2.6 volt Heater 2.0 volt Filament 3.3 volt Filament 3.3 volt Filament 2.5 volt Heater	Detector or Amplifier r Power Amplifier Rectifier Power Amplifier Half Wave Rectifier Amplifier
25A6 25A6G 25A7G 25B6G 25L6 25L6G 25Z5 25Z6 25Z6	Pentode Pentode Diode Pentode Pentode Tetrode Tetrode Twin Diode Twin Diode Twin Diode	25 volt Heater 25 volt Heater 26 volt Heater	Power Amplifier Power Amplifier Rectifier Power Amplifier Power Amplifier Power Amplifier Power Amplifier Rectifier Voltage Doubler Rectifier Voltage Doubler Rectifier Voltage Doubler
59 71A 75 76 77 78 79 80 81 82 83 83V	Triode Triode Triode Triode Triode Triode Triode Pentode Pentode Pentode Tetrode Tetrode Tetrode Triode Pentode Pentode Pentode Pentode Pentode Pentode Pentode Pentode Triode Dual Grid Triode Dual Grid Triode Dual Grid Triode Triode Dual Grid Triode Triode Dual Grid Triode Triode Triode Dual Grid Triode Triode Triode Triode Triode Triode Pentode Triode Pentode Triode Pentode Triode Pentode Triode Twin Diode Twin Diode Twin Diode Twin Diode Twin Diode Twin Diode Triode Pentode	1.5 volt Filament 2.5 volt Heater 2.0 volt Filament 2.5 volt Heater 6.3 volt Heater 2.5 volt Filament 3.5 volt Filament 7.5 volt Filament 7.5 volt Filament 7.5 volt Filament 2.5 volt Heater 3.0 volt Heater 6.3 volt Heater 6.3 volt Heater 6.3 volt Heater 6.3 volt Filament 5.0 volt Filament 5.0 volt Filament 5.0 volt Filament 5.0 volt Filament 6.3 volt Heater	Detector or Amplifier Detector or Amplifier Power Amplifier Detector or Amplifier Power Amplifier Remote Cutoff Amplifier Remote Cutoff Amplifier Detector or Amplifier Detector or Amplifier Power Amplifier Remote Cutoff Amplifier Amplifier Amplifier Power Amplifier Amplifier Power Amplifier

950 BA BH	Pentode Twin Diode Twin Diode Diode	2.0 volt Filament Cold Cold Cold	Power Amplifier Full Wave Rectifier Full Wave Rectifier Half Wave Rectifier
BR WD-11	Triode	1.1 volt Filament	Detector or Amplifier
WX-12 V-99	Triode Triode	<pre>1.1 volt Filament 3.3 volt Filament</pre>	Detector or Amplifier Detector or Amplifier
X-99	Triode	3.3 volt Filament	Detector or Amplifier

Individual tube data sheets are arranged in the same numerical order as in the above listing.

### RAYTHEON SPECIAL RECEIVING TUBES (Supplied for Replacement Use Only)

TYPE NO.		NT AMP	BASI		SHIELD CONNECTED TO	CHARACTERISTICS USE & DIMENSIONS
2A7S 2	.5	1.0	Same a	as 2A7	Cathode Pin	Same as 2A7
<b>2E</b> 5 2	.5	8,0	Same a	as 6E5	No Shield	Same as 6E5 Except Filament Rating
28/48 2	.5	1.35	Same a	as 84/6Z4	Cathode Pin	Approx.40 ma per plate at 50 volts d-c. Duo-Diode Detector,4 3/16"xl 9/16"
2Z2/G84 2	.5	1.5	Same :	as 81	No Shield	Similar to 1-V
6A7S 6	.3	0.3	Same a	as 6A7	Cathode Pin	Same as 6A7
<b>6B7S</b> 6	.3	0.3	Same a	as 6B7	Cathode Pin	Same as 6B7
607 6	.3	0.3	See Be	elow	Separate Pin	Same as 85AS
<b>6D7</b> 6	.3 (	0.3	See Be	low	Separate Pin	Same as 606
<b>6E</b> 7 6	.3 (	0.3	See Be	elow .	Separate Pin	Same as 6D6
6F7S 6	.5 (	0.3	Same a	as 6F7	Cathode Pin	Same as 6F7
<b>6</b> ¥ <b>5</b> 6	.3	8.0	See Be	low	Separate Pin	Similar to 84/6Z4
6 <b>Z</b> 5 1		0.4	See Be	elow	No Shield	Similar to 84/6Z4
248 2	.5	1.75	Same (	as 24A	Cathode Pin	Same as 24A
278 2	.5	1.75	Same a	as 27	Cathode Pin	Same as 27
<b>35</b> 8/518 2	.5	1.75	Same a	as 35/5 <b>1</b>	Cathode Pin	Same as 35/51
558 2	.5	1.0	Same :	as 55	Cathode Pin	Same as 55
568 2	.5	1.0	Same :	as 56	Cathode Pin	Same as 56
56-AS 6	.3	0.3	Same :	as 76	Cathode Pin	Same as 76
57 <b>S</b> 2	.5	1.0	Same a	as 5 <b>7</b>	Cathode Pin	Same as 57
57-AS 6	.3	0.4	Same s	as 606	Cathode Pin	Same as 6C6 Except Heater Amps.
58 <b>S</b> 2	.5	1.0	Same s	as 58	Cathode Pin	Same as 58
58-AS 6	.3	0.4	Same e	as 6D6	Cathode Pin	Same as 6D6 Except Heater Amps.
<b>75S</b> 6	.3	0.3	Same :	as 75	Cathode Pin	Same as 75
8 <b>5-AS</b> 6	.3	0.3	Same :	as 85	Heater Pin Adjacent to Cathode Pin	Similar to 85 Except $M\mu=20;G_{m}=1250;I_{p}=5.5 \text{ ma};$ $E_{p}=250 \text{ v. } E_{g}=-9 \text{ v.}$
182B 5 482B	.0	1.25	Same a	as 45	No Shield	Similar to 45 Except Filament Rating;Mµ=5; G <sub>m</sub> =1500;I <sub>p</sub> =18ma;E <sub>p</sub> =250v; E <sub>g</sub> = -35 v.
183 5 483	i.o :	1,25	Same :	as <b>4</b> 5	No Shield	Similar to 45 Except Filament Rating; M $\mu$ =3; $G_m$ =1500; $I_p$ =20 ma; $E_p$ =250v; $E_g$ = -58 v.
485 3	i.o :	1.25	Same :	as 27	No Shield	Similar to 27 Except Heater Rating; Mu=12.8; $G_m=1300; I_p=5.2$ ma; $E_p=180$ v; $E_g=-10$ v.



BOTTOM VIEWS OF SOCKETS

### INTERCHANGEABLE TUBE TYPES

Raytheon tubes can be used as replacements for tubes of other manufacturers as follows:

- A Tube types having the same RiA type numbers (with a letter, or two letters, between two numbers, as 6A7 or 6ZYSG) are interchangeable.
- On standard tube types with two or three figure type numbers, the last two figures form the significant type numbers regardless of letter prefixes. For example, the Raytheon 45 will replace the UX-245, CX-345, or SX-245 tubes.
- Types differing in number by the suffix letters "A", "G", "H", "MG" or "V are interchangeable in general regardless of this letter. For example the 12A may replace a 112 or 112A, the 2A3 may replace a 2A3M, and a 6A8 may replace a 6A8 or 6A6MG. "MG" or "V"
- Tubes with octal bases and standard size glass bulbs are designated by the suffix, "G" on the type number, as 6A8G. Tubes with octal bases, glass bulbs and attached metal shields are designated by the suffix "MG" on the type number, as 6A8G. Tubes with octal bases and metal bulbs have no suffix on the type number, as 6A8. "G" type tubes having type glass bulbs and attached metal shields are designated by the suffix "MG" on the type number, as 6A8MG. Tubes with octal bases and metal bulbs have no suffix on the type number, as 6A8. "G" type tubes having type numbers corresponding to metal tube or "MG" type numbers have, in general the same electrical characteristics excepting capacitances, and are usually interchangeable with the corresponding metal or "MG" types except for space requirements and the possible requirement of external tube shields.
- Shielded types distinguished by the added letter "S" interchangeable with types without this letter suffix. added letter "S" may or may not be
- Exceptions to the above tubes are types, D-1, DE-1, RE-1, SO-1, RE-2, SO-2, KR-20, KR-22, KR-22, KR-22, KR-23, KR-30, 59B, G-84, 182B, 183, Kellogg 401, 482A, 482B, 494, 484A, and 2525MG, which do not correspond with types 1-V, 20, 22, etc. The OlA (201A) is not interchangeable with the 1-V, cr 1, and the WX-12 is not interchangeable with the 12A (112A). Types 57AS, 58AS, 485 and 950 may be replaced only by Raytheon tubes bearing Exceptions to the above 1-V, 20, 22, etc. The 0 or 1, and the WX-12 is no 57AS, 58AS, 485 and 950 m the same full type number.
- The following table lists the obsolete and non-standard tube the Raytheon types which normally may be used for replacement. and non-standard tube types with

TYPE	NORMALLY	TYPE	NORMALLY	TYPE	NORMALLY
NO.	REPLACEABLE BY RAYTHEON TYPE	NO.	REPLACEABLE BY RAYTHEON TYPE	NO.	REPLACEABLE BY RAYTHEON TYPE
00	OOA	25Z5MG	25Z6G	210	10
01	Ola	25Z6MG	25Z6G	213	80
OLAA	Ola	27-HM	56	216	81
D-1/2	81	KR-28	8 <b>4/</b> 6 <b>Z4</b>	216B	81
_ 1	1-V	35	35/51	220	20
D-1	80	358	35S/51S	222	22
DE-1	27	36A	36	224	24A
KR→l RE-l	1-V 80	37A 38A	37 38	22 <b>4</b> A	24A
2A3H	2A3	39	39/44	226	26
ZAON G→2	2S/4S	39A	39/44	227 230	27 30
G-2S	25/45 25/45	4311G	25A6G	231	31
RE-2	81	44	39/44	232	32
so-2	50	HZ-50	1223	233	33
G-4	28/48	51	<b>3</b> 5/5 <b>1</b> .	234	34
G-4S	28/48	518	35S/51S	235	35/51
5Y <b>3</b>	5Y3G	56-A	76 *	236	36
5Z4MG	5Z4, 5V4G	57-A	57-AS	237	37
KR-5	6A4/LA	58-A	58-AS	238	<b>3</b> 8
6A8MG	6A8G	64	<b>3</b> 6 *	239	39/44
6B6	6B6G	6 <b>4</b> A	36	240	<b>4</b> 0
6B6MG	6B6G	65	39/44 *	245	<b>4</b> 5
6C5MG	605G	65A	39/44	247	47
6F5MG	6F5G	67	37 *	250	50
6F6MG	6F6G	67A	37	280	80
605	6G5/6H5 6G5/6H5	68	<b>3</b> 8 *	280M	8 <b>3</b> V
6H5	6H6G	A88	38 83 <b>†</b>	281	81
6H6MG 6J7MG	6J7G	80M 81M	81	288 C-299	83V
6K7MG	6K7G	84	84/6Z4	X-299	V-99 X-99
6L7MG	6L7G	G-84	2Z2/G84	A-299	X-99
6N6	6N6G	88	83 †	482A	71A
6N6MG	6N6G	95	2A5	482B	182B/482B
6P7	6P7G	96	1-V	482B	183/483 1
6Q7MG	6Q7G	98	84/624	483	183/483
6R711G	6R7G		•	585	50
6X5MG	6X5G	112	12A	586	50
6Y5 <b>V</b>	6Y5	112A	12A	P-861	6Z <b>4/</b> 84
6Z3	1-V	120	20	95 <b>1</b>	1B4 <b>/9</b> 51
6Z4/8	1 84/6Z4	171	71A	986	83 🕇
6Z5/12	Z5 6Z5	171A	71A		
C-11	WD-11	171AC	71A	AD	1-V
C-12	WX-12 WX-12	171B	71A	AF	82
WD-12 14Z3	WX-12 12Z3	182-A	71A	AG	83 🕇
22AC	24A	182-B V-199	183 ‡ V-99	AX	OLA
24	24A	V=199 X-199	X-99	B E	V-99
25A6M0		V-799	A= 00	E G	20 40
25A7	25A7G	200	GOA	H	40 00A
25A8	25A7G	201	Ola	L.A	6A4/LA
25S	1B5/25S	ALOS	Ola	PZ	47
25/25	B5/25S	202	10	PZH	2A5
,	•				~

<sup>†</sup> When the filament supply will stand one ampere additional drain. \* In automobile receivers only.

<sup>#</sup> When both power tubes are changed together.

### RAYTHEON RESISTOR TUBES


### FOR

### A-C - D-C RECEIVERS

Type No.	No.of 6.3 V Tubes	No.of 25 V Tubes	Volts Drop at 300ma	No.of Dial Lamps	Dial Lamp Type	Cir- cuit	R	Ro	Number Tl t page	<sub>T</sub> 2	Inter- change- able with
SMALL METAL SHELL TYPES											
36A K36B K36C K36D L36B L36C L36D 42A K42B K42C K42C L42B L42B L42B L42B L42C L42D 49A K49C K49CB K49CB K49CB K49CB	55555554444444333 333	2 2 2	36.0 36.0 36.0 36.0 36.0 36.0 36.0 42.3 42.3 42.3 42.3 42.3 42.3 42.3 42.3	2	# <b>4</b> 0 # <b>4</b> 6 # <b>4</b> 6	D B C	35555555555555555555555555555555555555	77777777777777777777777777777777777777	8 8	2	
L49D 55A K55B K55C K55D L55B L55C L55D	55588886688	ଷଷଷଷଷଷଷ	48.6 54.9 54.9 54.9 54.9 54.9 54.9	None 1 2 2 1 2 2 2	#46 #40 #40 #46 #46 #46	D A B C D B C	3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	7 7 7 7 7 7 7	8 8 8 8 8 8 8	2 2	
				GLASS B	ULB TY	PES					
140L4 140L8 140L4 140R4 140R4 140R4 165L4 165L4 165L4 165R4	44444333333	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	42.3 42.3 42.3 42.3 42.3 42.6 48.6 48.6 48.6	l 2 2 None 1 2 2 1 2 2 None	#46 #46 #46 #40 #46 #46 #46 #40	B C D A B C D B C D A B	111111111111111111111111111111111111111	4 4 4 4 4 4 4 4 4 4 4	333 333333	2 2	40B2 40A2
165R8 165R44 185L4 185L8 185L44 185R4 185R4 185R4 185R44 60R3OG 878R48	3 3 3 3 2 2 2 2 2 3 2 2 3 7 5 7 5 7 5 7	2 2 2 3 1 2 2	48.66.9999999665 544.999999665	2 2 2 2 None 1 2 2 1 None	#40 #466 #466 #400 #400 #400 #400	C D B C D A B C D B	i i i i i i i i special	4 4 4 4 4 4 4 4 4 4 6 1 7	3 3 3 3 3 3 3 3 3 3 4 t	2 2	50A2 50X3 50X3T
		L	ARGE PEI	RFORATE	O METAL	L SHELI	L TYPES				
42A1 42A2 42B2 49A1 49A2 49B2 55A1 55A2 55B2 2LR212	4 4 4 3 3 3 2 2 2 Spec	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	42.3 42.3 42.3 48.6 48.6 54.9 54.9 54.9	None 1 2 None 1 2 None 1 2 2 2 2 2	#40 #40 #40 #40 #40 #40 #40	A B C A B C D	4 4 4 4 4 4 4 4 4 4	88888888888	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2	

Voltage drops are computed to supply filament current of 300 ma. with line voltage of 117.5 volts.

Continued on next page



For data on RAYTHEON RESISTOR TUBES FOR BATTERY OPERATED RECEIVERS refer to the TTPES NB-1 to NB-8 at the end of the rating and characteristic data section.

### RAYTHEON MINATURE LAMPS

### RADIO PANEL TYPES

Type	Volts	Amps.	C.P.	Bulb	Bulb Base		B <b>ead</b> Color	L.C.L. Inches	M.O.L. Inches
R40 A R41 A R42 A R43 A R45 A R46 A R48 A R49 A R50 A R50 A R292 A	6-8 6-2,5 3,5 6-8 2,6-8	0.15 0.15 0.5 0.5 0.25 0.25 0.25 0.06 0.06 0.12 0.2 0.17	0.5 0.5 0.75 0.75 0.8 0.75 0.8 0.03 0.03 0.07 1.0	T-3 1/4	Min. Min. Min. Min. Min. Min. Min. Min.	Bayonet Bayonet Bayonet Screw Bayonet Bayonet Screw Screw Bayonet	Brown Brown White Green White Blue Green Blue Pink Pink White White White	29/32 23/32 29/32 29/32 23/32 23/32 23/32 29/32 25/52 23/32 23/32 29/32 23/32	1 1/8 1 1/8
				AUTOMO					4
R51 R55	6-8 6-8	0.2	1.0 1.5	G-3 1/2 G-4 1/2	Min.	Bayonet Bayonet	White White	1/2 1/2	15/16 1 1/16
	DIA MAT.	332	DIR. MIST.	[2]	DIA. MAX.	1/2	DIA. MAX.	5" DIR.	HICL Mal.
R 4 R 4 R 4 R 4 R 2	! 2 6 8	R R R R	40 A 43 44 45 49 49 A 292 A	R 5	0	R :	51	R 55	

SI4-BULE

nn

### **RAYTHEON**

### OOA

TRIODE

VAPOR TYPE DETECTOR Filament Type Glass Bulb

The OO-A is a vapor type triode tube designed for service as a detector in storage battery operated receivers.



BOTTOM VIEW OF SOCKET

RATINGS

The OO-A is

Filament Voltage Filament Current d-c volts 0.25 amp Max. Plate Voltage volts

CHARACTERISTICS

Plate Voltage 45 volts Grid Bias volts 20 Amplification Factor 30000 olims Plate Resistance unhos Transconductance 666 Plate Current (approximate) 1.5

DETECTOR - GRID LEAK TYPE

volts Plate Voltage 45 Return to negative filament 2 to 3 megohms Grid megohms Grid Leak Resistance 0.00025 Grid Condenser цſ


DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate 8.5 μμf Input 3.2 uu£ Output ulli

### O1A

### **RAYTHEON**

### 01A



TRIODE DETECTOR OR AMPLIFIER Filament Type Glass B Glass Bulb

The Ol-A is a triode type amplifier tube designed for service as a detector or amplifier in storage battery operated receivors.



BOTTOM VIEW OF SOCKET

RATINGS

Filament Voltage Filament Current 5 d-c volts 0.25 amp 135 volts Max. Plate Voltage

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate 8.1 μμf Input μμ£ Out put 2.2 unf

AMPLIFIER - CLASS A

Plate Voltage 90 135 volts Grid Bias -4.5 \_a volts Amplification Factor R 8 11000 10000 Plate Resistance ohms Transconductance 725 800 umhos Plate Current 2.5

DETECTOR - BIASED TYPE

Plate Voltage Grid Bias (approximate) 90 135 volts -7.5 -13.5 volts
Adjusted to 0.2 ma with no signal Plate Current


DETECTOR - GRID LEAK TYPE

Plate Voltage 45 volts Grid Returned to positive filament 0.25 to 5 megohms Grid Leak Resistance 250 Grid Condenser DUC

#### 0Z4 0Z4G

#### **RAYTHEON**

0Z4 0Z4G



TWIN DIODE
FULL WAVE GAS FILLED RECTIFIER
Ionic Heated Cathode Type
Hetal Bulb-0Z4 Glass Bulb-0Z4G

The OZ4 is a full wave gas filled type rectifier tube with an ionic heated cathode requiring no heater supply voltage. It is designed particularly for service where high overall efficiency is desired.

FULL WAVE RECTIFIER



BOTTOM VIEW OF SOCKET OZ4G -#1 PIN -NO CONN. -#2 PIN-OMITTED




No Heater Supply Required
Maximum D-C Output Voltage 300 volts
Minimum D-C Output Current 30 ma
Maximum D-C Output Current 75 ma
Maximum Peak Plate Current 200 ma
Minimum Starting Peak Voltage 300 volts
Average Dynamic Voltage Drop 24 volts

The OZ4 was developed primarily for use in vibrator type B supply units for automobile receivers. It has the typical characteristics of all gas-filled rectifiers as regards a constant drop and ability to handle high peak currents. Any tendency of the tube to generate r-f noise may be eliminated by proper filtering and by connecting the metal shell to the point giving the best shielding. The shielding and filtering commonly used to eliminate vibrator noise will usually be sufficient.

The 0Z4 is filled with a permanent gas rather than a vapor filling. The tube characteristics are independent of the surrounding temperature.

The 0Z4 has the same external form and dimensions as other tubes of the metal line. However, in this tube the metal shell serves chiefly as container and electrostatic shield for the glass bulb, which is required to insulate the contained gas from the grounded shell.



TETRODE

REMOTE CUTOFF AMPLIFIER
Filament Type Glass Bulb



The lA4T is a tetrode type amplifier tube with remote cutoff characteristics designed for service as a high frequency amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1D50T. For characteristics of the pentode type, 1A4P, refer to the type 1D50F.



BOTTOM VIEW OF SOCKET

IA4-P, G, CONNECTED TO ◆4 PIN (-F)

#### RATINGS

Filament Voltage	2.0 d-c	volts
Filament Current	0.060	amp
Maximum Plate Voltage	180	volts
Maximum Screen Voltage	67.5	volts


#### DIRECT INTERELECTRODE CAPACITANCES

L2 max.∜	արք արք արք
0.01	).012 max.*
1.6	4.6
11	il

#### AMPLIFIER - CLASS A

Plate Voltage	180	volts
Screen Voltage	67.5	volts
Grid Bias	-3	volts
Amplification Factor	720	
Plate Resistance	0.96	megohm
Transconductance	750	umhos
Plate Current	2.3	ma.
Screen Current	0.7	ma
Transconductance at -15 volts bias	15	umhos

\*With tube shield.




ST 12-0 BULB

ST

## HEPTODE PENTAGRID CONVERTER Filament Type Glass Bulb

The 1A6 is a pentagrid type converter tube designed for service as a combined mixer and oscillator in battery operated superheterodyne receivers. The rations and electrical characteristics are identical with those of the type 1D7G.



RATINGS BOTTOM VIEW OF SOCKET


Filament Voltage	2.0 d-c	volts
Filament Current	0.060	amp
Maximum Plate Voltage	180	volts
Maximum Screen Voltage	67.5	volts
Maximum Grid #2 Voltage	135	volts
Maximum Grid #2 Supply	180†	volts
Minimum Crid #4 Blas	-3	volts
Maximum Cathode Current	9	ma

DIRECT INTERELECTRODE CAPACITANCES	(approximate)	
Grid #4 to Plate	0.25*	μμf
Grid #4 to Grid #2	0.2 *	μμ <b>f</b>
Grid #4 to Grid #1	0.1 *	μμ <b>£</b>
Grid #1 to Grid #2	0.8	цц <b>f</b>
Grid #4 to all other Elements (r-f input)	10.5	μμf
Grid #1 to all other Elements (osc. input)	5	uu£
Grid #2 to all other Elements (osc. output)	6	цц <b>г</b>
Plate to all other Elements (mixer output)	9	μμf

	UPERHETERODYNE CIR		
Plate Voltage	135_	180	volts
Screen (Grids #3 and #5) Voltage	67.5	67.5	volts
Anode Grid (#2) Voltage	135	135	volts
Anode Grid Supply Voltage		180 <b>†</b>	volts
Control Grid (#4) Bias	-3	-3	volts
Oscillator Grid (#1) Resistor	50000	50000	ohms
Plate Resistance	O.4	0.5	megohm
Conversion Transconductance	275	300	μmhos
Plate Current	1,2	1.3	ma
Sereen Current	2.5	2.4	ma
Anode Grid Current	2.3	2.3	ma
Oscillator Grid Current	0.2	0.2	ma.
Total Cathode Current	6.2	6.2	ma
Control Grid Bias	-22.5	-22.5	volts
(For Conversion Transconductance = 4 μ	mhos)		

With plate voltage = 135 to 180 volts, screen voltage = 67.5 volts, anode grid voltage = 135 volts (no series resistor), control grid bias = -3 volts and oscillator grid voltage = 0 volts, the transconductance of the oscillator section (not oscillating) is 425  $\mu mhos$  and the anode grid current is 2.3 ma.

†Applied through a 20000 ohm series resistor, by-passed by a 0.1  $\mu f$ . condenser. \*With tube shield.



RAYTHEON ENGINEERING SERVICE

PENTODE AMPLIFIER

AMPLIFIER
Filament Type Glass Bulb



BOTTOM VIEW OF SOCKET

ST 12-0 BULB ST 12

The 1B4/951 is a pentode type amplifier tube designed for service as a high frequency amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1E5GP.

RATINGS

Filament Voltage Filament Current	
Maximum Plate Voltage Maximum Screen Voltage	

2.0	d=0	volts
0.060		amp
180		volts
67.5		volts


#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate Input Output	0.007 max.* 5 11	րրք Դող
AND TETED OF LOCAL		

#### AMPLIFIER - CLASS A


Plate Voltage Soreen Voltage Grid Bias Amplification Factor	90 67.5 -3 600	180 67.5 -3 975	volts volts volts
Plate Resistance Transconductance Plate Current Soreen Current Grid Bias for Plate Current Cutoff	1 600 1.6 0.7 -8	1.5 650 1.7 0.6	megohm µmhos ma me volts

\*With tube shield.



RAYTHEON ENGINEERING SERVICE

DUO-DIODE TRIODE DETECTOR AMPLIFIER Filament Type Glass Bulb



The 1B5/25S is a duo-diode triode type amplifier tube designed for service as a combined diode detector, AVC rectifier and adds frequency amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1866.



#### RATINGS

Filament Voltage	2.0 d-e	volts
Filament Current	0.060	amp
Maximum Plate Voltage	135	volts

#### DIRECT INTERELECTRODE CAPACITANCES - TRIODE SECTION

Grid to Plate	3.6	քպդ
Input	2.0	uμf
Output	3	$\mu\mu\mathbf{f}$


#### AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage	135	volts
Grid Bias	<b>-3</b>	~olts
Amplification Factor	20	
Plate Resistance	35000	ohm <b>s</b>
Transconductance	5 <b>7</b> 5	μmho <b>s</b>
Plate Current	0.8	ma.

#### DIODE SECTION

The two diode units are independent of each other and of the triode section except for the common filament. The diodes may be used as a half-wave or as a full-wave rectifier; or one diode may be used as a half-wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVO voltage.

If only one diode plate is used as an audio rectifier, DL on pin 4 should be used because DL is near the negative end of the filament and current will flow to this plate with zero signal when returned to the negative end of the filament.




RAYTHEON ENGINEERING SERVICE

# ST 12-0 BULB ST

## HEPTODE PENTAGRID CONVERTER Filament Type Glass Bulb

The 106 is a pentagrid type converter tube designed for service as a combined mixer and oscillator in battery operated superheterodyne receivers. The ratings and electrical characteristic are identical with those of the type 107G.



#### RATINGS BOTTOM VIEW OF SOCKET

	201101111121	, or obtain
Filament Voltage	2.0	d-o volts
Filament Current	0.12	amp
Maximum Plate Voltage	180	volts
Maximum Screen Voltage	67.5	volts
Maximum Grid #2 Voltage	135	volts
Maximum Grid #2 Supply	180+	volts
Minimum Grid #4 Bias	-3	volts
Maximum Cathode Current	9	ma.

#### DIRECT INTERELECTRODE CAPACITANCES (approximate)

Grid #4 to Flate Grid #4 to Grid #2 Grid #4 to Grid #1 Grid #1 to Grid #1 Grid #1 to all other Elements (r-f input) Grid #1 to all other Elements (osc. input) Grid #2 to all other Elements (osc. output) Flate to all other Elements (maker output) Flate to all other Elements (maker output)	0.3 * 0.15* 1.5 10 6 10	Դոր Դոր Դոր Դոր Դոր Դոր Դոր Դոր
--	-------------------------	--


#### FREQUENCY CONVERTER - SUPERHETERODYNE CIRCUIT

Plate Voltage	135	<b>1</b> 80	volts
Screen(Grids #3 and #5) Voltage	67.5	67.5	volts
Anode Grid (#2) Supply Voltage	135 †	180 +	volts
Control Grid (#4) Blas	-3	-3	volts
Oscillator Grid (#1) Resistor	50000	50000	ohm <b>s</b>
Plate Resistance	0.55	0.75	megohm
Conversion Conductance	300	325	umhos
Plate Current	1.3	1.5	me
Screen Current (approximate)	2	2	ma.
Anode Grid Current	2.6	3.3	ma.
Oscillator Grid Current	0.2	0.2	ma.
Total Cathode Current (approximate)	6.5	7	me
Control Grid Bias	-14	-14	volts
(For conversion conductance = 4 μmhos)			

With plate voltage = 135 to 180 volts, screen voltage = 67.5 volts, anode grid voltage = 135 volts (no series resistor), control grid bias= -3 volts, and oscillator grid voltage = 0 volts, the transconductance of the oscillator section (not oscillating) is 1000  $\mu\rm mhos$ , and the anode grid current is 4.9 ma.

†Applied through a 20000 ohm series resistor, bypassed by a 0.1  $\mu$ f. condenser.

\*With tube shield.



## ST 12-0 BIH B 19 00 N 01 SIL 8 PRONG OCTAL BASE

#### HEPTODE PENTAGRID CONVERTER Filament Type Glass Bulb

The 1076 is a pentagrid type converter tube designed for service as a combined mixer and oscillator in battery operated superbetarodyne receivers. The ratings and electrical characteristics are identical with those of the type 106.



#### RATINGS

Filament Voltage
Filament Current
Haximum Plate Voltage
Haximum Screen Voltage
Maximum Grid #2 Voltage
Maximum Grid #2 Supply
Minimum Grid #4 Bias
Maximum Cathode Current

U	<b>6</b>
BOTTOM VIEW	OFSOCKET
2.0 d-c	volts
0.12	amp
180	volts
67.5	volts
135	volts
180 †	volts
<b>-</b> 3	volts
9	ma

#### DIRECT INTERELECTRODE CAPACITANCES\*


Grid #4 to Plate Grid #4 to Grid #2 Grid #4 to Grid #1 Grid #1 to Grid #2 Grid #4 to all other Elements (r-f input) Grid #1 to all other Elements (oso. input) Grid #2 to all other Elements (oso. output)	0,3 0,3 0.1 1.5 11 7	րդ <b>Ր</b> Արդ <b>Ր</b> Արդ <b>Ր</b> Արդ <b>Ր</b> Արդ Մ
Grid #2 to all other Elements (osc. output) Plate to all other Elements (mixer output)	7 14	μμ <b>ք</b> μμ <b>ք</b>

#### FREQUENCY CONVERTER - SUPERHETERODYNE CIRCUIT

With plate voltage = 135 to 180 volts, screen voltage = 67.5 volts, anode grid voltage = 135 volts (no series resistor), control grid bias = -3 volts and oscillator grid voltage = 0 volts, the transconductance of the oscillator section (not oscillating) is 1000 mmhos, and the anode grid current is 4.9 ma.

\*With tube shield connected to cathode.

†Applied through a 20000 chm series resistor, bypassed by a 0.1 µf conden-



#### 1D5G-P

PENTODE
REMOTE CUTOFF AMPLIFIER
Filament Type Glass Bulb

ST 12-0 BULB

ST 12-0 BULB

A GO
B MARK

T PRONG
SMALL

OCTAL BASE

The 1D5GP is a pentode type amplifier tube with remote cutoff characteristics designed for service as a high frequency amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1A4P. For characteristics of the tetrode type, 1D5GT, refer to the type 1A4T.



BOTTOM VIEW OF SOCKET

#### RATINGS

Filament Voltage	2.0 d-c	volts
Filament Current	0.060	amp
Maximum Plate Voltage	180	volts
Maximum Screen Voltage	67.5	volts


#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	0.007 max.*	μ <b>μ</b>
Input	6.2	μμ <b>f</b>
Output	12	$\mu\mu \mathbf{f}$

#### AMPLIFIER - CLASS A


Plate Voltage	90	180	volts
Screen Voltage	67.5	67.5	volts
Grid Bias	<b>-</b> 3	-3	volts
Amplification Factor	425	750	megohm
Plate Resistance	0.6	1	megohm
Transconductance	720	750	umhos
Plate Current	2.2	2.3	` ma
Screen Current	0.9	0.8	me.
Transconductance at -15 volts bias	15	15	umhos

\*With tube shield.



HEPTODE

PENTAGRID CONVERTER Filament Type Glass Bulh



The 1DWG is a pentagrid type converter tube designed for service as a combined mixer and oscillator in battery operated superheterodyne receivers. The ratings and electrical characteristics tings and electrical characteristics are identical with those of the type IAG.



Filament Voltage Filament Current Maximum Plate Voltage Maximum Flate Voltage
Maximum Soreen Voltage
maximum Grid #2 Voltage
Maximum Grid #2 Supply
Minimum Grid #4 Bias Maximum Cathode Current

_	~
BOTTOM VIEW	OFSOCKET
2.0 d-c	volts
0,060	amp
180	volts
67.5	volts
135	volts
1.80 <del>†</del>	volts
-3	volts
٥	me

#### DIRECT INTERELECTRODE CAPACITANCES\*


Grid #4 to	o Plate	0.3	$\mu\mu f$
Grid #4 to	o Grid #2	0.3	uu£
Grid #4 to	o Grid #1	0.1	μμf
Grid #1 to		1.5	μμτ
Grid #4 to	o all other elements (r-f input)	11	μμΩ
Grid #1 to	o all other elements (osc.input)	7	μμ⊈
	o all other elements (osc.output)	7	μμf
Plate to	o all other elements (mixer output)	14	$\mu\mu f$

#### FREQUENCY CONVERTER - SUPERHETERODYNE CIRCUIT

·			
Plate Voltage	135	180	volts
Screen (Grids #3 and #5) Voltage	67.5	67.5	volts
Anode Grid (#2) Voltage	135	135	volts
Anode Grid Supply Voltage		180 <del>1</del>	volts
Control Grid (#4) Bias	-3	-3	volts
Oscillator Grid (#1) Resistor	50000	50000	ohma
Plate Resistance	0.4	0.5	megohm
Conversion Transconductance	275	300	μmhos
Plate Current	1.2	1.3	ma
Screen Current	2.5	2.4	me.
Anode Grid Current	2.3	2.3	ma.
Oscillator Grid Current	0.2	0.2	ma.
Total Cathode current	6.2	6.2	ma.
Control Grid Bias	-22.5	-22.5	volts
(For Conversion Transconductance =			
(= == convergion frameonadosanos =	# hunton)		

With plate voltage = 135 to 180 volts, screen voltage = 67.5 volts, anode grid voltage = 135 volts (no series resistor), control grid bias = 3 volts and oscillator grid voltage = 0 volts, the transconductance of the oscillator section (not oscillating) is 425 mmhos and the anode grid ourrent is 2.3 ma.

\*With tube shield connected to cathode. †Applied through a 20000 ohm series resistor, bypassed by a 0.1 uf condenser.



#### 1E5G P

PENTODE
ALPLIFTER
Filament Type Glass Bulb



The 1E5GP is a pentode type amplifier tube designed for service as a high frequency amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1E4/951.



BOTTOM VIEW OF SOCKET

#### RATINGS

Filament	: Volte	age
Filament	: Curre	ent
Maximum	Plate	Voltage
Maximum	Sareer	1 Voltage

2.0	d-c	volts
0.060		amp
180		volts
67.5		volts


#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	0.007 max.*	uuf
Inpu <b>t</b>	6.2	μμ <b>1</b>
Output	12	μμf


#### AMPLIFIER - CLASS A

Plate Voltage	90	180	volts
Screen Voltage	67.5	67.5	volts
Grid Bias	-3	-3	volts
Amplification Factor	600	975	
Plate Resistance	1	1.5	megohms
Transconductance	600	650	umhos
Plate Current	1.6	1.7	m <b>a</b> .
Screen Current	0.7	0.6	m <b>s</b> .
Grid Bias for Plate Current Cutoff	<del>-</del> 8	-8	volts

\*With tube shield.



TWIN PENTODE
POWER AMPLIFIER
Filament Type Glass Bulb



The LETG is a twin pentode type amplifier tube designed for service as a push-pull amplifier in the output stage of battery operated receivers.



#### BOTTOM VIEW OF SOCKET

	barrory	oporatou	100011018	
	77700			
KA'	INGS			

d-c volts
volts


#### AMPLIFIER - CLASS A - EACH PENTODE

Plate Voltage Screen Voltage Grid Bias* Amplification Factor	135 135 •4.5 350	volts volts volts
Plate Resistance	0.22	megohm
Transconductance	1600	µmhos
Plate Current	7.5	ma
Screen Current	2.1	ma

#### AMPLIFIER - CLASS A - PUSH-PULL

na		
Plate Voltage	135	volts
Screen Voltage	135	volts
Grid Bias*	-7.5	volts
No-Signal Plate Current (total)	6.5	ma.
No-Signal Screen Current (total)	2	ma.
Load Resistance	24000	ohms
Total Harmonic Distortion	5	percent
Power Output	0.65	watt
(With signal = 12 volts RMS grid to grid)		

\*Grid return to negative filament.



STI4 BULB

#### **RAYTHEON**

#### 1F4

#### PENTODE POWER AMPLIFIER Filament Type Glass Bulb

The 1F4 is a pentode type power amplifier tube designed for service in the output stage of battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1F5G.



#### BOTTOM VIEW OF SOCKET

#### RATINGS


Filament Voltage	
Filament Current	
Maximum Plate Voltage	
Maximum Soreen Voltage	

#### 2.0 d-c 0.12 135 135 volts amp volts

volts

#### AMPLIFIER - CLASS A


Plate Voltage	90	135	volts
Soreen Voltage	90	135	volts
Grid Bias	-3	-4.5	volts
Amplification Factor	340	340	
Plate Resistance	0.24	0.2	megohm
Transconductance	1400	1700	umhos
Plate Current	4	8	ma
Screen Current	1.3	2.6	ma
Load Resistance	20000	16000	ohms
Total Harmonic Distortion	5	5	percent
Power Output	120	340	mw



RAYTHEON ENGINEERING SERVICE

#### 1F5G

PENTODE
POWER AMPLIFIER
Filament Type Glass Bulb



The 1F5G is a pentode type power amplifter tube designed for service in the output stage of battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1F4.




BOTTOM VIEW OF SOCKET

RATINGS

Filament Voltage Filament Current Maximum Plate Voltage Maximum Screen Voltage 2.0 d-c volts 0.12 amp 135 volts 135 velts

#### AMPLIFIER - CLASS A

Plate Voltage Soreen Voltage Grid Bias	90 90 <b>-3</b>	135 135 -4.5	volts volts volts
Amplification Factor	340	340	
Plate Resistance	0.24	0.2	megohm
Transconductance	1400	1700	µmho∎
Plate Current	4	8	ma.
Soreen Current	1.3	2.6	ma.
Load Resistance	20000	16000	ohm <b>s</b>
Total Harmonic Distortion	5	5	percent
Power Output	120	340	III.M.



ST 12-0 BUU B

MAX.

DUO-DIODE PENTODE DETECTOR AMPLIFIER Filament Type Glass Bulb

The 1F6 is a duo-diode pentode type amplifier tube designed for service as a combined diode detector, AVC rectifier, and high or audio frequency amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1F7G.



BOTTOM VIEW OF SOCKET

RATINGS		
Filament Voltage	2.0 d-c	volts
Filament Current	0.060	amp
Max. Plate Voltage	180	volts
Max. Screen Voltage	67.5	volts

DIRECT INTERELECTRODE CAPACITANCES - PENTODE SECTION Grid to Plate 0.007 max.\* uuf Input  $\mu\mu \mathbf{f}$ Output μμf


AMPLIFIER - CLASS A - PENTODE SECTION Screen Voltage Grid Bias Amplification Factor (approximate) Flate Resistance (approximate) Transconductance Flate Current Screen Current Transconductance at -12 volts bias	180 67.5 -1.5 650 1 650 2 0.6 15	volts volts volts megohm µmhos ma µmhos
---	--	---

CLASS A (Resist	ance Coupled)	-PENTODE	SECTION
135	135	135	volts
135	135	135	volts
-1.0	<b>-1.</b> 5	-2.0	volts
0.25	0.25	0.25	megohm
1	0.9	0.8	megohm
0.64	0.63	0.62	volts
0.42	0.42	0.42	me.
0.34	0.34	0.34	me.
1 0.5	1 0.5	1 0.	5 megohm
30.8 28	29.4 26.6	28 25	.2 volts
5 5	5 5	5 5	percent
48 43	47 42	46 41	
	135 135 -1.0 0.25 1 0.64 0.42 0.34 1 0.5 30.8 28	135 136 135 135 135 135 135 135 135 135 135 135	135 135 135 135 135 135 135 135 135 135

#### DIODE SECTION

The two diodes are located at the negative end of the filament. They are independent of each other and of the pentode section except for the common filament. The diodes may be used as a half wave or as a full wave rectifier or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain AVC voltage.

\*With tube shield. †If a grid resistor is used, its value should not exceed 1 megohm. For following tube.





RATINGS

DUO-DIODE PENTODE
DETECTOR AMPLIFIER
Filament Type Glass Bulb

The 1F7G is a duo-diode pentode type amplifier tube designed for service as a combined diode detector, AVC rectifier, and high or audio frequency amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1F6.



BOTTOM VIEW OF SOCKET

2.0 dec. volts

Filament Voltage 2.0 d-c volts
Filament Current 0.060 amp
Maximum Plate Voltage 180 volts
Maximum Screen Voltage 67.5 volts
DIRECT INTERRELECTRODE CAPACITANCES-PENTODE SECTION
Grid to Plate (with tube shield) 0.007 max. 

µµf

Grid to Plate (with tube shield) 0.007 max. µµf Input 4.0 µµf Output 9 µµf AMPLIFIER - CLASS A - PENTODE SECTION

Plate Voltage	<b>1</b> 80	volts
Screen Voltage	67.5	volts
Grid Bias	-1.5	volts
Amplification Factor (approximate)	650	
Plate Resistance (approximate)	1	megohm
Transconductance	650	μ. <b>mhos</b>
Plate Current	2	ma.
Soreen Current	0.6	ma.
Transconductance at -12 volts bias	15	μ <b>mhos</b>


AMPLIFIER	- CLAS	S A →	RESISTANC	E COUPLE	D → P	ENTODE	SECTION
Plate Supply Voltage	13	5	13.	วี	13	5	volts
Screen Supply Voltage	13	5	13	5	13	5	volts
Grid Biast	-1.	0	-1.	5	-2.	0	volts
Plate Resistor	0.	25	0.	25	0.	25	megohm
Sereen Resistor	1.	0	0.	9	0.	8	megohm
Signal Peak Voltage	0.	64	0.	6 <b>3</b>	0.	62	volts
No-Signal Plate Current	0.	42	0.	42	٥.	42	ma.
Max-Signal Plate Current	0.	34	0.	3 <b>4</b>	٥.	34	ma
Grid Resistor!	1.0	0.5	1.0	0.5	1.0	0.5	megohm
Output Peak Voltage!	30.8	28	29.4	26.6	28	25.2	volts
Total Harmonic Distortion	5	5	5	5	5	5	percent
Voltage Amplification	<b>4</b> 8	43	47	42	<b>4</b> 6	41	

DIODE SECTION

The two diode units are independent of each other and of the triode section except for the common filament. The diodes may be used as a half-wave or as a full wave rectifier; or one diode may be used as a half-wave rectifier for detection and the other diode used as a rectifier to obtain delayed AVC voltage.

If only one diode plate is used as an audio rectifier,  $D_{\rm L}$  on pin 5 should be used because  $D_{\rm L}$  is near the negative end of the filament and current will flow to this plate with zero signal when returned to the negative filament.

†If a grid resistor is used, its value should not exceed 1 megohm. iFor following tube.



RAYTHEON ENGINEERING SERVICE

#### **1G5G**

PENTODE POWER AMPLIFIER Filament Type Glass Bulb

STIA BULB ZON. 7 PRONG MEPIUM OCTAL BASE

The 1656 is a pentode type power amplifier tube designed for service in the output stage of battery operated receivers.

RATINGS

Filament Voltage Filament Current Maximum Plate Voltage Maximum Screen Voltage


AMPLIFIER - CLASS A



BOTTOM VIEW OF SOCKET volts

2.0 d-c 0.12 90 90 amp volts

Plate Voltage	90	volts
Sgreen Voltage	90	volts
Grid Bias	<b>-</b> 6	volts
Amplification Factor	200	
Plate Resistance	0.133	megohm
Transconductance	1500	umhos
Plate Current	8.5	ma.
Screen Current	2.7	ma
Load Resistance	8000	ohma
Total Harmonics	9	percent
Power Output	0.3	watts



-15

0.5

2.1

2000

volts

ma

ohma


wat:t.e

volts

Bias

Grid

#### **RAYTHEON**



Power Outputt (With average power input = 260 mw. grid to grid)

Wo-Signal Clate Current (per tube)
Load Resistance (plate to plate)

DETECTOR - BLASED TYPE Plate Voltage Grid Dias (approximate) Plate Current; 135 90 180 -9 -13.5 -18 volts
Adjusted to 0.2 ma, with no signal


DETECTOR - GRID LEAK TYPE

Plate Voltage Returned to positive filament 1 to 5 megohms Grid Grid Leak Resistance megohm**s** Grid Condenser 0.00025

twith one type 1846 as driver operated at plate voltage of 157.5 volts, grid hiss of -11.3 volts, plate load of approximately 18000 ohms, and input transformer ratio, primary to 1/2 secondary, of 1.165. Total distortion is 6% to 7%.

1With normal maximum signal the average d-c plate current should not exceed 2 ma.

For additional curves refer to the type 30.



RAYTHEON ENGINEERING SERVICE

DUO-DIODE TRIODE
DETECTOR AMPLIFIER
Filament Type Glass Bulb



The 1H6G is a duo-diode triode type amplifier tube designed for service as a combined diode detector, AVC rectifier and audio frequency amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1B5/25S.



BOTTOM VIEW OF SOCKET

RATINGS

Filament Voltage 2.0 d-c volts
Filament Current 0.060 amp
Eaximum Flate Voltage 135 volts

DIRECT INTERELECTRODE CAPACITANCES - TRIODE SECTION

Orid to Flate 3.6 µиf Input 2.0 µuf Output 3 µuf


AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage	135	volts
Grid bias	-3	volts
Amplification Factor	20	
Plate Resistance	35000	ohms
Transconductance	575	umho <b>s</b>
Plate Current	0.8	ma

#### DIODE SECTION

The two diode units are independent of each other and of the triode section except for the common filament. The diodes may be used as a half-wave or as a full-wave rectifier; or one diode may be used as a half-wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVO voltage.

If only one diode plate is used as an audic rectifier,  $D_L$  on pin 5 should be used because  $D_L$  is near the negative end of the filament and current will flow to this plate with zero signal when returned to the negative end of the filament.



RAYTHEON ENGINEERING SERVICE

### PENTODE POWER AMPLIFIER Filament Type Glass Bulb

ST 14 BULB

The 1J5G is a pentode type power amplifier tube designed for service in the output stage of battery operated receivers. The ratings and electrical characteristics are identical with those of the type 950.




BOTTOM VIEW OF SOCKET

#### RATINGS

Filament Voltage	2.0 d-c	volts
Filament Current	0.12	amp
Maximum Plate Voltage	<b>13</b> 5	volts
Maximum Screen Voltage	135	volts

#### AMPLIFIER - CLASS A

Plate Voltage Screen Voltage Grid Bias Amplification Factor	135 135 -16.5 100	volts volts volts
Plate Resistance Transconductance Flate Current Soreen Current Load Resistance Power Output Maximum Signal Voltage (RMS)	0.1 1000 7 2 13500 450 11.7	megohm  µmhos  ma  ma  ohms  mw  volts





TWIN TRIODE POWER AMPLIFIER Filament Type Glass Bulb

The 1J66 is a twin triode type amplifier tube designed for service as a Class B power amplifier in the output stage of battery operated receivers. The ratings and electrical characteristics, except filament current, are identical with those of the type 19.



BOTTOM VIEW OF SOCKET


RATINGS

Filament Voltage Filament Current	2.0 d-c 0.24	volts
Haximum Plate Voltage	135	volts
Maximum Peak Plate Čurrent (per plate)	50	ma

ALPLIFIER - CLASS B


Plate Voltage	135	135	135	volts
Grid Bias	-6	-3	0	volts
No-Signal Plate Current (per plate)	0.5	2	5	ma
Load Resistance (plate to plate)	10000	10000	10000	ohms
Power Output (approximate) Average Power Input (grid to grid)	1.6 0.095	1.9	2.1 0.17	watts watts

For additional curves refer to the type 19.



RAYTHEON ENGINEERING SERVICE

DIODE



HALF WAVE HIGH VACUUM RECTIFIER Heater Type Glass Bulb


The 1-V is a half wave high vacuum type rectifier tube having a low voltage drop designed for service in power supplies for storage battery or a-c operated receivers. It is interchangeable with the mercury vapor type 1.



BOTTOM VIEW OF SOCKET

HALF WAVE RECTIFIER - CONDENSER OR CHOKE INPUT FILTER


Heater Voltage (a-c or d-c) Heater Current Haximum A-C Plate Voltage (RMS) Haximum Inverse Peak Voltage Haximum D-C Output Current Maximum D-C Voltage between Heater and Cathode	6.3 0.3 350 1000 50 500	volts volts volts ma volts
AVERAGE TUBE VOLTAGE DROP (At 100 ma. Output Current)	23	volts



#### **2A3 2A3H**

#### **RAYTHEON**

#### **2A3 2A3H**



TRIODE POWER AMPLIFIER Glass Bulb Filament Type-2A3 Heater Type-2A3H

The 2A3 and 2A3II are triode type power amplifier tubes designed for sorvice in the output stage of a-c operated receivers.

#### RATINGS

2A3 Fil. Voltage (a-c or d-c)2.5 Fil. Current 2.5 volts amp

#### 2A3H

Heater Voltage (a-c or d-c)2.5 volts Leater Current 2.8 amp



BOTTOM VIEWS OF SOCKETS 2A3H-CATHODE CONNECTED INT. TO MID-POINT OF HEATER

2A31

Plate Voltage
Grid Bias*
Amplification Factor
Plate Resistance
Transconductance

Plate Current Load Resistance Power Output (5% second harmonic)

250 max. volts - 45 volts 4.2 800 ohms 5250 umhos 60 mp 2500 ohms 3.5 watts

#### AMPLIFIER - CLASS AB - PUSH-PULL - TWO TUBES

Plate Voltage Grid Bias*	Fixed-Bias 300 max. -62	Self-Bias 300 max.	volts
Sclf-Bias Resistor Schignal Flate Current (per tube) Load Resistance (plate to plate) Total Marmonic Distortion Power Output	40 3000 2.5 15		ohms ma ohms ercent watts

The self-bias resistor for a single tube should be approximately 750 ohms. In either single tube or preh-pull operation, the self-bias resistor should be shunted by a suitable filter network to minimize grid bias changes due to current surges through the resistor.

Transformer or impedance input systems are recommended. If resistance coupling is used, the d-c resistance in the grid circuit should not exceed 0.5 megohm with self-bias or 0.05 megohm with fixed-bias.


\*2A3 Grid bias measured from mid-point of a-c operated filament.

For claracteristic curves refer to the types 6A3 and 6B4G. The characteristics of the 2A5 are the same as these of the 6A3 and the 6B4G except for the filement rating.

PENTODE POWER AMPLIFIER

Heater Type Glass Bulb

The 2A5 is a pentode type power amplifier tube designed for service in the output stage of a-c. operated receiv-RATINGS



BOTTOM VIEW OF SOCKET

AMPLIFIER -	CLASS	Α
-------------	-------	---

	Pentode	Connection		Connection
Plate Voltage	25	50 <b>315</b>	250	max. volts
Screen Voltage	28	50 315		volts
Grid Bias	-16	5.5 -22	-20	volt <b>s</b>
Amplification Fact	tor 20	00‡ 200;	† 7	
Plate Resistance	80	00001 7500	001 2600	ohm <b>s</b>
Transconductance	25	500 2650	2700	μmihos
Plate Current	34	42	31	m <b>a</b>
Screen Current	6.	.5 8		ma,
Load Resistance	70	000 7000	<b>4000</b>	ohm <b>s</b>
Total Harmonic Dis	st. 7	7	5	percent
Power Output	3	5	0.85	watts

AMPLIFIER - CLASS AB - TWO TUBES					
	Pentode Co	nnection	Triode C	onne <b>cti</b> or	a <b>†</b>
	Fixed-Bias	Self-Bias	Fixed-Bia	s Self-Bi	las
Plate Voltage	375 max.	3 <b>7</b> 5 max.	350 max.	350 max.	volts
Screen Voltage	250 max.	250 max.			volts
Grid Bias	-26 min.		<b>-3</b> 8		volts
Self-Bias Resistor		340		730 min.	ohm <b>s</b>
Signal Pk. Volt. (G to G)	8 <b>2</b>	94	123	132	volts
No-Signal Plate Current	34	54	45	50	ma
No-Signal Screen Current	5	8			ma.
Load Resistance (P to P)	10000	10000	6000	10000	ohm <b>s</b>
Total Harmonic Dist.	5	5	7	7	percent
Power Outnut (approx.)#	7.94	191	1824	7 4er	wette

#With one 2A5 triode connected as driver operated at plate voltage of 250 volts,grid bias of -20 volts and plate load of approximately 10000 ohms.

\*Input transformer ratio, primary to 1/2 secondary = 3.32 Almput transformer ratio, primary to 1/2 secondary = 2.5 \*\*Input transformer ratio, primary to 1/2 secondary = 1.67 \*\*Input transformer ratio, primary to 1/2 secondary = 1.29

†Screen connected to plate


1Approximate

For characteristic curves refer to the types 6F6G and 42. The characteristics of the 2A5 are the same as those of the 6F6G and the 42 except for the heater rating.

DUO-DIODE TRIODE DETECTOR AMPLIFIER Heater Type Glass Bulb

The 2AG is a duo-diode triode type amplifier tube designed for service as a combined diode dotector, AVC rectifier and resistance coupled audio frequency amplifier in a-c operated receivers.

RATINGS



BOTTOM VIEW OF SOCKET

2.5	volts
0.8	amp
250	volts
	0.8

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	1.7	րա <b>ք</b>
Input	2.0	դա <b>ք</b>
Output	3.5	դա <b>ք</b>
output	٥,٥	trh

AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage	250	volts
Grid Bias	-2	volts
Amplification Factor	100	
Plate Resistance	91000	ohms
Transconductance	1100	μmhos
Plate Current	1	ma

DIODE SECTION

The two diodes are independent of each other and of the triode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection and the other diode used as a rectifier to obtain delayed AVC voltage.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

For characteristic curves refer to the type 75. The characteristics of the 75 are the same as those of the 2A6 except for the heater rating.

## ST 12-P BULB ST 12-P BULB ST 12-P BULB T PBOWG SMALL BASE

## HEPTODE PENTAGRID CONVERTER Heater Type Glass Bulb

The 2A7 is a pentagrid type converter tube designed for service as a combined oscillator and mixer in a-c operated superheterodyne receivers.

RATINGS

Heater Voltage(a-c or	d-c)2.5	Volts
Heater Current	0.8	amp
Max. Plate Voltage	250	volts
Max. Screen Voltage	100	volts
Max. Grid #2 Voltage	200	volts
Max. Grid #2 Supply	250	volts
Min. Grid #4 Blas	-3	volts
Max. Cathode Current	14	ma



BOTTOM YIEW OF SOCKET

#### DIRECT INTERELECTRODE CAPACITANCES

Grid #4 to Plate Grid #4 to Grid #2		0.3 * 0.15*	լորը Մորը
Grid #4 to Grid #1 Grid #1 to Grid #2		0.15* 1.0	րրք Ղու
Grid #4 to all other Elements		8.5	μμf
Grid #1 to all other Elements Grid #2 to all other Elements		7 5.5	րևք Արդ
Plate to all other Elements	(Mixer Output)	9	μμf

#### FREQUENCY CONVERTER - SUPERHETERODYNE CIRCUIT

	200	050	
Plate Voltage	100	<b>25</b> 0	volts
Screen (Grids #3 and #5) Voltage	50	100	volts
Anode Grid (#2) Voltage	100		volts
Anode Grid Supply Voltage		250+	volts
Control Grid (#4) Bias	-1.5	-3	volts
Oscillator Grid Resistor	50000	50000	ohms
Plate Resistance	0.6	0.3	megohm
Conversion Transconductance	360	550	μmhos
Plate Current	1.1	3.5	me.
Screen Current	1.3	2.7	ma.
Anode Grid Current	2.0	4.0	ma
Oscillator Grid Current	0.25	0.4	ma.
Control Grid Bias (approximate)	-20	-45	volts
(For Conversion Transconductance = 2 μmhos)			

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

†Applied through a 20000 ohm series resistor, by-passed by a  $0.1 \mu f$  condenser. \*With tube shield.

For characteristic curves refer to the type 6A7. The characteristics of the 2A7 are the same as those of the 6A7 except for the heater rating.

DUO-DIODE PENTODE DETECTOR AMPLIFIER Heater Type Glass Bulb



The 2B7 is a duo-diode pentode type amplifier tube designed for service as a combined diode detector, AVC rectifier, and high or audio frequency amplifier in a-c operated receivers.



#### BOTTOM YIEW OF SOCKET RATINGS

Heater Voltage (a-c or d-c)	2.5	volts
Heater Current	0.8	amp
Maximum Plate Voltage	250	volts
Maximum Screen Voltage	125	volts

#### DIRECT INTERELECTRODE CAPACITANCES - PENTODE SECTION

Grid to Input Output	Plate		0.007 max.* 3.5 9.5	դդ <b>ք</b> դդ <b>ք</b> դդդ

#### AMPLIFIER - CLASS A - PENTODE SECTION

Plate Voltage	100	180	250	250	volts
Screen Voltage	100	75	100	125	volts
Grid Bias	-3	-3	-3	-3	volts
Amplification Factor	285	8 <b>4</b> 0	800	730	
Plate Resistance	0.3	1	0.8	0.65	megohm
Transconductance	930	840	1000	1125	μmho <b>s</b>
Plate Current	5.8	3.4	6	9	m <b>a</b> .
Screen Current	1.7	0.9	1.5	2.3	m <b>a</b> .
Grid Bias	-17	-13	-17	-21	volts
(For asthode current out	ስ <b>ኖ</b> ድ)				

Plate Supply Voltage	250	250	250	volts
Soreen Voltage	45	50	100	volts
Grid Bias	-5	-4.5	-3	volts
Plate Resistor	0.5	0.25	0.027	megohm
Plate Current	0.25	0.65	5.4	m <b>e</b>

DIODE SECTION

The two diode units are independent of each other and of the pentode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVC voltage.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.


\*With tube shield.

For characteristic curves refer to the type 6B7. The characteristics of the 2B7 are the same as those of the 6A7 except for the heater rating.

60

mo

TWIN DIODE FULL WAVE HIGH VACUUM RECTIFIER Metal Bulb Filament Type



The 5T4 is a full wave high vacuum type rectifier tube designed for service in power supplies delivering high output currents.

BOTTOM VIEW OF SOCKET


FULL WAVE RECTIFIER - CONDENSER INPUT FILTER

Filament Voltage
Filament Current
Haximum A-C Plate Voltage (RMS)
Maximum Inverse Peak Voltage
Haximum D-C Output Current 250

5 volts 8-0 amp volts 450 1250 volts

FULL WAVE RECTIFIER - CHOKE INPUT FILTER(10 henrys minimum)

Filament Voltage	5 a-c	volts
Filament Current	2	amp
Maximum A-C Plate Voltage (RMS)	550	volts
Maximum Inverse Peak Voltage	1550	volts
Maximum D-C Output Current	250	ma



ST 16 BULB

21 OR
28 M82

A PROVING MEDIUM OCTAL BASE

TWIN DIODE
FULL WAVE HIGH VACUUM RECTIFIER
Filament Type Glass Bulb

The 5U4G is a high vacuum type full wave rectifier tube designed for service in power supplies delivering high output currents. The ratings and electrical characteristics are identical with those of the types 5X4G and 5Z3.



BOTTOM VIEW OF SOCKET

250

volts


amp volts

volts

FULL WAVE RECTIFIER
Condenser or Choke Input Filter

Maximum D-C Output Current

AVERAGE TUBE VOLTAGE DROP 61 volts (At 250 ma, output current)



RAYTHEON ENGINEERING SERVICE

STI4 BULB

15 MAX

5 PRONG MEDIUM OCTAL BASE TWIN DIODE
FULL WAVE HIGH VACUUM RECTIFIER
Heater Type Glass Bulb

The 5V4G is a full wave high vacuum type to rectifier tube having a low voltage drop designed for service in power supplies delivering high output currents. The ratings and characteristics are identical with those of type 83-V.

(At 200 ma. output current per plate)

AVERAGE TUBE VOLTAGE DROP



BOTTOM VIEW OF SOCKET


25

volts

FULL WAVE RECTIFIER - CONDENSER OR CHOKE INPUT FILTER

Heater Voltage	5 a <b>-c</b>	volts
Heater Current	2	amp
Maximum A-C Voltage per Plate (RMS)	400	volts
Maximum Inverse Peak Voltage	1100	volts
Maximum Peak Plate Current	700	ma
Maximum D-C Output Current	200	ma.

The cathode is connected within the tube to the center of the heater.



RAYTHEON ENGINEERING SERVICE

#### 5W4 **5W4G**

5W4 MT8B BULB

/ OD

#### **RAYTHEON**

#### 5W4 **5W4G**

TWIN DIODE
FULL WAVE HIGH VACUUM RECTIFIER
Filament Type Metal Bulb-5W4

Glass Bulb-5W4G



The 5W4 is a full wave high vacuum type rectifier tube designed for service in power supplies delivering low output

5W4

60

FULL WAVE RECTIFIER Condenser Input Filter

Filament Voltage (a-c) Filament Current Max. A-C Voltage (RMS)

volts 3/K amp volts volta


(per plate)


Max. Inverse Peak Voltage 1000

Max. D-C Output Current 110

1.5 350

5W4G BOTTOM VIEW OF SOCKET






TWIN DIODE
FULL WAVE HIGH VACUUM RECTIFIER
Filament Type Glass Bulb

The 5X40 is a high vacuum type full wave rectifier tube designed for service in power supplies delivering high output currents. The ratings and electrical characteristics are identical with those of the types 5U4G and 5Z3.




BOTTOM VIEW OF SOCKET




FULL WAVE RECTIFIER
Condenser or Choke Input Filter

Filament Voltage	5 a-c	volts
Filament Current	3	amp
Maximum A-C Voltage per Plate (RMS)	500	volts
Maximum Inverse Peak Voltage	1400	volts
Maximum D-C Output Current	250	ma

AVERAGE TUBE VOLTAGE DROP 61 volts (At 250 ma. output current)



TWIN DIODE HIGH VACUUM RECTIFIER



FULL WAVE Filament Type Glass Bulb

The 5736 is a full wave high vacuum type rectifier tube designed for service in power supplies for a-c operated receivers. The ratings and electrical characteristics are identical The 5Y3G is with those of the type 80.



BOTTOM VIEW OF SOCKET

FULL WAVE RECTIFIER - CONDENSER INPUT FILTER

Filament Voltage	5 a-c	volts
Filament Current	2	amp
Maximum A-C Voltage per Plate (RMS) 3	300 400	volts
Maximum Inverse Peak Voltage	1000 1100	volts
Maximum Peak Plate Current 4	400 350	me.
Maximum D-C Output Current	125 110	ma.

FULL WAVE RECTIFIER - CHOKE INPUT FILTER\*

Filament Voltage Filament Current Maximum A-C Voltage per Flate (RMS) Maximum Inverse Peak Voltage Maximum Peak Plate Current Maximum D-C Output Current	5 a-c 2 550 1500 300 135	volts amp volts volts ma ma
maximum D=C Output Current	199	mex

AVERAGE TUBE VOLTAGE DROP 60 volts (At 135 ma. output current per plate)

\*Input choke must be at least 20 henries. than 0.1 µf. may be used. An input condenser of not more

For characteristic curves refer to the type 80.

#### **5Y4G**

#### **RAYTHEON**

**5Y4G** 



TWIN DIODE HIGH VACUUM RECTIFIER FULL WAVE Filament Type Glass Bulb

The 5Y4G is a full wave high vacuum type rectifier tube designed for service in power supplies for a-c operated receivers. The ratings and electrical characteristics are identical with those of the type. with those of the type 80.



BOTTOM VIEW OF SOCKET

FULL WAVE RECTIFIER - CONDENSER INPUT FILTER

Filament Voltage		5 a-c	volts
Filament Current		2	amp
Maximum A-C Voltage per Plate (RMS)	300	400	volts
Maximum Inverse Peak Voltage	1000	1100	volts
Maximum Peak Plate Current	400	350	ma.
Maximum D-C Output Current	125	110	m <b>a</b>

FULL WAVE RECTIFIER - CHOKE INPUT FILTER\*

Filament Voltage Filament Current Maximum A-C Voltage per Plate (RMS) Maximum Inverse Peak Voltage Maximum Peak Plate Current Maximum Pec Cutrut Current	2 550 1500 300	volts amp volts volts ma
Maximum D-C Output Current	135	ma

AVERAGE TUBE VOLTAGE DROP 60 volts (At 135 ma. output current per plate)

\*Input choke must be at least 20 henries. than 0.1 uf. may be used. An input condenser of not more

For characteristic curves refer to the type 80.

ST 16 BULB

#### **RAYTHEON**

TWIN DIODE
FULL WAVE HIGH VACUUM RECTIFIER
Filament Type Glass Bulb




The 523 is a high vacuum type full wave rectifier tube designed for service in power supplies delivering high output ourrents. The ratings and electrical characteristics are identical with those of the types 5U4G and 5X4G.

BOTTOM VIEW OF SOCKET

FULL WAVE RECTIFIER Condenser or Choke Input Filter

Filament Voltage	5 a <b>⊸c</b>	volts
Filament Current	3	amp
Maximum A-C Voltage per Plate (RMS)	500	volts
Maximum Inverse Peak Voltage	1400	volts
Maximum D-C Output Current	250	ma
•		

AVERAGE TUBE VOLTAGE DROP 61 volts (At 250 ma. output current)



TWIN DIODE

FULL WAVE HIGH VACUUM RECTIFIER Heater Type Metal Bulb

66 (2\H


The 5Z4 is a full wave high vacuum type rectifier tube having a low voltage drop designed for service in power supplies for a-c operated receivers.

FULL WAVE RECTIFIER - CONDENSER OR CHOKE BOTTOM VIEW OF SOCKET INPUT FILTER

Heater Voltage
Heater Current
Maximum A-C Voltage per Plate (RMS)
Maximum Inverse Peak Voltage 5 volts amp 2 400 1100 volts Maximum D-C Output Current 125 ma


AVERAGE TUBE VOLTAGE DROP 20 volts (At 125 ma. output current per plate)

The cathode is connected to the heater within the tube.



RAYTHEON ENGINEERING SERVICE

TRIODE



POWER AMPLIFIER
Filament Type Glass Bulb

The 6A3 is a triode type power amplifier tube designed for service in the output stage of storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the type 6B4G.



BOTTOM VIEW OF SOCKET

#### RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	1.0	amp
Maximum Plate Voltage	325	volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	16	μμ <b>£</b>
Input	7	μμ <b>1</b>
Output	5	$\mu\mu$ f

#### AMPLIFIER - CLASS A


Plate Voltage Grid Bias* Amplification Factor	250 max. -45 4.2	volts volts
Plate Resistance	80 <b>0</b>	ohm <b>s</b>
Transconductance	<b>52</b> 50	umhos
Plate Current	60	ma.
Load Resistance	2500	ohms
Power Output (5% second harmonic)	3.2	watts

#### AMPLIFIER - CLASS AB - PUSH-PULL - TWO TUBES

Plate Voltage	Fixed-Bias 325	Self-Bias 325	
Grid Bias*	-68	323	volts volts
Self-Bias Resistor	- 00	750	ohms
No-Signal Plate Current (per tube)	40	40	ma.
Load Resistance (plate to plate)	3000	5000	ohm <b>s</b>
Power Output	15	1.0	watts
Total Harmonic Distortion	2.5	5	percent

\*Grid bias measured from midpoint of a-c operated filament.

For additional curves refer to the type 6B4G.



STIA BULL

5 PRONG MED BASE MAX

#### PENTODE

POWER AMPLIFIER Filament Type Glass Bulb

The 6A4/LA is a pentode type power amplifier tube designed for service in the output stage of storage battery operated receivers.



RATINGS BOTTOM VIEW OF SOCKET


Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum Plate Voltage	200	volts
Maximum Sameen Voltage	200	volts

#### AMPLIFIER - CLASS A

Plate Voltage	100	135	180	volts
Screen Voltage	<b>1</b> 00	135	<b>1</b> 80	volts
Grid Bias*	-6.5	-9	-12	volts
Amplification Factor (approximate)	100	100	100	
Plate Resistance	83250	52600	45500	ohm <b>s</b>
Transconductance	1200	1900	2200	μ <b>m</b> ho <b>s</b>
Plate Current	9	14	22	ma
Screen Current	1.6	2.5	3.9	ma
Load Resistance	11000	9500	8000	ohms
Power Output	0.31	0.7	1.4	watts
Total Harmonic Distortion	9	9	9	percent

AMPLIFIER - CLASS AB - PUSH-PULL - TWO TUBES - SELF-BIAS

\*Grid bias measured from negative end of d-c operated filament.If the filament is a-c operated, the tabulated values of grid bias should be increased by 4 volts and be referred to the mid-point of the filament.



ST 16 BULB


2 TO MAX

8 PRONG MEDIUM OCTAL BASE

TRIODE

POWER AMPLIFIER Heater Type Glass Bulb

6A5G is a triode type power amplifier tube designed for service in the output stage of storage battery or a-c operated receivers.



RATINGS

BOTTOM VIEW OF SOCKET

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage

6**.3** 1.25 325 volts volts

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate 16 uu.f Input uuf Output


AMPLIFIER - CLASS A

Plate Voltage Grid Bias 250 max. volts -45 4.2 800 volts Amplification Factor Plate Resistance ohms Transconductance 5250 umhos Plate Current Load Resistance 60 me. 2500 ohms Power Output (5% second harmonic) 3.75 watts

AMPLIFIER - CLASS AB - TWO TUBES

Plate Voltage Grid Bias	Fixed-Bias 325 -68	Self-Bias 325	volts
Self-Bias Resistor		850	ohm <b>s</b>
No-Signal Plate Current (per tube)	40	40	ma.
Load Resistance (plate to plate)	3000	5000	ohms
Total Harmonics	2.5	5	p <b>ercent</b>
Power Output	<b>1</b> 5	10	watts


The cathode is connected internally to the mid-point of the heater and to pin #8.



STIA BULB T PRONG MER BRSE 855 DIR PII CIRCLE

TWIN TRIODE POWER AMPLIFIER Heater Type Glass Bulb

The 6A6 is a twin triode type amplifirne can list win triode type amplifi-er tube designed for service as a Class B power amplifier in the output stage of storage battery or a-c oper-ated receivers. The ratings and elec-trical characteristics are identical with those of the types 6N7 and 6N7G.



RATINGS

# BOTTOM VIEW OF SOCKET

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.8	amp
Maximum Plate Voltage	300	volts
Maximum Peak Plate Current (per plate)	125	ma.
Maximum Average Plate Dissipation	10	watts

AMPLIFIER - CLASS B


Plate Voltage	250	300	volts
Grid Bias	0	0	volts
No-Signal Plate Current (per plate)	14	17.5	ma
Load Resistance (plate to plate)	8000	10000	ohms
Power Output (approximate)	8	10	watts
(With average power input = 350 mw.	grid	to grid	.)

AMPLIFIER - CLASS A - DRIVER TRIODES CONNECTED IN PARALLEL

LTate Actrage	250	294	volts
Grid Blast	-5	-6	volts
Amplification Factor	35	35	
Plate Resistance	11300	11000	ohms
Transconductance	3100	3200	umhos
Plate Current	6	7	ma
Load Resistance - Depends on the design of the followin	g Clas	s Bamp	lifier.
Usually between 20000 and 40000 ohms.		•	
Power Output (approximate)		400	mw

†The d-c resistance in the grid circuit should not exceed 0.5 megohm with self-bias or 0.1 megohm with fixed-bias.

For additional curves refer to the type 6N7G.



ST 12-D BUN B

T PRONG MALL BASE

# HEPTODE PENTAGRID CONVERTER Heater Type Glass Bulb

The 6A7 is a pentagrid type converter tube designed for service as a combined oscillator and mixer in storage battery or a-o operated superheterodyne receivers. The ratings and electrical characteristics are identical with those of the types 6AS and 6ASG.



BOTTOM VIEW OF SOCKET



812

Heater Voltage (a-c or	d-c)6.3	volts
Heater Current	0.3	amp
Max. Plate Voltage	250	volts
Max. Screen Voltage	100	volts
Max. Grid #2 Voltage	200	volts
Max. Grid #2 Supply	250 <b>†</b>	volts
Min. Grid #4 Bias	<b>-</b> 3	volts
Max. Cathode Current	1.4	ma

# DIRECT INTERELECTRODE CAPACITANCES.


Grid #4 to Flate Grid #4 to Grid #2 Grid #4 to Grid #1 Grid #1 to Grid #1 Grid #1 to Grid #2 Grid #4 to all other Elements (R-F Input) Grid #1 to all other Elements (Osc. Input) Grid #2 to all other Elements (Osc. Output) Flate to all other Elements (Mixer Output)	0.3* 0.15* 0.16* 1.0 8.5 7 5.5	դող Գոր Գոր Գոր Գոր Գոր Գոր Գոր Գոր Գոր Գոր
--	--	---

#### FREQUENCY CONVERTER - SUPERHETERODYNE CIRCUIT

Plate Voltage Screen (Grids #3 and #5) Voltage Anode Grid (#2) Voltage	100 50 100	250 <b>1</b> 00	volts volts volts
Anode Grid Supply Voltage		250 <b>†</b>	volts
Control Grid (#4) Bias	-1.5	-3	volts
Oscillator Grid Resistor	50000	50000	ohms
Plate Resistance	0.5	0.3	megohm
Conversion Transconductance	360	550	umhos
Plate Current	1.1	3.5	ma
Screen Current	1.3	2.7	ma
Anode Grid Current	8.0	4.0	ma.
Oscillator Grid Current	0.25	0.4	m <b>a</b> .
Control Grid Bias (approximate)	-20	-45	volts
(For Conversion Transconductance =	2 μmhos)		

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

†Applied through a 20000 ohm series resistor, bypassed by a 0.1  $\mu f$  condenser. \*With tube shield.



RAYTHEON ENGINEERING SERVICE

# **6A8 6A8G**

# RAYTHEON

# **6A8 6A8G**



HEPTODE PENTAGRID CONVERTER

Metal Bulb-648

The 6A8 is a pentagrid type converter tube designed for service as a combined oscillator and mixer in storage battery or a-c operated superheterodyne receivers. The ratings and electrical characteristics are identical with those of the type 6A7.





DIRECT INTERELECTRODE CAPACITANCES



6ABG BASING SAME AS 6AB EXCEPT NO CONN. TO PIN #1

BOTTOM VIEW OF SOCKET



		6A8*	6A8G**	
Grid #4 to Plate		0.03	0.3	цц <b>£</b>
Grid #4 to Grid #2		0.1	0.2	uuf
Grid #4 to Grid #1		0.09	0.2	uuf
Grid #1 to Grid #2		0.08	1.3	uu <b>t</b>
Grid #4 to all othe	r El.(r-f input)	12.5	10	uuf
Grid #1 to all othe	r El. (osc.input)	6.5	6	11.L
Grid #2 to all othe	r El. (osc.output)	5	5	<b>ևև</b> £
Plate to all othe	r El. (mix.output)	12.5	10	μμ <b>f</b>

#### FREQUENCY CONVERTER - SUPERHETERODYNE CIRCUIT


D1-4- V-14	100	050	
Plate Voltage	100	250	volts
Screen (Grids #3 and #5) Voltage	50	<b>1</b> 00	volts
Anode Grid (#2) Voltage	100		volts
Anode Grid Supply Voltage		250+	volts
Control Grid (#4) Bias	7 6		
	-1.5	<b>-</b> 3	volts
Oscillator Grid Resistor	50000	50000	ohms
Plate Resistance	0.6	0.3	megohm
Conversion Transconductance	360	550	umhos
Plate Current	1.1	3.5	ma
Screen Current	1.3	2.7	ma.
Anode Grid Current	2.0	4.0	ma.
Oscillator Grid Current			
	0.25	0.4	ma
Control Grid Bias (approximate)	-20	<b>-4</b> 5	volts
(For Conversion Transconductance = 2 umhos)			

The voltage between heater and catho where they are not directly connected. cathode should be kept as low as possible

\*With shell connected to cathode.

\*\*With tube shield connected to cathode.

†Applied through a 20000 ohm series resistor, bypassed by a 0.1 uf condenser.



TA RIII B


6 PRONG SMALL BA

# RAYTHEON

# **6AB5**

CATHODE RAY TUNING INDICATOR Reater Type

Glass Bulb



MAX The 6AB5 is a ing

3<u>9"</u>MAX.

The 6AB5 is a high vacuum type indica-tor tube designed for service as a tun-ing indicator in radio receivers requira low heater current tube.


BOTTOM VIEW OF SOCKET RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Leater Current	0.150	amp
Lax. Plate Supply Voltage	135	volts
Lax. Target Voltage	135	volts

#### TUNING INDICATOR

Plate Supply Voltage	135	volts
Target Voltage	135	volts
Plate Resistor	0.25	megohm
Target Current (approximate)	4.5	ma
Plate Current (zero bias )	0.5	ma
Grid Bias for Shadow Angle = 00(approx.)	-7.5	volts
Grid Bias for Shadow Angle =900(approx.)	0	volts

The 6AB5 is a high-vacuum tube designed to visually indicate the effect of changing the control grid bias. The shaded pattern produced on the fluorescent target varies through an angle from 90° to approximately 0° as the control voltage is varied. The voltage on the shadow control electrode, the extension of the triode plate between the cathode and target, controls the extent of the shaded area. The voltage of the shadow control electrode is determined by the voltage of the control grid of the triode connected as a d-c amplifier. Thus the control grid voltage determines the extent of the shadow. An increase of control grid bias thus increases the shadow control voltage and decreases the shadow while a decrease of bias increases the shadow. In practical use the control grid voltage is obtained from a suitshade point in the AVC network. able point in the AVC network.



# 6AC5G

TRIODE
POWER AMPLIFIER
Heater Type Glass Bulb

The 6AC5G is a high-mu triode power amplifier tube designed for positive bias class Ag operation particularly in a direct or dynamic coupled circuit using a type 76 driver tube. Two 6AC5G tubes are also adapted for use in a Class B stage.

\*\*RATINGS\*\*

6 PRONG\*\*

SAMAL ONE MAXIMUM Plate Voltage

Maximum Plate Voltage

Maximum Plate Current

Maximum Plate Current



BOTTOM	VIEW	OF SOCKET
--------	------	-----------

RATINGS	2011011	TIET OF COUNTY
Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.4	amp
Maximum Plate Voltage	250	vclts
Maximum Peak Plate Current	110	ma.
Maximum Plate Dissipation	10	watts

🛨 AMPLIFIER - CLASS A

Plate Voltage	250	volts
Grid Bias	+13	volts
Amplification Factor	125	
Plate Resistance	36700	ohms
Transconductance	3400	umhos
Plate Current	32	ma
Grid Current	5	m <b>a</b>
	· ·	1.161

#### AMPLIFIER - CLASS A - DIRECT OR DYNAMIC COUPLED


	gle Tube - Type	Push-Pull-T		
	Driver	2-Type 76 Drivers 6	2-Type	
Plate Supply Voltage	250	250	250	volts
Grid Bias	*	*	*	volts
No-Sig. Plate Current	32	64	48	ma
Max. Sig. Plate Current		76	72	ma
No-Sig. Driver Plate Current	5 <b>.5</b>	10	8	ma
Max. Sig. Driver Plate Current		19	20	ma
Load Resistance	7000	10000(P-P)	10000 (P-P)	ohms
Max.Signal Voltage RMS (Driver)	16.5	47 (G-G)	50 (G-G)	volts
Total Harmonics	10	10	10	percent
Power Output	3.7 🕈	9.5	9.5	watts


#### AMPLIFIER - CLASS B - TWO TUBES

AMPLIFIER - CLASS B - TWO TUBES		
Plate Voltage	250	volts
Grid Bias	0	volts
Signal Peak Voltage (grid to grid)	70	volts
No-Signal Plate Current	5	ma.
Load Resistance (plate to plate)	10000	ohms
Power Output (approximate)	8	watts
(With peak input of 950 mw. grid to grid)	-	44005

\* No external grid bias is required as the direct or dynamic coupled circuit automatically supplies the proper bias to both tubes. The total d-c resistance in the grid circuit of the type 76 driver tube should not exceed 1.0 megoim.

† Maximum power output at start of driver grid current is 4.3 watts with total harmonic distortion of approximately 16%.





# TRIODE POWER AMPLIFIER Filament Type Glass Bulb

The 6B4G is a triode type power amplifier tube designed for service in the output stage of storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the type 6A3.



BOTTOM VIEW OF SOCKET

#### RATINGS

1.0	amp
325	volts
	1.0 325

# DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	16	ոս <b>ք</b>
Input	7	$\mu\mu f$
Output	5	μμ <b>1</b>

#### AMPLIFIER - CLASS A


Plate Voltage Grid Bias* Amplification Factor	250 max. -45 4.2	volts volts
Plate Resistance	800	ohms
Transconductance	5250	μmho <b>s</b>
Plate Current	60	ma
Load Resistance	2500	ohms
Power Output (5% second harmonic)	3.2	watts

# AMPLIFIER - CLASS AB - PUSH-PULL - TWO TUBES

Plate Voltage	Fixed-Bias 325	Self-Bias 325	volts
Grid Bias*	-68		volts
Self-Bias Resistor		750	ohms
No-Signal Plate Current (per tube)	40	40	me.
Load Resistance (plate to plate)	3000	5000	ohma
Power Output	15	10	wat <b>ts</b>
Total Harmonic Distortion	2.5	5	percent

\*Grid bias measured from midpoint of a-c operated filament.

For additional curves refer to the type 6A3.



STI4 BULB

DUO-TRIODE
DIRECT COUPLED POWER AMPLIFIER
Heater Type Glass Bulb

The 6B5 is a direct coupled power amplifier tube designed for service in the output stage of storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the type 6NGC.



BOTTOM VIEW OF SOCKET

RATIN	3S
-------	----

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.8	amp
Maximum Plate Voltage	325	volts

## AMPLIFIER - CLASS A

250	300	325	volts
250	300	325	volts
0	0	0	volts
	58		
	24100		ohm <b>s</b>
	2400		μmhos
33	45	51	ma.
6.5	8	9	ma
7000	7000	7000	ohms
5	5	5	percent
2.5	4	5.2	watts
13.5	15	17	volts
	250 0 33 6.5 7000 5 2.5	250 300 0 58 24100 2400 33 45 6.5 8 7000 7000 5 5 2.5 4	250 300 325 0 0 0 58 24100 2400 33 45 51 6.5 8 9 7000 7000 7000 5 5 5 2.5 4 5,2


#### AMPLIFIER - CLASS A - PUSH-PULL - TWO TUBES

Output-Plate Voltage	250	300	325	volts
Input-Plate Voltage	250	300	325	volts
Grid Bias	0	0	0	volts
Output-Plate Current (per tube) Input-Plate Current (per tube) Load Resistance (plate to plate)	35	45	51	ma
	6.5	8	9	ma
	10000	10000	10000	ohms
Total Harmonic Distortion Power Output Signal Voltage RMS (grid to grid)	5	5	5	percent
	8.5	10	13.5	watts
	38	38	42	volts

The voltage between heater and cathode should not exceed 50 volts and in no case should the heater be left floating.

If a grid resistor is used its value should not exceed 0.5 megohm.

For additional curves refer to the type 6N6G.



RAYTHEON ENGINEERING SERVICE

DUO-DIODE TRIODE
DETECTOR AMPLIFIER
Heater Type Glass Bulb



The 6B6G is a duo-diode triode type amplifier tube designed for service as a combined diode detector, AVC rectifier and resistance coupled audio frequency amplifier in storage battery or a -o operated receivers. The ratings and electrical characteristics are identical with those of the type 75.



BOTTOM VIEW OF SOCKET

#### RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum Plate Voltage	250	volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	1.3	uu£
Inpu <b>t</b>	2.7	uu <b>f</b>
Output	4.5	uuf


#### AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage Grid Bias	250 <b>-</b> 2	volts volts
Amplification Factor	100	
Plate Resistance	91000	ohm <b>s</b>
Transconductance	1100	umhos
Plate Current	1	me.

## DIODE SECTION

The two diodes are independent of each other and of the triode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection and the other diode used as a rectifier to obtain delayed AVC voltage.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



DUO-DIODE PENTODE
DETECTOR AMPLIFIER
Heater Type Glass Bulb

The 6B7 is a duo-diode pentode type amplifier tube designed for service as a combined diode detector, AVC rectifier, and high or audio frequency amplifier in storage battery or a-o operated receivers.



BOTTOM YIEW OF SOCKET

RATINGS
---------

Maximum Screen Voltage 125 volts	Heater Voltage (a-c or d-c) 6.3 Heater Current 0.3 Haximum Plate Voltage 250 Laximum Soreen Voltage 125	volts amp volts volts
----------------------------------	---	--------------------------------

DIRECT INTERELECTRODE CAPACITATICES - PENTODE SECTION

Grid to Plate	0.007 max.*	դր <b>ք</b>
Input	3.5	դր <b>ք</b>
Output	9.5	դրք

AMPLIFIER - CLASS A - PENTODE SECTION

Plate Voltage	100	180	250	250	volts
Screen Voltage	100	75	100	125	volts
Grid Bias	-3	-3	-3	-3	volts
Amplification Factor	285	840	800	730	
Plate Resistance	0.3	1	0.8	0.65	megohm
Transconductance	950	840	1000	1125	umhos
Plate Current	5.8	3.4	6	9	m <b>a</b> .
Screen Current	1.7	0.9	1.5	2.3	ma
Grid Bias	-17	-13	-17	-21	volts
(There was the sale assessment assets					

(For cathode current cutoff)
AMPLIFIER - CLASS A - RESISTANCE COUPLED - PENTODE SECTION


Plate Supply Voltage	250	250	250	valts
Screen Voltage	45	50	100	volts
Grid Bias	<b>-</b> 5	-4.5	-3	volts
Plate Resistor	0.5	0.25	0.027	megohm
Plate Current	0.25	0.65	5.4	ma

DIODE SECTION

The two diode units are independent of each other and of the pentode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVC voltage.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*With tube shield.



RAYTHEON ENGINEERING SERVICE



DUO-DIODE PENTODE
DETECTOR AMPLIFIER
Metal Bulb Heater Type

The 6B8 is a duo-diode pentode type amplifier tube designed for service as combined diode detector, AVC rectifier and r-f, i-f, or a-f amplifier.

BOTTOM VIEW OF SOCKET

#### RATINGS

Heater Voltage 6,3 volts
Heater Current 0,3 amp
Max. Plate Voltage 250 volts
Max. Screen Voltage 125 volts

DIRECT INTERELECTRODE CAPACITANCES - PENTODE SECTION (Shell connected to cathode)


Grid to Plate 0.005 max. uµf Input 6 uµf Output 9 uµf

#### AMPLIFIER - CLASS A - PENTODE SECTION

Plate Voltage	250		volts
Screen Voltage	125		volts
Grid Bias	-3		volts
Amplification Factor	800	approx.	
Plate Resistance	0.6	approx.	megohm
Transconductance	1325		μ <b>m</b> ho <b>s</b>
Plate Current	10		ma
Screen Current	2.3		me.
Grid Bias for Cathode Current Cutoff	-21	approx.	volts

# DIODE SECTION

The two diode units are independent of each other and of the pentode section except for the common cathode. The diode units may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVC voltage.



8 PRONG SMALL OCTAL BASE

DUO-DIODE PENTODE DETECTOR AMPLIFIER

Heater Type Glass Bulb

The 6B8G is a duo-diode pentode type amplifier tube designed for service as combined diode detector, AVC rectifier and r=1, i=f, or a=f amplifier.



RATINGS

4 FE MAX

Heater Voltage Heater Current Max. Plate Voltage Max. Screen Voltage 6.3 volts 0.3 amp volts

volts

DIRECT INTERELECTRODE CAPACITANCES - PENTODE SECTION (With close fitting shield connected to cathode)

0.007 3.5 9.5	max.	դդդ դդդ դդդ
	3.5	

AMPLIFIER - R-F or I-F - PENTODE SECTION


Plate Voltage Screen Voltage Grid Bias Amplification Factor Flate Resistance Transconductance Flate Current	100 100 -3 285 0,3 950 5,8	180 75 -3 840 1 840 3,4	250 100 -3 800 0.8 1000 6	250 125 -3 730 0.65 1125 9	volts volts volts megohm µmhos ma
Screen Current Grid Bias (For Cathode Current Cutoff)	1.7	0.9	1.5	2.3	ma
	-17	-13	-17	-21	volts

AMPLIFIER - RESISTANCE COUPLED - PENTODE SECTION

Plate Supply Voltage Screen Voltage	250 45	250 50	250 100	volts volts
Grid Bias	<b>-5</b>	-4.5	<b>-3</b>	volts
Plate Resistor	0.5	0.25	0.027	megohm
Plate Current	0.25	0.65	5.4	ma

#### DIODE SECTION

The two diode units are independent of each other and of the pentode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVC voltage.



# **6C5** 6C5G

# RAYTHEON

# **6C5 6C5G**



TRIODE DETECTOR OR AMPLIFIER
Heater Type
L Bulb-6C5 Glass Bulb-6C5G Metal Bulb-605

The 605 is a triode type amplifier tube designed for service as a detector or amplifier in storage battery or a-c op-


erated receivers.

# RATINGS

Heater Voltage (a-c or d-c)6.3 volts Heater Current 0.3 amp Maximum Plate Voltage 250 volts

(**3**/p (2)H 605 8

BOTTOM VIEW OF SOCKET 6C5G - INT. SHIELD CONNECTED TO#1 PIN



DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate 1.8 Input Output 4.0 no.c 605# 13 9.5 6060\*\* 2.5 uuf

AMPLIFIER - CLASS A

Plate Voltage Grid Bias 250 volts -8 volts 20 Amplification Factor Plate Resistance 10000 ohms Transconductance 2000 umhos Plate Current

AMPLIFIER - CLASS A - RESISTANCE COUPLED

250 volts Plate Supply Voltage Grid Bias (approximate) -5 volts 50000 to 10000 Plate Resistor ohms Plate Current ma Voltage Amplification 14 Voltage Output (5% second harmonic) RMS 42 volts

DETECTOR - BIASED TYPE

Plate Voltage Grid Bias (approximate) Plate Current 250 -17 Adjusted to 0.2 ma. with no signal

DETECTOR - GRID LEAK TYPE

Plate Voltage Grid Grid Leak Resistance Grid Condenser


45 to 100 volta Return to Cathode 0.1 to 1.0 0.00005 to 0.0005 megohm иf

voIts

volta

The voltage between heater and cathode should be kept as low as possible where they are not directly connected. \*With shell connected to cathode.

\*Internal shield connected to cathode.



PENTODE

DETECTOR OR ALPLIFIER Glass Bulb Heater Type

The 606 is a pentode type amplifier tube designed for service as a detector or high frequency amplifier in storage bat-

tery or a-c operated receivers.



ST 12-F BILLS

19" 00 18 Mar

NUX

Heater Voltage (a-c or d-c) 6.3 volts
Heater Current 0.3 amp
Maximum Plate Voltage 250 volts Maximum Screen Voltage 100 volts

BOTTOM VIEW OF SOCKET

(2 P

DIRECT INTERELECTRODE CAPACITANCES

Pentode Connection C.007 max.\* 5.0 Triode Connectiont μμf Grid to Plate 2.0 3.0 Input Output uuf  $\mu \mu \mathbf{f}$ 6.5

AMPLIFIER - CLASS A

Pentode Connection Triode Connectiont 100 250 volts Plate Voltage 250 volts 100 Screen Voltage -3 -3 -8 volts Grid Bias Connected to Catnode at Socket Suppressor 1500 min. 1.5 min. 20 approx. Amplification Factor 1185 0.0105 megohm 1900 umhos 1.5 1225 Plate Resistance 1185 Transconductance 2 2 6.5 ma Plate Current Screen Current 0.5 0.5 Grid Bias (approximate) -7 volts (For cathode current cutoff)


## DETECTOR - BIASED TYPE

Plate Supply Voltage Screen Voltage Grid Bias	100 12 -1.16	100 30 -1.83	250 50 -1.95	250 <b>1</b> 00 <b>-4.3</b>	volts volts volts
Cathode Resistor	18000	10000	3000	10000	ohms
Suppressor		Conn	ected to	Cathode at	Socket
Cathode Current (no signal)	0.063	0.183	0.65	0.43	ma
Plate Resistor	1.0	0.25	0.25	0,5	megohm
Blocking Condenser	0.01	0.01	0.03	0.03	μ£
Grid Resistor (for following tube)	1.0	0.5	0.25	0.25	megohm
R-F Signal Voltage (RMS)	1.05	1.6	1,18	1.37	volts
Output Peak Voltage	17	17	17	17	volts
(At grid of following tube with s	ignal mo	odulat <b>e</b> d	. 20%)		

The shield in the dome of the tube is connected internally to the cathode. The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*With tube shield.

†Grids #2 and #3 connected to plate.



# RAYTHEON ENGINEERING SERVICE

8 PRONG SMALL OCTAL BASE TWIN TRIODE

Heater Type

The 608G is a twin triode type amplifier tube designed for service as voltage amplifier or phase inverter. The triode units are independent of each other as the elements of each triode are brought out to separate terminals.



BOTTOM VIEW OF SOCKET



Heater Voltage (a-c or d-c)6.3 volts
Heater Current 0.3 amp
Max. Plate Voltage 250 volts

DIRECT INTERELECTRODE CAPACITANCES

T	riode	Li	Triode	R	
(Triode	R to	Cathode)	(Triode L to	Cathode)	
Grid to Plate	2.5		2.4		$\mu\mu\mathbf{f}$
Input	3.4		2.5		$\mu\mu\mathbf{f}$
Output	3.5		3.9		$\mu\mu f$
Grid to Grid		0.	L		uuf
Plate to Plate		1.5	5		$\mu\mu\mathbf{f}$

Glass Bulb


AMPLIFIER - CLASS A - EACH TRIODE

Plate Voltage	250	volts
Grid Bias	-4.5	volts
Amplification Factor	38	
Plate Resistance	26000	ohms
Transconductance	1450	umhos
Plate Current	3.1	ma

#### PHASE INVERTER

111100 1111011			
Plate Supply Voltage Grid Bias Plate Current (per plate) Plate Resistor (per plate)	250 -3 1.7 0.05	250 -3 1 0.1	volts volts ma megohm
Grid Resistor (following tubes)	0.1	0.5	megohm
Maximum Output Voltage RMS (G to G)	60	80	volts
Cathode Resistor (common to both triodes)	900	1500	ohms

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



PENTODE

REMOTE CUTOFF AMPLIFIER

Heater Type Glass Bulb

The 6D6 is a pentode type amplifier tube with remote cutoff characteristics designed for service as a high frequency amplifier or mixer in storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the type 6UVG.



BOTTOM VIEW OF SOCKET

## RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum Plate Voltage	250	volts
Maximum Screen Voltage	100	volts

#### DIRECT INTERELECTRODE CAPACITANCES

1 դա1 1 դա1 1 դա1
)

#### AMPLIFIER - CLASS A

Plate Voltage	100	250	volts
Screen Voltage	100	100	volts
Grid Bias	-3	-3	volts
Supressor	Connected to	Cathode at	Socket
Amplification Factor	375	1280	
Plate Resistance	0.25	0.8	megohm
Transconductance	1500	1600	umhos
Plate Current	8	8.2	ma
Screen Current	2.2	2	ma.
Grid Bias for Transconductance = 2 µmhos	<b>-</b> 50	-50	volts

#### MIXER - SUPERHETERODYNE CIRCUIT


Plate Voltage Screen Voltage Grid Bias	100 100 -10		250 100 -10		volts volts volts
Suppressor	Connected	to	Cathode	at	

The grid bias is not critical with an oscillator peak swing 1 voltless than the grid bias.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

The shield in the dome of the tube is connected internally to the cathode.

For additional curves refer to the type 6U7G.



RAYTHEON ENGINEERING SERVICE

ST 12-D BULE

8 PRONG SMALL OCTAL BASE 

# HEPTODE

PENTAGRID CONVERTER Heater Type Glass Bulb

The 6DSG is a pentagrid type converter tube designed for service as a combined oscillator and mixer in storage battery or a-c operated receivers requiring alow heater current tube.



Heater Voltage (a-c or	d-c)6.3 volts
Heater Current	0.150 amp
Max. Plate Voltage	250 volts
Max. Sareen Voltage	100 volts
Max. Grid #2 Voltage	200 volts
Max. Grid #2 Supply	250† volts
Min. Grid #4 Blas	-3 volts
Max. Cathode Current	13 ma



BOTTOM VIEW OF SOCKET

# DIRECT INTERELECTRODE CAPACITANCES\*


Grid #4 to Plate Grid #4 to Grid #2 Grid #4 to Grid #1 Grid #4 to Grid #1	0.3 0.2 0.2	րր <b>ք</b> Արդ
Grid #1 to Grid #2  Grid #4 to all other Elements (R-F input)  Grid #1 to all other Elements (Osc. input)	1.3 8.8 6	դդդ դդդ դդդ
Grid #2 to all other Elements (Oso. output) Plate to all other Elements (Mixer output)	5 11	μμ <b>ք</b> μμ <b>ք</b>

#### FREQUENCY CONVERTER - SUPERHETERODYNE CIRCUIT

Plate Voltage	135	250	volts
Screen (Grids #3 and #5) Voltage	<b>67.</b> 5	100	volts
Anode Grid (#2) Voltage	135		volts
Anode Grid Supply Voltage		250+	volts
Control Grid (#4) Bias	-3	-3	volts
Oscillator Grid (#1) Resistor	50000	50000	ohms
Plate Resistance	0.4	0.32	megohm
Conversion Transconductance	325	500	umhos
Plate Current	1.2	3.3	ma.
Screen Current	2	3.2	me.
Anode Grid Current	3.4	4	me.
Oscillator Grid Current	0.45	0.5	ma
Control Grid Bias	-25	<b>~38</b> .5	volts
(For Conversion Transconductance =	10 µmhos)	•	
Grid #1 to Grid #2 Transconductance	1150	1000	umhos
(At O volts bies on Grid #1)			•

†Applied through a 20000 ohm series resistor, bypassed by a 0.1 µf.condenser.

\*With tube shield connected to cathode.



volts

volts

5T 12-0 PULL 6 PRONG SMALL BA

CATHODE RAY TUNING INDICATOR Heater Type Glass Bulb

The 6E5 is a high vacuum type indicator tube designed for service as a tuning indicator in radio receivers.

# (KI3


#### RATINGS

MI INGS	BOTTOM VIEW OF SOCKET		
Heater Voltage (a-c or d-c)	6.3	volts	
Heater Current	0.3	amr	
Maximum Plate Supply Voltage	250	volts	
aximum Target Voltage	250	volts	
Minimum Target Voltage	90	volts	

## TUNING INDICATOR

Plate Supply Voltage Target Voltage Plate Resistor Target Current (approx.) Plate Current (zero bias) Grid Bias (approx.) (For shadow angle = 00)	100 100 0.5 4.5 0.19	200 200 1 4.5 0.19 -6.5	250 250 1 4.5 0.24	volts volts megohm ma ma volts
Grid Bias (approx.) (For shadow angle =90°)	0	0	0	volts

The 6E5 is a high vacuum tube designed to visually indicate the effect of changing the control grid bias. The shaded pattern produced on the fluorescent target varies through an angle from 90° to approximately 0° as the control voltage is varied. The voltage on the shadow control electrode the extension of the triode plate between the cathode and target, controls the extent of the shaded area. The voltage of the shadow control electrode is determined by the voltage of the control grid of the triode connected as a d-c amplifier. Thus the control grid voltage determines the extent of the shadow. An increase of control grid bias thus increases the shadow control voltage and decreases the shadow while a decrease of bias increases the shadow. In practical use the control grid voltage is obtained from a suitable point in the AVC network.



STI4 BULB

7 PRONG MER BASE .855 DIA. PIN CIRCLE TWIN TRIODE
POWER AMPLIFIER
Heater Type Glass Bulb

The 6E6 is a twin triode type power amplifier tube designed for service as a Class A push-pull amplifier in the output stage of storage battery or a-c operated receivers.



BOTTOM YIEW OF SOCKET

RATINGS


Heater Voltage (a-c or d-c) 6.3 volts
Heater Current 0.6 amp
Maximum Plate Voltage 250 volts

AMPLIFIER - CLASS A - EACH TRIODE

Plate Voltage	180	250	volts
Grid Bias	-20	-27.5	volts
Amplification Factor	6	6	
Plate Resistance	4300	3500	ohms
Transconductance	1400	1700	μmhos
Plate Current	11.5	18	ma

## AMPLIFIER - CLASS A - PUSH-PULL

Plate Voltage Grid Bias Plate Current (per plate) Load Resistance (plate to plate)	180 -20 11.5 15000 0-75	250 -27.5 18 14000	volts volts ma ohms watts
Power Output	0.75	1.6	Watts



# **6F5** 6F5G

# **RAYTHEON**

# **6F5** 6F5G



5 PROMO

OCTAL BASE

TRIODE AMPLIFIER Type Glass Bulb-6F5G Heater Metal Bulb-6F5

The 6F5 is a triode type amplifier tube designed for service as a resistance coupled audio frequency amplifier in storage battery or a-c operated receivers.

RATINGS

2015



BOTTOM VIEW OF SOCKET 6F5G-NO CONNECTION TO # 1 PIN 6.3 0.3 volts

250

amp

volts

volts

volts

ohma

ma

umhos

Heate	er Voltage (a-c or d-c) er Current mum Plate Voltage	
DIRECT	INTERELECTRODE CAPACITANCE	S
6F5* 6F5G	Grid to Plate 2.0 2.0	Ιr

Input Output 12  $\mu\mu\mathbf{f}$ 2.5 3.5 μμf


AMPLIFIER - CLASS A

Plate Voltage 250 Grid Biast Amplification Factor -2 100 Plate Resistance 66000 Transconductance 1500 Plate Current 0.9

AMPLIFIER - CLASS A - RESISTANCE COUPLED

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.


\*With shell connected to cathode †The d-c resistance in the grid circuit should not exceed 1 megchm. ‡For following tube



# **6F6** 6F6G

# **RAYTHEON**

# **6F6 6F6G**



PENTODE POWER AMPLIFIER Heater Type -6F6 Glass Bulb-6F6G Metal Bulb-6F6

The 6F6 is a pentode type power amplifier tube designed for service in the output stage of storage battery or a-o operated receivers. The ratings and electrical characteristics are identi-

cal with those of the type 42.



RATINGS

11

BOTTOM VIEW OF SOCKET 6F6G-NO CONNECTION 10 #1 PIN

Madade Connections

Heater Voltage (a-c or d-c)6.3 volts
Heater Current 0.7 amp
Maximum Plate Voltage 315 volts Maximum Screen Voltage 315 volts

6F6G ST/4 BULB	
15 OR ANAL	16 MAX. 48 MAX
7 PRONG MEDIUM OCTAL BRSE	
	12/19

AMPLIFIER - CLASS A

MILL TITL - OTHERD V				
Pen	tode Conn	ection	Triode Conn	ectiont
Plate Voltage	250	315	250 max	, volts
Screen Voltage	250	315		volts
Grid Bias	-16.5	-22	-20	volts
Amplification Factor	2001	200‡	7	
Plate Resistance	#0000	75000	2600	ohms
Transconductance	2500	2650	2700	um <b>ho</b> s
Plate Current	34	42	31	mø.
Screen Current	6.5	8		ma
Load Resistance	7000	7000	4000	ohms
Total Harmonic Dist.	7	7	5	percent
Power Output	3	5	0.85	watts

AMPLIFIER - CLASS AB - TWO TUBES
Pentode Connection

	Lettrone Com		TITOUG	COURTAGELLC	217
	Fixed-Bias	Self-Bias	Fixed-Bia	s Self-Bi	.as
Plate Voltage	375 max.	375 max.	350 max.	350 max.	volts
Screen Voltage	250 max.	250 max.			volts
Grid Bias	-26 min.		<b>-3</b> 8		volts
Self-Bias Resistor		340 min.		730 min.	ohm <b>s</b>
Signal Pk. Volt. (G to G)	82	94	123	132	volts
No-Signal Plate Current	34	54	45	50	ma
No-Signal Screen Current	5	8			ma.
Load Resistance(P to P)	10000	10000	6000	10000	ohms
Total Harmonic Dist.	5	5	7	7	percent
Power Output (approx.)#	19*	19∆	18**	14¶	watts


#With one 6F6 or 6F6G triode connected as driver operated at plate voltage of 250 volts, grid bias of -20 volts and plate load of approximately 10000

\*Input transformer ratio, primary to 1/2 secondary = 3.32 AInput transformer ratio, primary to 1/2 secondary = 2.5 \*\*Input transformer ratio, primary to 1/2 secondary = 1.67 \*\*Input transformer ratio, primary to 1/2 secondary = 1.29

†Screen connected to plate.

**‡**Approximate

For additional curves refer to the type 42.



7 PRONG SMALL BASE

Z

RATTMOS

TRIODE-PENTODE AMPLIFIER OR CONVERTER Heater Type Glass Bulb

The 6F7 is a duplex tube, combining in one bulb a triode and a remote cutoff pentode, designed for service as an oscillator and mixer or as a high frequency amplifier and second detector, in ers. The ratings and electrical characteristics are identical with those of the type 6P7G.



BOTTOM VIEW OF SOCKET

Heater Voltage (a-c or d-c) Heater Current		6.3 0.3	volts amp
DIRECT INTERELECTRODE CAPACITANCES Grid to Plate	Input	Output	
Triode Section ** 2.0 Pentode Section ** 0.008 max.*	2.5 3.2	3.0 12	րր <b>ք</b> րր <b>ք</b>


remode peorton.	O.OOO Max.	0.0	12	Tru-
AMPLIFIER - CLASS A				
	Triode Section	Pentode	Section	
Plate Voltage	100 max.	100	250 ma:	x. volts
Screen Voltage		100	100 ma:	x. volts
Grid Bias	-3	•3	-3 min	n. volts
Amplification Factor	8	300	900	
Plate Resistance	0,016	0.29	0.85	megohm
Transconductance	500	1050	1100	µmhos
Plate Current	3.5	6.3	6.5	ma
Sereen Current		1.6	1.5	ma.
Transconductance (at -35 volts bias	)	9	10	$\mu$ mhos
FREQUENCY CONVERTER				

FREQUENCY CONVERTE	R		
Maximum Plate Voltage Maximum Screen Voltage Minimum Grid Blas	100	Pentode Section 250 100 -3 #	volts volts volts
Maximum Oscillator Plate Current(a	verage) 4		ma
Typical Operation:			
Plate Voltage	1001	250	volts
SereenVoltage		100	volts
Grid Bias	+	-10 A	volts
Plate Resistance	•	2	megohm
Conversion Transconductance		300	umhos
Plate Current	2.4	2.8	ma.
Grid Current	0.15	Ö	ma.
Screen Current		0.6	me.
Oscillator Pack Voltage Input		7	volts

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*Where they are not directly connected to ground.
†Usually obtained by means of a grid leak.
#Grid bias should be at least 3 volts greater than the peak oscillator voltage applied to the pentode grid.
They be obtained from 250 volt supply through 60000 ohm series resistor.
Abbtained by means of 1700 ohm cathode resistor.

For additional curves refer to the type 6P7G.



ST 12-0 BUL B

8 PRONG SMALL OCTAL BASE


JUUU

# RAYTHEON

# 6F8G

TWIN TRIODE AMPLIFIER

Heater Type Glass Bulb





BOTTOM VIEW OF SOCKET

RATINGS

#### DIRECT INTERELECTRODE CAPACITANCES


# TRIODE L TRIODE R (Triode R to Ground)(Triode L to Ground)

Grid to Plate	4.5	4.16	1 1441
Input	3.3	3.0	μμ <b>f</b>
Output	1.5	2.0	μμ <b>ſ</b>
Grid to Grid	0.	.13	μμ <b>£</b>
Plate to Plate	1.	.2	uu£
Grid R to Plate L	0.	.2	μμ£

#### AMPLIFIER -CLASS A - EACH TRIODE

Plate Voltage	250	volts
Grid Bias	<b>-</b> 8	volts
Amplification Factor	20	
Plate Resistance (approximate)	7700	ohms
Transconductance (approximate)	2600	umhos
Plate Current	9	ma.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



CATHODE RAY TUNING INDICATOR Heater Type Glass Bulb

ST 12-P BULB

ST 12-P BULB

ST 12-P BULB

SW 7150

SW MAIL

SW 7150

SW MAIL BASE

TORO

T

The 605/605 is a high vacuum type indicator tube with remote cutoff characteristics designed for service as a tuning indicator in radio receivers. The ratings and electrical characteristics are identical with those of the type 605.




RATTINGS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum Plate Supply Voltage	250	volts
Maximum Target Voltage	250	volts
Minimum Target Voltage	90	volts


#### TUNING INDICATOR

Plate Supply Voltage Target Voltage Plate Resistor Target Current (approximate) Plate Current (zero bias) Grid Bias (approximate) (For shadow angle = 00)	100 100 0.5 4.5 0.19	200 200 1 4.5 0.19 -18.5	250 250 1 4.5 0.24	volts volts megohm ma ma volts
Grid Bias (approximate) (For shadow angle =900)	0	0	0	volts

The 665/6H5 is a high vacuum tube designed to visually indicate the effect of changing the control grid bias. The shaded pattern produced on the flurorescent target varies through an angle from 90° to approximately 0° as the control voltage is varied. The voltage on the shadow control electrode, the extension of the triode plate between the exthode and target, controls the extent of the shaded area. The voltage of the shadow control electrode is determined by the voltage of the control grid of the triode connected as a d-c amplifier. Thus the control grid voltage determines the extent of the shadow. An increase of control grid bias thus increases the shadow control voltage and decreases the shadow while a decrease of bias increases the shadow. In practical use the control grid voltage is obtained from a suitable point in the AVC network.



PENTODE
POWER AMPLIFIER
Heater Type Glass Bulb



The 6060 is a pentode type power amplifier tube designed for service in the output stage of receivers where maximum overall efficiency is required.



BOTTOM	VIEW OF SOCKET
6.3	volts
0.15	amp
180	volta
180	volts


Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage Maximum Soreen Voltage

AMPLIFIER - CLASS A

135	180	volts
135	<b>1</b> 80	volts
~6 *	<b>-9 *</b>	volts
4 <b>4</b> 0	<b>51</b> 0	ohms
<b>36</b> 0	400	
0,170	0.175	megohm
<b>21</b> 00	2300	μ <b>mhos</b>
11.5	15	ma.
2	2.5	ma.
12000	10000	രിമ്പുട
7.5	10	percent
0.6	1.1	watts
	135 -6 * 440 360 0,170 2100 11,5 2 12000 7,5	135

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\* Transformer or impedance input systems are recommended. If resistance coupling is used the d-o resistance in the grid circuit should not exceed 0.5 megchm with self-blas. With fixed-blas the d-o grid circuit resistance should not exceed 0.5 megohm under the 135 volt operating conditions or 0.05 megohm under the 180 volt conditions.



# 6H6 6H6G

# **RAYTHEON**

# 6H6 6H6G




TWIN DIODE DETECTOR

Heater Type Metal Bulb-6H6 Glass Bulb-6H6G

The 6H6 is a twin diode tube designed for service as a diode detector and AVO rectifier or as a low current rectifier in storage battery or a-c operated receivers.



BOTTOM VIEW OF SOCKET 6H6G-INT. SHIELD CONNECTED TO #1 PIN



RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum A-C Voltage per Plate (RMS)	100	volts
Maximum D-C Output Current	4	ma

#### DIRECT INTERELECTRODE CAPACITANCES

6H6* 6H6G**	Plate to Plate 0.02 max. 0.4	Plate to Cathode 1.2 1.5	րր <b>ք</b> Ար <b>ք</b>

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*With shell connected to cathode.
\*\*With internal shield connected to cathode.

# 6J5 6J5G

# **RAYTHEON**

# 6J5 6J5G




TRIODE AMPLIFIER Heater Type Letal Bulb-6J5 Glass Bulb-6J5G

The 6J5 is a triode type amplifier tube designed for service in storage battery or a-c operated receivers.



BOTTOM VIEW OF SOCKET 6J5G-NO CONNECTION TO #1 PIN



RATINGS

Heater Voltage(a-c or d-c)6.3 volts
Heater Current 0.3 amp
Maximum Plate Voltage 250 volts

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate Input Output

6J5 3.4 3.4 3.6 μμf
6J5G 3.4 3.8 3.3 μμf

AMPLIFIER - CLASS A

 Plate Voltage
 250 volts

 Grid Blas
 -8 volts


 Amplification Factor
 20

 Plate Resistance
 7700 ohms

 Transconductance
 2600 µmhos

 Plate Current
 9 ma

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.




6/7

100 MARY SASE

# PENTODE


DETECTOR OR AMPLIFIER
Heater Type Metal Bulb-6J7 Glass Bulb-6J7G



RATTNGS Heater Voltage Heater Current Max. Plate Voltage Max. Screen Voltage 6.3 0.3 250 volts amp volts



6J7G BASING SAME AS 6J7, EXCEPT SHIELD CAGE CONN. TO PIN# I BOTTOM VIEW OF SOCKET



	GRID TO H	LATE	INPUT	OUTPUT	
* 6J7	0.00	)5 max.	7	12	<b>ը</b> և <b>£</b>
**6J7G	0.00	os max.	4.5	12	$\mu\mu\mathbf{f}$
AMPLIFIER - C	LASS A				
Plate Volts	ge		100	250	volts
Screen Volt	age		100	100	volts
Grid Bias	Ü		<b>-3</b>	-3	volts
Suppressor			Connected	to Cath	node at Socket
Amplificati	on Factor		1185	1500	min.
Plate Resis	stance		1	1.5	min. megohms
Transconduc	tance		1185	1225	μmho <b>s</b>
Plate Curre	n <b>t</b>		2	2	ma
Screen Curr	ent		0.5	0.5	me.
Grid Bias			<b>-</b> 7	-7	approx. volts
(For Cathode	Current (	intoff)			-

125

volts


DETECTOR - GRID BIASED TYPE

Plate Supply Voltage	250	250	250	250	volts
Screen Voltage	50	33	100	100	volts
Grid Bias	-2	-1.7	-3.9	<b>-4.3</b>	volts
Cathode Resistor	3000	8000	4000	10000	ohms
Suppressor			Connected	to Cathode	at Socket
Cathode Current (No Signal)	0.65	0.21	0.97	0.43	me.
Plate Resistor	0,25	0.5	0.25	0.5	megohm
Blocking Condenser	0.03	0.03	0.03	0.03	μ <b>f</b>
Grid Resistor(For Following Tu	be) 0.25	0.25	0.25	0.25	megohm
R-F Signal Voltage (RMS)	1.18	1.21	1.38	1.37	volts
Output Peak Voltage	17	17	17	17	volts
(At grid of following tube wi	th signal	modu	lated 20%	1	

When a resistor is used in the grid circuit, its value should not exceed 1 megohm.


The voltage between heater and cathode should be kept as low as possible where they are not directly connected,

\* With shell connected to cathede \*\*With tube shield and internal shield connected to cathede.



# **6J8G**

TRIODE HEPTODE
FREQUENCY CONVERTER
Heater Type Glass Bulb



The 6J8G is a duplex tube containing a triode unit and a heptode unit, having a common cathode, in the same envelope. The grid of the triode unit is connected internally to the injector grid of the heptode unit. It is designed for converter service in circuits similar to those employing a separate triode oscillator and pentagrid mixer.




BOTTOM VIEW OF SOCKET

#### RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum Plate Voltage (Heptode)	250	volts
Maximum Screen Voltage (Heptode)	100	volts
Maximum Plate Supply Voltage (Triode)	250*	volts

#### FREQUENCY CONVERTER


\* Applied through a 20000 ohm series resistor by-passed by a 0.1  $\mu f$  condenser.



# **6K5G**

TRIODE AMPLIFIER Heater Type

Glass Bulb





BOTTOM VIEW OF SOCKET

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum Plate Voltage	250	volts


#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	2.0	$\mu\mu\mathbf{f}$
Input	2.4	μμ <b>f</b>
Output	3,6	μμ⊈


#### AMPLIFIER - CLASS A

Plate Voltage Grid Blas Amplification Factor (approximate)	100 -1.5 70	250 -3 70	volts volts
Plate Resistance (approximate ) Transconductance Plate Current	78000	50000	ohm <b>s</b>
	900	1400	µmhos
	0,35	1.1	ma

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



# 6K6G



PENTODE
POWER AMPLIFIER
Heater Type Glass Bulb

The 6K6G is a pentode type power amplifier tube designed for service in the output stage of storage battery or a-coperated receivers. The ratings and electrical characteristics are identical with those of the type 41.



#### BOTTOM VIEW OF SOCKET

RI	۱Ţ	1	Ν	G٤

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.4	amp
Haximum Plate Voltage	250	volts
Haximum Screen Voltage	250	volts


#### AMPLIFIER - CLASS A

Plate Voltage		135	180	250	volts
Screen Voltage		135	180	250	volts
Grid Bias		-10	-13.5	-18 †	volts
Amplification Factor (approx.) Plate Resistance (approx.) Transconductance Plate Current	150 103500 1450 9	150 94000 1600 12.5	150 81000 1850 18.5	150 68000 2200 32	ohms µmh <b>os</b> ma
Screen Current	1.6	2.2	3	5.5	ma
Load Resistance	12000	10400	9000	7600	ohms
Total Harmonic Distortion	10	10	10	10	percent
Power Output	0.33	0.75	1.5	3.4	watts

Transformer or impedance input coupling devices are recommended. If resistance coupling is used, the d-c resistance in the grid circuit should not exceed 1 megchm with self-bias, or 0.1 megchm with fixed-bias.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

†A bias of -16.5 volts and a load resistance of 7000 ohms will give power output of 3.2 watts with 7% total harmonic distortion.



RAYTHEON ENGINEERING SERVICE

# **6K7 6K7G**

# RAYTHEON

# **6K7 6K7G**

PENTODE REMOTE CUTOFF AMPLIFIER

E CUTOFF AME -Heater Type
Glass Bulb-6K7G Metal Bulb-6K7



The 6K7 is a pentode type amplifier tube with remote cutoff characteristics designed for service as a high frequency amplifier or mixer in storage battery or a-c operated receivers. The ratings and electrical characteristics ar cal with those of the type 78. are identi-



6K7G-NO CONNECTION TO #1 PIN

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum Plate Voltage	250	volts
Maximum Screen Voltage	125	volts
DIRECT INTERELECTRODE CAPACITANCES		

# AKTG 9"00 Mar 81 7 PRONG SMALL OCTAL BASE

#### Grid to Plate Output 12 Input 6K7\* 0.005 max. muf 6K7G\*\* 4.5 μμΩ AMPLIFIER - CLASS A Plate Voltage 90 180 75 250 250 volts Screen Voltage 100 125 90 volts -3 -3 min.volts Connected to Cathode at Socket Grid Bias Suppressor Amplification Factor 1160 0.8 1450 400 990 1100 Plate Resistance 0.315 1.0 0.6 1650 megohm Transconductance umhos Plate Current 10.5 5.4 4 ma ĺ i.7 Screen Current 1.3 2.6 Grid Bias rid Bias -38.5 -32.5 (For Transconductance = 2 umhos) 42.5 -52.5 volts

# MIXER - SUPERHETERODYNE CIRCUIT

Plate Voltage Screen Voltage Grid Bias† Suppressor

250 volts 100 volts **-1**0 volts Connected to Cathode at Socket

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

The internal shield in the 6K7G is connected to the cathode within the tube.


- \* With shell connected to cathode.

RATINGS

\*\*With tube shield connected to cathode,

† The grid bias is not critical with an oscillator peak voltage 1 volt less than the grid bias.

For additional curves refer to the type 78.



# 6L5G

TRIODE
DETECTOR OR AMPLIFIER
Heater Type Glass Bulb

ST 12-9 BULS

ST 12-9 BULS

AG MARK

FROM

G SMORL

OCTRL BASE

The 6L5G is a triode type amplifier tube designed for service as a detector or amplifier in storage battery or a-o operated receivers requiring a low heater current tube.



BOTTOM VIEW OF SOCKET

RATINGS

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage 6.3 volts 0.15 amp 250 volts

DIRECT INTERELECTRODE CAPACITANCES\*

 Grid to Plate
 2.7
 μμf

 Input
 3
 μμf


 Output
 5
 μμf

AMPLIFIER - CLASS A

Plate Voltage	135	250	volts
Grid Bias	<b>-</b> 5	-9	volts
Amplification Factor	17	17	ohma
Plate Resistance	11300	8900	
Transconductance Plate Current	1500	1900	µmhos
	3.5	8	ma
Grid Bias for Plate Current Cutoff	-1i	-20	volts

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*With tube shield connected to cathode.




# **6L6** 6L6G

# RAYTHEON

# **6L6** 6L6G

G



TETRODE POWER AMPLIFIER OWER AMELIA-Heater Type G145 Bulb-6L60 Metal Bulb-6L6

The 6L6 is a tetrode type power amplifier tube designed for service in the output stage of storage battery or a-c operated receivers.

#### RATTNGS

Heater Voltage (a-c or d-c)# Heater Voltage (a-c or d-o)#
Heater Current
Max, Plate Voltage
Max, Soreen Voltage
Max, Flate & Soreen Dissipation (total)†

Max. Screen Dissipation


(J) (2\H) (4)7 DEF (A)

BOTTOM VIEW OF SOCKET 6L6G-NO CONNECTION TO #1 PIN

6.3 0.9 400 amp volts 300 volts watts

volts

#### AMPLIFIER - CLASS A - FIXED BIAS



375 125 375 max. 250 max. Plate Voltage 250 300 volts Screen Voltage 250 200 volts -14 14 135 Grid Bias -12.5-9 -17.5 volts Signal Peak Voltage Amplification Factor 12,5 8 17.5 volts Plate Resistance 22500 ohms Transconductance 6000 umhos Transconductance
No-Sig. Plate Current
Max.Sig. Plate Current
No-Sig. Soreen Current
Max.-Sig. Soreen Current
Load Resistance 72 48 24 57 ma 26 0.7 79 55 67 ma 2.5 2.5 5 ma ž 7.3 6 ma 4500 14000 4000 2500 ohms Total Harmonics 10 11 9 14.5 11.5 percent Second Harmonic Third Harmonic Power Output 10.7 8 2.5 4 9.7 percent 2.5 4.2 percent 4.2 11.5 6.5 6.5 wet.t.s

#### AMPLIFIER - CLASS A - SELF-BIAS

Plate Voltage	375	300	250	volts
Screen Voltage	125	200	250	volts
Self-Bias Resistor	365	220	170	ohms
Signal Peak Voltage	8.5	12.5	14	volts
No-Sig. Plate Current	24	51	75	ma
MaxSig. Plate Current	24.3	54.5	78	ma
No-Sig. Plate Current	0.7	3	5.4	ma
MaxSig. Screen Current	1.8	4.6	7.2	ma.
Load Resistance	14000	4500	2500	ohm <b>s</b>
Total Harmonics	9	11	10	percent
Second Harmonic	8	10.7	9.7	percent
Third Harmonic	4	2.5	2.5	percent
Power Output	4	6.5	6.5	watts
		Continu	ed on ne	ext page

AVERAGE PLATE CHARACTERISTICS 616 AVERAGE CHARACTERISTICS Ec= 6.3 6L6G CLASS A OPERATION

E\_=6.3 Ep=250 E56=250 SIGHAL ADJUSTED TO I G=1 Jule. En 250 LOAD LINE - NO SIGNAL LOAD LINE - MAXIMUM SIGNAL WATTS R DUTPUT- W 820 REEN 10 64 CURRENT-56 ENT-A OR SCREEN #ma d 15 E PLATE MONICS-P RREHT 204 25 V 8 şo, 200

AMPLIFIER - CLASS A - PUSH-PULL - TWO TUBES

		Fixed-Bias	Self-Bias	
Plate Voltage	375 max.	250	250	volts
Screen Voltage	250 max.	250	250	volts
Grid Bias		-16		volts
Self-Bias Resistor			125	ohm <b>s</b>
Signal Peak Voltag	e (grid to grid)	32	35.6	volts
No-Signal Plate Cu	rrent	120	120	ma.
MaxSignal Plate	Current	140	130	ma
No-Signal Screen C	urrent	10	10	ma
MaxSignal Screen	Current	16	1.5	ma.
Load Resistance (p	late to plate)	5000	5000	ohms
Total Harmonics		2	2	percent
Third Harmonic		2	2	percent
Power Output		14.5	13.8	watts

AMPLIFIER - CLASS AB1 - PUSH-PULL - TWO TUBES


		Fixed	-Blas		Seli	-B1as	3
Plate Voltage	400	400	400	400	400	400	volts
Screen Voltage	250	250	300	300	250	300	volts
Grid Bias	-20	-20	-25	<b>-2</b> 5			volts
Self-Bias Resistor					190	200	ohms
Signal Peak Voltage (g to g)	40	40	50	50	43.8	57	volts
No-Signal Plate Current	88	88	102	102	96	112	ma
MaxSignal Plate Current	124	126	152	<b>1</b> 56	110	128	ma
No-Signal Screen Current	4	4	6	6	4.6	7	ma
MaxSignal Screen Current	12	9	17	12	10.8	16	ma.
Load Resistance (p to p)	8500	6000	6600	3800	8500	6600	ohma
Total Harmonics	2	1	2	0.6	2	2	percent
Third Harmonic	2	1	2	0.6	2	2	percent
Power Output	26.5	20	34	23	24	32	watts

AMPLIFIER - CLASS  $AB_2$  - PUSH-PULL - TWO TUBES

	Fixed-Bias	Fixed-Bias	3
Plate Voltage	400	400	volts
Screen Voltage	250	300	volts
Grid Bias	-20	-25	volts
Signal Peak Voltage (grid to grid)	57	80	volts
No-Signal Plate Current	88	102	m <b>a</b>
MaxSignal Screen Current	168	230	ma
No-Signal Screen Current	4	6	ma.
MaxSignal Screen Current	13	20	ma
Load Resistance (plate to plate)	6000	3800	ohm <b>s</b>
Peak Driving Power	180	350	mw
Total Harmonics‡	2	2	percent
Third Harmonic ‡	2	2	percent
Power Output	40	60	watts
#Under maximum dissination conditi	one the heater volter	h Ironde	never

#Under maximum dissipation conditions the heater voltage should never fluctuate so that it exceeds 7.0 volts. The voltage between heater and cathode should be kept as low as possible.

The rated dissipation should not be exceeded with expected line voltage fluctuations, especially in fixed-bias operation. Fixed-bias values up to 10% of each typical screen voltage can be used without increasing distortion. iwith ideal driver and perfect power supply regulation.



# **6L7** 6L7G

6L7 CAPPED WITTBA BULB

IS BASE

6176

7 PRONG SMALL OCTAL BASE

# **RAYTHEON**

# **6L7** 6L7G

HEPTODE

MIXER or AMPLIFIER PENTAGRID

) MIADA G. Heater Type Glass Bulb-6L7G Metal Bulb-6L7

The 6L7 is a pentagrid type tube designed for service as a mixer in storage battery or a-c operated superheterodyne oscillator (2) receivers using a separate RATINGS

Heater Voltage Heater Current 6.3 0.3 volts amp Max. Plate Voltage 250

(d)65 6LTG SAME AS 6LT EXCEPT NO CONN.TO PIN#1 BOTTOM VIEW OF SOCKET

GIRCVY

DIRECT INTERELECTRODE CAPACITANCES CTTV

				ODIA	OTHERWA	
Grid #1	to	Plate		0.0005	0.003 max.	μμf
Grid #1	to	Grid #3		0.12	0.15	nuf
Grid #3	to	Plate		0.025	0.25	μμſ
Grid #1	to	all other E	Elements	8.5	5.8	щſ
Grid #3	to	all other H	Elements	11.5	11.5	uuf
Plate	to	all other E	Elements	12.5	9	μμf

AMPLIFIER - CLASS A

Plate Voltage	250	volts
Screen (Grids #2 & #4) Voltage	100 r	max. volts
Control Grid (#1) Bias	-3 r	min. volts
Control Grid (#3) Bias	-3	volts
Amplification Factor	880	
Plate Resistance	0.8	megohm
Transconductance	1100	µmhos
Plate Current	5.3	ma
Screen Current	6.5	ma
Transconductance	5	umhos
(Grid #1 Bias = -15 volts; Grid #3	Bias = -15	5 volts)


MIXER - SUPERHETERODYNE CIRCUIT

Plate Voltage	250	250	volts
Screen (Grids #2 & #4) Voltage	100	150	max. volts
Signal Grid (#1) Bias	-3	-6	min. volts
Oscillator Grid (#3) Bias	-10	-15	volts
Oscillator Peak Voltage (Grid #3)	12	18	volts
Plate Resistance	Greate	r the	an 1 meg <b>ohm</b>
Conversion Conductance	350	350	umhos
Plate Current	2.4	3.3	ma
Screen Current	7.2	9.2	ma.
Signal Grid (#1) Bias	<b>-</b> 30	-45	volts
(Conversion Conductance = 5 µmhos)			

# With Shell connected to cathode. \*\*With tube shield connected to cathode

The D-C resistance in the oscillator grid (#3) circuit should not exceed

50000 ohms.
The voltage between heater and cathode should be as low as possible where they are not directly connected.



ST 12-D BULB

19 '00

18 MINE

SHALL BASE

CATHODE RAY TUNING INDICATOR Heater Type Glass Bull

Heater Type Glass Bulb

The 6N5 is a high vacuum type indicator tube designed for service as a tuning indicator in radio receivers requiring a low heater current tube.



BOTTOM VIEW OF SOCKET


#### RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.15	amp
Maximum Plate Supply Voltage	135	volts
Maximum Target Voltage	1.35	volts

#### TUNING INDICATOR

Plate Supply Voltage	135	volts
Target Voltage	135	volts
Plate Resistor	0.25	megohm
Target Current (approximate)	4.5	ma
Plate Current (zero bias)	0.5	m.a.
Grid Bias for Shadow Angle= 0 (approx.)	-12	volts
Grid Bias for Shadow Angle=900 (approx.)	0	volts

The 6N5 is a high-vacuum tube designed to visually indicate the effect of changing the control grid bias. The shaded pattern produced on the fluorescent target varies through an angle from 90° to approximately 0° as the control voltage is varied. The voltage on the shadow control electrode the extension of the triode plate between the cathode and target, controls the extent of the shaded area. The voltage of the shadow control electrode is determined by the voltage of the control grid of the triode connected as a d-c amplifier. Thus the control grid voltage determines the extent of the shadow. An increase of control grid bias thus increases the shadow control voltage and decreases the shadow while a decrease of bias increases the shadow. In practical use the control grid voltage is obtained from a suitable point in the AVC network.




RAYTHEON ENGINEERING SERVICE

# **6N6G** 6N6MG

# **RAYTHEON**

# **6N6G** 6N6MG

DUO-TRIODE DIRECT COUPLED POWER AMPLIFIER Heater Type 6N6G Meta-Glass-6N6MG Glass Bulb-6N6G




The 6N6G is a direct coupled power amplifier tube designed for service in the output stage of storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the type 6B5.



BOTTOM VIEW OF SOCKET 6N6MG-SHELL CONNECTED

	TO#1PIN
volts	6.3
amp	0.8



Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage 325 volts AMPLIFIER - CLASS A 250 300 325 volts

Output-Plate Voltage Input-Plate Voltage Grid Bias 250 300 325 volts volts Amplification Factor 58 Plate Resistance 241.00 ohma Transconductance 2400 umhos Output-Plate Current Input-Plate Current 33 45 51 ma 6.5 7000 ma Load Resistance Total Harmonic Dist. Power Output Signal Voltage RMS 7000 7000 ohms 5 5 5 percent 2.5 5.2 watts 13.5 15 volts


AMPLIFIER - CLASS A - PUSH-PULL - TWO TUBES

Output-Plate Voltage Input-Plate Voltage	250 250	300 300	325 325	volts volts
Grid Bias	0	0_	0_	volts
Output-Plate Current (per tube) Input-Plate Current (per tube)	33	45	51	ma
Load Resistance (plate to plate)	6.5 10000	8 <b>1</b> 0000	9	ma. ohma
Total Harmonic Distortion	5	5	5	percent
Power Output	8.5	10	13.5	watta
Signal Voltage RMS (grid to grid)	38	<b>3</b> 8	42	volts

The voltage between heater and cathode should not exceed 50 volts and in no case should the heater be left floating.

If a grid resistor is used its value should not exceed 0.5 megohm.

For additional curves refer to the type 6B5.




# **6N7 6N7G**

# **RAYTHEON**

# **6N7 6N7G**

TWIN TRIODE POWER AMPLIFIER


Heater Type Glass Bulb-6N7G Metal Bulb-6N7



The 6N7 is a twin triode type amplifier tube designed for service as a Class B power amplifier in the output stage of storage battery or stage of storage battery or a c operated receivers. The ratings and electrical characteristics are identical with those of the type 6A6.



BOTTOM VIEW OF SOCKET 6N7G-NO CONNECTION TO #1 PIN



Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage Maximum Peak Plate Current (per plate) Maximum Average Plate Dissipation	6.3 0.8 300 125 10	volts amp volts ma watts
AMPLIFIER - CLASS B		
Plate Voltage 250	300	volts


Grid Bia				0	0	volts
		Current(p			17.5	ma
Load Res	istance	(plate to	plate)	8000	10000	ohms
Power Ou	tput (a	pproximate	•)	8	10	watts
(With a	verage	power inpu	t = 350 r	nw. grid	to gr	rid)
AMPLIFIER	- CLASS	A-DRIVER	TRIODES	CONNECT	ED IN	PARALLEL
				250	294	volts

Voltage Plate Grid Biast -6 volts -5 35 35 11000 Amplification Factor Plate Resistance 11300 ohms Transconductance 3100 3200 umhos Plate Current ma Load Resistance - Depends on the design of the following Class B amplifier.
Usually between 20000 and 40000 ohms.

Power Output (approximate) 400 mw

d-c resistance in the grid circuit should not exceed 0.5 megohm with self-bias or 0.1 megohm with fixed-bias.

For additional curves refer to the type 6A6.





TRIODE-PENTODE AMPLIFIER OR CONVERTER Heater Type Glass Bulb

The 6P7G is a duplex tube, combining in one bulb a triode and a remote cutoff pentode, designed for service as an oscillator and mixer or as a high frequency amplifier and second detector, in storage battery or a coperated receivers. The ratings and electrical characteristics are identical with those of the type FFY. the type 6F7.



BOTTOM VIEW OF SOCKET

RATINGS Heater Voltage (a-c of Heater Current	r d-e)	6.3 0.3	volts amp
DIRECT INTERELECTRODE C Grid to Triode Section * 2 Pentode Section*	Plate Input 0 3.5	0utput 3.0 12	քող Դուդ
AMPLIFIER - CLASS A			

Plata Waltage	Triode Section	Pentode 100	Section 250 max.	volts
Plate Voltage Screen Voltage	100 max.	100	100 max.	
Grid Bias	-3	-3	-3 min.	volts
Amplification Factor	8	300	900	
Plate Resistance	0.016	0.29	0.85	megohm
Transconductance	500	1050	1100	umhos
Plate Current	3.5	6.3	6.5	ma
Screen Current		1.6	1.5	ma.
Transconductance (at -35 volts bias)	)	9	10	µmhos

#### FREQUENCY CONVERTER


Triode	Section	Pentode Secti	on
Maximum Plate Voltage	100	250	volts
Maximum Screen Voltage		100	volts
Minimum Grid Bias	ţ	<b>-</b> 3 #	volts
Maximum Oscillator Plate Current(average) Typical Operation:	4		ma.
Plate Voltage	100‡	250	volts
Screen Voltage	·	100	volts
Grid Bias	†	-10 A	volts
Plate Resistance		2	megohm
Conversion Conductance		300	μmhos
Plate Current	2.4	2.8	mp.
Grid Current	0.15	0	ma
Screen Current		0.6	m <b>e</b> .
Oscillator Peak Voltage Input		7	volts

The voltage between heater and catho where they are not directly connected. cathode should be kept as low as possible

\*With tube shield connected to cathode and other section connected to ground †Usually obtained by means of a grid leak.
#Grid bias should be at least 3 volts greater than the peak oscillator volt-

age applied to the pentode grid.
They be obtained from 250 volt supply through 60000 chm series resistor. ΔObtained by means of 1700 ohm cathode resistor.

For additional curves refer to the type 6F7.



# **6Q7 6Q7G**

# RAYTHEON

# **6Q7** 607G

DUO-DIODE TRIODE DETECTOR AMPLIFIER

Heater

Type Glass Bulb-6Q7G Metal Bulb-607

The 6Q7 is a duo-diode triode type amplifier tube designed for service as a combined diode detector, AVC rectifier and resistance coupled audio frequency

amplifier in storage battery or a-o op



BOTTOM VIEW OF SOCKET 6Q7G-NO CONNECTION TO #1 PIN 6.3 volts

amp

uuf

volt:

0.3

250

4,5

607

6Q1G

7 PRONG SMALL OCTAL BASE

1010

MAX

212

RATINGS

Heater Voltage (a-c or d-c) Heater Current

Maximum Plate Voltage 607# 607G

erated receivers.

DIRECT INTERELECTRODE CAPACITANCES - TRIODE SECTION Grid to Plate Input Output  $\mu\mu f$ 

AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage Grid Bias 100 250 volts -1.5 70 -3 70 volts Amplification Factor Plate Resistance 87500 58000 ohms Transconductance 1200 umbos Plate Current 0.35 1.1

AMPLIFIER - CLASS A - RESISTANCE COUPLED - TRIODE SECTION


<u> </u>			
Plate Supply Voltage	100	250	volts
Grid Bias	-1.1	-2	volts
Plate Resistor	0.15	0.2	megohm
Plate Current	0.25	0.5	ma
Grid Resistor‡	0.5	0.5	megohm
Voltage Amplification	35	43	
<u> </u>			

#### DIODE SECTION

The two diode units are independent of each other and of the triode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed. AVC voltage.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*With shell connected to cathode. #For following tube.



# **6R7 6R7G**

# **RAYTHEON**

# **6R7 6R7G**



DUO-DIODE TRIODE DETECTOR AMPLIFIER Heater

Metal Bulb-6R7

Type Glass Bulb-6R7G

The 6R7 is a duo-diode triode type amplifier tube designed for service as a combined diode detector, AVC rectifier and audio frequency amplifier in storage battery or a-c operated receivers.

#### RATINGS

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage

(3)p

BOTTOM VIEW OF SOCKET 6R7G-NO CONNECTION TO #1 PIN

6.3 vol ta amp 0.3 volts



# DIRECT INTERELECTRODE CAPACITANCES - TRIODE SECTION

6R7* 6R7G	Grid to Plate 2.5 3.5	Input 5.5 2.5	Output 4.0 4.5	րր <b>ք</b> դո <b>ւ</b>
AMPLIFIER	- GLASS A - TRIODE	SECTION		

Plate Voltage 250 volts Grid Bias **-**9 volts Amplification Factor **1**6 Plate Resistance 8500 ohms Transconductance 1900 μmhos Plate Current Load Resistance 9.5 mg ohms Power Output (5% second harmonic) 280 mw

AMPLIFIER - CLASS A - RESISTANCE COUPLED - TRIODE SECTION


#### DIODE SECTION

The two diode units are independent of each other and of the triode section except for the common cathode. The diode may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVG voltage.

The voltage between heater and catho where they are not directly connected. cathode should be kept as low as possible

\*With shell connected to cathode.


iFor following tube.





PENTODE
REMOTE CUTOFF AMPLIFTER
Heater Type Glass Bulb

The 687G is a pentode type amplifier tube with remote outoff characteristics designed for service as a high frequency amplifier in storage battery or a-c operated receivers requiring a low heater current tube.



BOTTOM VIEW OF SOCKET

RATINGS

 Heater Voltage (a-c or d-c)
 6.3
 volts

 Heater Current
 0.15
 amp

 Haximum Plate Voltage
 250
 volts

 Haximum Soreen Voltage
 100
 volts


DIRECT INTERELECTRODE CAPACITANCES\*

Grid to Plate 0.007 max. upf Input 4.6 uth Output 7.8

ALIPLIFIER - CLASS A

250 volts Plate Voltage 1.35 Screen Voltage 67.5 100 Grid Bias **-**3 <u>-3</u> volts Suppressor Connected to Cathode at Socket Amplification Factor 850 min. 1100 min. 0.63 min.megohm 1750 µmhos 0.68 min. 1250 Plate Resistance Transconductance 3.7 Plate Current 8.5 ma Screen Current 0.9 ma Grid Bias **-**25 -38.5 volts (Transconductance = 10 umhos)

\*With tube shield.



RAYTHEON ENGINEERING SERVICE

# **RAYTHEON**

CATHODE RAY TUNING INDICATOR
Heater Type Glass Bulb

The 6T5 is a high-vacuum type indicator tube with remote cutoff characteristics designed for service as a tuning indicator in radio receivers. The shaded pattern on the fluorescent target is annular in shape.



# BOTTOM VIEW OF SOCKET


#### RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Max. Plate Supply Voltage	250	volts
Max. Target Voltage	250	volts

#### TUNING INDICATOR

Plate Supply Voltage	250	volts
Target Voltage	250	volts
Plate Resistor	1	megohm
Target Current (approximate)	3	ma
Plate Current (zero bias)	0.24	ma.
Grid Bias for Min. Shadow Diameter	-22	volts
Grid Bias for Max. Shadow Diameter	0	volts

The 6T5 is a high vacuum tube designed to visually indicate changes of control grid bias. With the triode section connected as a d-c amplifier, the voltage of the shadow control electrode which is connected to the triode plate increases with an increase of control grid bias and causes a reduction in shadow diameter. Similarly, a decrease of control grid bias increases the shadow diameter. In tuning indicator service the control grid bias is obtained from a suitable tap in the AVC network.



RAYTHEON ENGINEERING SERVICE

ST 12-D BULB XHK 7 PRONG SMALL OCTAL BASE

DUO-DIODE TRIODE DETECTOR AMPLIFIER Heater Type Glass Bulb

The 6T7G/6Q6G is a duo-diode triode type The of Grant and the combined triving as a combined diode detector, AVC rectifier, and audio frequency amplifier in storage battery or a-c operated receivers requiring a low heater current tube. ing a low heater current tube. The 6176/6Q6G replaces the type 6Q6G, single-BOTTOM VIEW OF SOCKET diode triode.



RATINGS

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage 6.3 0.15 volts amp 250 volts

DIRECT INTERELECTRODE CAPACITANCES - TRIODE SECTION


Grid to Plate uu f Input μμf Output μμ1

AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage Grid Bias 250 135 volts -3 volts Amplification Factor Plate Resistance 65 65 65000 62000 ohma Transconductance 1,000 1050 μmhos. Plate Current 0.9 1.2 ma

#### DIODE SECTION


The two diode units are independent of each other and of the triode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVC voltage.



CATHODE RAY TUNING INDICATOR Heater Type Glass Bulb



The 6US is a high vacuum type indicator tube with remote cutoff characteristics designed for service as a tuning indicator in radio receivers. The ratings and electrical characteristics are identical with those of the type 665/6US.



BOTTOM VIEW OF SOCKET


		NGS	
TIM	J 4.	MAD	

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Supply Voltage Haximum Tanget Voltage	6.3 0.3 250 250	volts volts volts
Minimum Target Voltage	90	volts

#### TURING INDICATOR

Plate Supply Voltage	100	200	250	volts
Target Voltage	100	200	250	volts
Plate Resistor	0.5	1	1	megohm
Target Current (approximate)	4,5	4.5	4.5	ma.
Plate Current (zero Bias)	0.19	0.19	0.24	ma.
Grid Bias (approximate)	-8	<b>~18.</b> 5	-22	volt <b>s</b>
(For Shadow angle = 00 )				
Grid Eias (approximate)	0	0	0	volts
(For Shadow angle = 90°)				

The 6US is a high vacuum tube designed to visually indicate the effect of changing the control grid bias. The shaded pattern produced on the fluorescent target varies through an angle from 90° to approximately 0° as the control voltage is varied. The voltage on the shadow control electrode, the extension of the triode plate between the cathode and target, controls the extent of the shaded area. The voltage of the shadow control electrode is determined by the voltage of the control grid of the triode connected as a d-c amplifier. Thus the control grid voltage determines the extent of the shadow. An increase of control grid bias thus increases the shadow control voltage and decreases the shadow while a decrease of bias increases the shadow. In practical use the control grid voltage is obtained from a suitable point in the AVC network.



RAYTHEON ENGINEERING SERVICE

ST 12-F BUIL

7 PRONG SMALL OCTAL BASE

#### PENTODE REMOTE CUTOFF AMPLIFIER

Heater Type Glass Bulb



The 6U7G is a pentode type amplifier tube with remote cutoff characteristics designed for service as a high frequency amplifier or mixer in storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the type 6D6.

BOTTOM VIEW OF SOCKET

#### RATINGS

Heater Voltage (a-c or d-c)6	.3 volts
Heater Current 0.	.3 amp
Max. Plate Voltage 2:	50 volts
Max. Screen Voltage	00 volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate Input	0.007max.* 4.5	μμ <b>f</b> μμ <b>f</b>
Output	9.0	μμf

#### AMPLIFIER - CLASS A

Plate Voltage Soreen Voltage	100 100	250 100	volts
Grid Bias	-3	-3	volts
Suppressor	Connected to	Cathode at	Socket
Amplification Factor	375	1280	
Plate Resistance	0.25	0.8	megohm
Transconductance	<b>150</b> 0	1600	μ <b>m</b> ho <b>s</b>
Plate Current	8	8,2	ma.
Screen Current	2.2	2	ma.
Grid Bias for Transconductance = 2 µmhos	<b>-</b> 50	<b>-</b> 50	volts

#### MIXER - SUPERHETERODYNE CIRCUIT

Plate Voltage	100	250	volts
Screen Voltage	100	100	volts
Grid Bias	-10	-10	volts
Suppressor	Connected to	Cathode at	Socket


The grid bias is not critical with an oscillator peak swing 1 voltless than the grid bias.

The shield in the dome of the tube is connected internally to the cathode. The voltage between heater and cathode should be kept as low as possible

\*With tube shield

where they are not directly connected.

For additional curves refer to the type 6D6.



# 6V6 6V6G

# **RAYTHEON**

# 6V6 6V6G

GVG MTAB BULB -/i OR --/ie MARX -/i OR MA TETRODE
POWER AMPLIFIER
Heater Type
Metal Bulb-6V6 Glass Bulb-6V6G

The 6V6 is a tetrode type power amplifier tube designed for service in the output stage of storage battery or a-c operated receivers.

#### RATINGS

Heater Volt.(a-c or d-c	0.45	volts
Heater Current	0.45	amp
Max. Plate Voltage	300	volts
Max. Screen Voltage	300	volts
Max. Plate and Screen Dissipation (total)	12.5	watts



BOTTOM VIEW OF SOCKET 6V6G-NO CONNECTION TO #1 PIN





Plate Voltage Screen Voltage Grid Blas* Signal Peak Voltage Amplification Factor Plate Resistance Transconductance	180 180 -8.5 8.5	250 250 -12.5 12.5 218 52000 4100	max. volts volts volts volts ohms umhos
No-Signal Plate Current MaxSignal Plate Current No-Signal Screen Current NaxSignal Screen Current Load Resistance Power Output Second Harmonic	29 30 3 4 5500 2 5.5	45 47 4.5 6.5 5000 4.25 4.5	μmnos ma ma ma ma chms watts percent

AMPLIFIER - PUSH-PULL - CLASS	AB - TWO	TUBES	
Plate Voltage	250	300	volts
Soreen Voltage	250	300	volts
Grid Bias*	-15	-20	volts
Signal Peak Voltage (grid to grid)	30	40	volts
No-Signal Plate Current	70	78	me.
MaxSignal Plate Current	79	90	m,e.
No-Signal Screen Current	5	5	ma
Fax Signal Screen Current	12	13.5	ma
Load Resistance (plate to plate)	10000	8000	ohms
Power Output	8.5	13	watts
Third Harmonic	3.5	3.5	percent
Total Harmonics	4	4	percent

\*Transformer or impedance input systems are recommended. If resistance coupling is used, the d-c resistance in the grid circuit should not exceed 0.5 megchm with self-bias, or 0.05 megchm with fixed-bias.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



7 PRONG SMALL OCTAL BASE WAX.

DUO-DIODE TRIODE
DEFECTOR AMPLIFIER

heater Type Glass Bulb

The 6VTO is a duo-diode triode type emplifier tube designed for service as combined diode detector, AVC rectifier, and a-f amplifier in storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of type 05.



RATINGS

BOTTOM VIEW OF SOCKET

Heater Voltage (a-c or d-c)6.3 volts
Heater Current 0.3 amp
Haximum Plate Voltage 250 volts

DIRECT LUTERELECTRODE CAPACITANCES - TRIODE SECTION

 Grid to Flate
 1.7
 μμf

 Input
 2.0
 μμf

 Jutput
 3.5
 μμf


AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage Grid Bias Amplification Factor	135 -10.5 8.3	180 -13.5 8.3	250 -20 8.3	volts volts
Plate Resistance	11000	8500	7500	ohms
Transconductance	750	975	1100	pumhos
Plate Current	3.7	6	8	ma
Load Resistance	25000	20000	20000	ohms
Power Output	75	160	350	mw

#### DIODE SECTION

The two diode units are independent of each other and of the triode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVC voltage.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



RAYTHEON ENGINEERING SERVICE

# **RAYTHEON**

# 6W5G


TWIM DIODE
FULL WAVE HIGH VACUUM RECTIFIER
Heater Type Glass Bulb

ST 12-0 BULB

GROWN SERVICE


GROWN S

The 6W5G is a full wave high vacuum type rectifier tube designed for service in either vibrator type or a-c operated power supplies.



## BOTTOM VIEW OF SOCKET

FULL WAVE RECTIFIER - CONDENSER OR CHOKE INPUT FILTER



# 6X5 6X5G

# RAYTHEON

# 6X5 6X5G


535 MT88 BULB 16 MRX. 187 MRX TWIN DIODE
FULL WAVE HIGH VACUUM RECTIFIER
Heater Type
Metal Bulb-6X5 Glass Bulb-6X5G

The 6X5 is a full wave high vacuum type rectifier tube designed for service in power supplies for storage battery or a-c operated receivers.

FULL WAVE RECTIFIER
Condenser or Choke Input Filter




BOTTOM VIEW OF SOCKET 6X5G-NO CONNECTION TO #1 PIN.




Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.6	amp
Maximum A-C Voltage per Plate (RMS)	350	volts
Maximum Inverse Peak Voltage	1250	volts
Maximum D-C Output Current	75	ma
Maximum D-C Voltage between		
Heater and Cathode	400	volts

AVERAGE TUBE VOLTAGE DROP 22 volts (At 75 ma, output current per plate)

There are certain 32 volt receivers designed with 6X5G tubes operated in series. The filament current value usedin this design was 0.5 ampere. Type 6X5G tubes marked 500 under the type designation may be obtained for this service.





TETRODE
POWER AMPLIFIER
Heater Type

Heater Type Glass Bulb

The 6Y6G is a tetrode type power amplifier tube designed for service in the contput stage of a-c operated receivers having relatively low plate supply voltages.

# RATINGS

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage Maximum Screen Voltage

# 

BOTTOM VIEW OF SOCKET

6.3	volts
1.25	amp
1.35	volts


volts

135

#### AMPLIFIER - CLASS A

Plate Voltage	135	volts
Screen Voltage	135	volts
Grid Bias	-13.5	volts
Signal Peak Voltage	13.5	volts
Amplification Factor	70	
Plate Resistance (approximate)	10000	ohms
Transconductance	7000	umhos
No-Signal Plate Current	58	ma.
MaxSignal Plate Current	60	mia.
No-Signal Screen Current	3	ma.
MaxSignal Screen Current	17	ma
Load Resistance	2000	ohms
Second Harmonic Distortion	2.5	percent
Third Harmonic Distortion	9	percent
Power Output	3.6	watts
	0.0	

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



8 PROMG SMALL OCTAL BASE

00,00

MRX

## **RAYTHEON**

# **6Y7G**

TWIN TRIODE POWER AMPLIFIER Heater Type Glass Bulb

The 6Y7G is a twin triode type power amplifier tube designed for service as a Class B amplifier in the output stage of storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the type 79.



BOTTOM VIEW OF SOCKET

RATINGS


Heater Voltage (a-c or d-c) 6.3 volts
Heater Current 0.6 amp
Maximum Plate Voltage 250 volts
Max. Peak Plate Current 90 ma (per plate)
Max. Av. Plate Dissipation 11.5watts

AMPLIFIER - CLASS B

Plate Voltage Grid Blas No-Signal Plate Current (per plate) Load Resistance (plate to plate) 180 250 volts ō volts 3.8 7000 5.3 ma 14000 ohms Power Output 5.5 watts (With average power input = 380 mw. grid to grid)

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

For additional curves refer to the type 79.



RAYTHEON ENGINEERING SERVICE

8 PRONG SMALL OCTAL BASE

# **RAYTHEON**

TWIN TRIODE POWER AMPLIFIER Heater Type

Dual Grid

Glass Bulb

The 627G is a twin triode type amplifier tube designed for service as a Class B power amplifier in the output stage of storage battery or a-c operated receivers requiring a low heater current tube.



BOTTOM VIEW OF SOCKET




Heater Voltage (a-c or d-c)6.3
Heater Current 0.3
Maximum Flate Voltage 180
Max, Peak Flate Current 60
(per plate)
Max. Av. Flate Dissipation 8 volts amp volts ma

watts

AMPLIFIER - CLASS B

Plate Voltage Grid Bias No-Signal Plate Current (per plate) Load Resistance (plate to plate)	135 0 3 15000	180 0 4.2 20000	volts volts ma ohms
Power Output	1.5	2.2	watts
(With average power input = 80 mw. grid Load Resistance Power Output	9000 2.8	12000 4.2	ohms watts
(With average power input = 320 mw.grid		-,	

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.




ST 12-D BULB

6 PRONG SMALL OCTAL BASE

TWIN DIODE FULL WAVE HIGH VACUUM RECTIFIER Heater Type

Glass Bulb The 6ZY5G is a full wave high vacuum type rectifier tube designed for service in power supplies for storage battery or a-c operated receivers requiring a low heater current tube.

AVERAGE TUBE VOLTAGE DROP (approximate) (At 35 ma. output current per plate)




BOTTOM VIEW OF SOCKET

volts


16.5

FULL WAVE RECTIFIER

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum A-C Voltage per Plate (RMS)	350	volts
Maximum D-C Output Current	<b>3</b> 5	ma.
Maximum Inverse Peak Voltage	1000	volts
Maximum Peak Plate Current per Plate Maximum D-C Voltage between	<b>1</b> 50	ma
Heater and Cathode	<b>40</b> 0	volts



10



†Grid bias values are given with respect to the mid-point of a-c opera filement. If d.o. is used the tabulated values of grid bias should decreased by 5 volts and referred to the negative end of the filement. operated

250

110

55

13

4000

-28

350

120

55

20

6000

-40

425

130

55

25

8000

-50

volts

wolts


volts ma

ma

ohms

watts watts

!Averaged over any audio frequency cycle.



RAYTHEON ENGINEERING SERVICE

STI4 BULB

TRIODE DETECTOR OR AMPLIFIER Filament type Glass Bulb

The 12-A is a triode type amplifier tube designed for service as a detector or amplifier in storage battery operated receivers.



BOTTOM VIEW OF SOCKET

	rat	INGS
--	-----	------

Filament Voltage	5.0 d-c	volts
Filament Current	0.25	amp
Haximum Plate Voltage	180	volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	7.5	դդ <b>ւք</b>
Input	4	դդ <b>ւք</b>
Output	3	դդդ

#### AMPLIFIER - CLASS A

Plate Voltage Grid Bias	90 -4.5	135 -9	180 -13.5	volts volts
Amplification Factor	8.5	8.5	8.5	
Plate Resistance	5400	5100	4700	ohm <b>s</b>
Transconductance	1575	1650	1800	μ <b>mhos</b>
Plate Current	5	6.2	7.7	ma
Load Resistance	5000	9000	10650	ohms
Power Output (5% second harmonic)	0.035	0,13	0.285	watts

If a grid resistor is used, its value should not exceed 1 megohm.

DETECTOR - BIASED TYPE

Plate Voltage	135	180	volts
Grid Bias (approximate)	<b>-1</b> 5	-21	volts
Plate Current	Adjusted to 0.	2 ma. with no	signal

#### DETECTOR - GRID LEAK TYPE

Plate Voltage	45	AOTER
Grid	Return to positive	filament
Grid Leak Resistance	0.25 to 5	megohm
Grid Condenser	0.00025	$\mu$ f

7 PRONG SMALL BASE

PENTODE POWER AMPLIFIER Glass Bulb

Heater Type ST 12-0 AU B The 12A5 is a pentode type power amplifier tube having two heaters which may be connected in series for a heater voltage of 12.6 volts, or connected in parallel for a heater voltage of 6.3 volts.

RATINGS




BOTTOM VIEW OF SOCKET Parallel

	Connection	Connection	
Heater Voltage (a-c or d-c)	12.6	6.3	volts
Heater Current	0.3	0.6	amp
Maximum Plate Voltage	1	80	volts
Maximum Screen Voltage	1	80	volts

Series

AMPLIFIER - CLASS A


100	180	volts
100	180	volts
-15	-25	volts
70	85	
41000	36000	ohms
1700	2400	umhos
17	<b>4</b> 5	ma
3	8	ma
<b>45</b> 00	3300	ohms
2.5	6.5	percent
9	8	percent
0.7	3.4	watts
	100 -15 70 41000 1700 17 3 4500 2.5	100 180 -15 -25 70 85 41000 36000 1700 2400 17 45 3 8 4500 3300 2.5 6.5 9 8



volts emp volts

DIODE-PENTODE
RECTIFIER-POWER AMPLIFIER
Heater Type Glass Bulb

The 12A7 is a diode-pentode type tube designed for service as a half wave rectifier and power amplifier in the output stage of a-o - d-o receivers.



RATINGS


Heater Voltage (a-c or d-c)	12.6
Heater Current	0.3
Pentode Section Maximum Plate Voltage Maximum Screen Voltage	135 135

AMPLIFIER - CLASS A - PENTODE SECTION

Plate Voltage	135	volts
Soreen Voltage	135	volts
Grid Bias	-13.5	volts
Amplification Factor	100	
Plate Resistance	0.102	megohm
Transconductance	975	μmhos
Plate Current	9	ma
Screen Current	2.5	me.
Load Resistance	13500	ohms
Power Output	0.55	watts

#### HALF WAVE RECTIFIER - RECTIFIER SECTION

Maximum A-C Plate Voltage (RMS)	125	volts
Maximum D-C Output Current	30	ma
Average Tube Voltage Drop	15	volts
(At 60 mg. output current)		



ST 12-0 BULB

ST 12-0 BULB

A PEONG
SMALL BASE

DIODE
HALF WAVE HIGH VACUUM RECTIFIER
Heater Type Glass Bulb

The 1223 is a half wave high vacuum type rectifier tube designed for service in a-o - d-o receivers.




BOTTOM VIEW OF SOCKET

HALF WAVE RECTIFIER

Condenser or Choke Input Filter

Heater Voltage (a-c or d-c) Heater Current Maximum A-C Plate Voltage (RES) Maximum Inverse Peak Voltage Maximum D-C Output Current Maximum D-C Voltage between Heater and Cathode	12.6 0.3 250 700 60 350	volts volts volts ma volts
neater and cathode	380	VOLUS

AVERAGE TUBE VOLTAGE DROP 18 volts (At 120 ma. output current)



RAYTHEON ENGINEERING SERVICE

# PENTODE AMPLIFIER Heater Type Glass Bulb

The 15 is a pentode type amplifier tube designed for service in battery operated receivers requiring a low voltage heater type tube.



RATINGS

Heater Voltage Heater Current Max. Plate Voltage Max. Screen Voltage BOTTOM VIEW OF SOCKET

2.0 d-c volts

0.22 amp

135 volts

67.5 volts


#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	(with shield)	0.01 max.	Ղոդ
Input		2.35	Ղոր
Output		7.8	Ղոր

#### AMPLIFIER - CLASS A


Plate Voltage	67.5	135	volts
Screen Voltage	67.5	67.5	volts
Grid Bias	-1.5	<b>-1.5</b>	volts
Amplification Factor	450	600	
Plate Resistance	0.63	0.8	megohm
Transconductance	710	750	umhos
Plate Current	1,85	1.85	ma
Screen Current	0.3	0.3	ma.

The voltage between heater and cathode should be as low as possible. It should never exceed 22.5 volts.



RAYTHEON ENGINEERING SERVICE

TWIN TRIODE POWER AMPLIFIER Filament Type Glass Bulb



The 19 is a twin triode type power amplifier tube designed for service as a Class B amplifier in the output stage of battery operated receivers. The ratings and electrical characteristics, except filament current, are identical with those of the type 1J6G.



BOTTOM YIEW OF SOCKET


#### RATTNGS

Filament Voltage	2.0 d-c	volts
Filament Current	0.26	amp
Maximum Plate Voltage	1.35	volts
Maximum Peak Plate Current (per plate)	50	ma


#### AMPLIFIER - CLASS B

Plate Voltage	135	135	135	volts
Grid Bias	<b>-</b> 6	<b>-</b> 3	0	volts
No-Signal Plate Current (per plate)	0.5	2	5	ma
Load Resistance (plate to plate)	10000	10000	10000	ohms
Power Output (approximate)	1.6	1.9	2.1	watts
Average Power Input (grid to grid)	0.095	0.13	0.17	watts

For additional curves refer to the type 1J6G.



RAYTHEON ENGINEERING SERVICE



# TRIODE POWER AMPLIFIER Filament Type Glass Bulb

The 20 is a triode type power amplifier tube designed for service in the output stage of battery operated receivers.



## BOTTOM VIEW OF SOCKET

Filament Voltage	3.0	3.3 d-c	volts
Filament Current	0.125	0.132	amp
Maximum Plate Voltage	135		volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	4.1	րրք
Input	2.0	Դող
Output	2.3	Արդ

# AMPLIFIER - CLASS A

Plate Voltage Grid Bias	90 -16.5	135 <b>-</b> 22 <b>.</b> 5	volts volts
Amplification Factor	3.3	3 <b>.3</b>	
Plate Resistance	8000	6300	ohms
Transconductance	415	525	umhos
Plate Current	3	6.5	ma.
Load Resistance	9600	6500	ohma
Power Output (5% second harmonic)	45	110	mw

# 22

STIA BULB

# RAYTHEON

22



TETRODE
AMPLIFIER
Filament Type Glass Bulb

The 22 is a tetrode type amplifier tube designed for service as a highfrequency amplifier in battery operated receivers.



BOTTOM VIEW OF SOCKET

# RATINGS

ATINGS		
Filament Voltage	3.3 d-c	volts
Filament Current	0.132	amp
Maximum Plate Voltage	135	volts
Maximum Screen Voltage	67.5	volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	0.020 max.* u	μf
Input	3,3 ù	μf
Output	12 μ	μf

#### AMPLIFIER - CLASS A

Plate Voltage	135	135	volts
Screen Voltage	45	67.5	volts
Grid Bias	-1.5	-1.5	volts
Amplification Factor	270	160	
Plate Resistance	0.725	0.325	megohm
Transconductance	375	500	µmho <b>s</b>
Plate Current	1,7	3.7	ma.
Screen Current	0.6	1.3	ma.

If a grid resistor is used, its value should not exceed 5 megohms with a screen voltage of 45 volts, or 1 megohm with a screen voltage of 67.5 volts.

\*With tube shield

#### RAYTHEON ENGINEERING SERVICE

STIA BULB

#### TROSTER

DETECTOR OR AMPLIFIER Heater Type Gless Bulh

The 24-A is a tetrode type amplifier tube designed for service as a detector amplifier in a-c operated receiv-



#### RATINGS

Input

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage Maximum Screen Voltage

DIRECT INTERELECTRODE CAPACITANCES

2.5 1.75 250 volts amp volts volts

10.5

0.007 max.\* μμf

μμf

uuf

# Grid to Plate Output AMPLIFIER - CLASS A

Plate Voltage Screen Voltage	180 90	250 90	volts volts
Grid Bias	-3	-3	volts
Amplification Factor	400	630	
Plate Resistance	0.4	0.6	megohm
Transconductance	<b>1</b> .000	1050	μ <b>mhos</b>
Plate Current	4	4	m <b>a</b>
Screen Current	1.7	1.7	ma.

#### DETECTOR - BIASED TYPE


Plate Voltage Soreen Voltage Grid Bias (approximate) Plate Load Plate Current volts 250 20 to 45 volts -5 0.25 megohm Adjusted to 0.1 ma. with no signal

#### DETECTOR - GRID LEAK TYPE

Plate Voltage Screen Voltage Grid 180 max.volts
20 to 45 volts
Conventional Grid Leak and Condenser Plate Load 0.25 megohm

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*With tube shield.




RAYTHEON ENGINEERING SERVICE

# 25A6 25A6G

# **RAYTHEON**

# 25A6 25A6G



PENTODE
POWER AMPLIFIER
Heater Type
Metal Bulb-25A6 Glass Bulb-25A6G

The 25A6 is a pentode type power amplifier tube designed for service in the output stage of a-o-d-o receivers. The ratings and electrical characteristics are identical with those of the type 45.



BOTTOM YIEW OF SOCKET 25A6G - NO CONNECTION TO #1 PIN



Heater Voltage(a-c or d-o)25 volts
Heater Current 0.3 amp
Max. Plate Voltage 180 volts
Max. Soreen Voltage 135 volts


AMPLIFIER - CLASS A

RATINGS

Plate Voltage	95	135	180	volts
Soreen Voltage	95	135	135	volts
Grid Bias -	-15	-20	-20	volts
Amplification Factor (approx.)	90	85	100	
Plate Resistance (approx.)	45000		40000	ohms
Transconductance	2000	2450	2500	µmhos
Plate Current	20	37	<b>3</b> 8	me
Screen Current	4	8	7.5	ma.
Load Resistance	4500	4000	5000	ohms
Total Harmonic Distortion	11	9	10	percent
Power Output	0.9	2	2.75	watts

Heater to cathode bias should not exceed 90 volts d-c, as measured between the negative heater terminal and the cathode.

For additional curves refer to the type 43.



STI4 BULB


MEDIUM OCTAL BASE

### **RAYTHEON**

# 25A7G

DIODE PENTODE
RECTIFIER POWER AMPLIFIER
Heater Type Glass Bulb

The 25A7G is a diode-pentode type tube designed for service as a half wave rectifier and power amplifier in the output stage of a-c - d-c receivers.



BOTTOM VIEW OF SOCKET


Heater Voltage (a-c or d-c)	25	volts
Heater Current	0.3	amp
Pentode Section		-
Maximum Plate Voltage	100	volts
Maximum Screen Voltage	100	volts

#### AMPLIFIER - CLASS A - PENTODE SECTION

Plate Voltage Soreen Voltage Grid Blas Amplification Factor	100 100 -15 90	volts volts volts
Plate Resistance	<b>30</b> 000	ohm <b>s</b>
Transconductance	1800	μmhos
Plate Current	20.5	ma.
Screen Current	4	ma.
Load Resistance	4500	ohms
Total Harmonic Distortion	9	percent
Power Output	0.77	watts

#### HALF WAVE RECTIFIER - RECTIFIER SECTION

Maximum A-C Plate Voltage RMS	125	volts
Maximum D-C Output Current	75	me.



7 PROMG MEDIUM OCTAL BASE

# **RAYTHEON**


# 25B6G

ALIGNED GRID PENTODE POWER AMPLIFIER Heater Type Glass Bulb

STI4 BULB The 25B6G is an aligned grid pentode type power amplifier tube designed for service in the output stage of a-c - d-c power ampl vice in the receivers. RATTNOS

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage

Maximum Screen Voltage




25 volts 0.3 95 amp 95 volts

# AMPLIFIER - CLASS A

Plate Voltage Screen Voltage 95 volts 95 volts Grid Bias 15 volts Subject to considerable variation Plate Resistance 4000 umhos Transconductance 45 шы Plate Current Screen Current ma Load Resistance 2000 ohm**s** Total Harmonics Power Output percent watts 10 ī.,75

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.




# 25L6 25L6G

# **RAYTHEON**

# 25L6 25L6G

BOTTOM VIEW OF SOCKET 25L66-NO CONNECTION

(**3**)




TETRODE
POWER AMPLIFIER
Heater Type
Metal Bulb-25L6 Glass Bulb-25L6G

The 25L6 is a tetrode type power amplifier tube designed for service in the output stage of a-c - d-c receivers.

#### RATINGS


	70 - 7 7 711	
Heater Voltage (a-c or d-c)	25	volts
Heater Current	0.3	amp
Maximum Plate Voltage	110	volts
Maximum Screen Voltage	110	volts



AMPLIFIER - CLASS A			
Plate Voltage	110	110	volts
Screen Voltage	110	110	volts
Grid Bias*	-7.5	-7.5	volts
Signal Peak Voltage	7.5	7.5	volts
Amplification Factor	82	82	
Plate Resistance (approx.)	10000	10000	ohms
Transconductance	8200	8200	μm <b>hos</b>
No-Signal Plate Current	49	49	m <b>a</b>
MaxSignal Plate Current	54	50	me.
No-Signal Screen Current	4	4	m <b>a</b> .
MaxSignal Screen Current	9	11	ma
Load Resistance	1500	2000	ohms
Total Harmonic Distortion	11	10	percent
Second Harmonic Distortion	10	3.5	percent
Third Harmonic Distortion	4	8.5	percent
Power Output	2.1	2.2	watts

The voltage between heater and cathode should not exceed 90 volts, as measured between the negative end of the heater and the cathode.

\*Transformer or impedance input systems are recommended. If resistance coupling is used, the d-c resistance in the grid circuit should not exceed 0.5 megohm with self-bias, or 0.1 megohm with fixed-bias.




ST 12-D BULB

6 PRONG

TWIN DIODE HIGH VACUUM RECTIFIER VOLTAGE DOUBLER

VOLTAGE DOUBLER
Heater Type Glass Bulb



The 25Z5 is a high vacuum type rectifier tube designed for service as a half wave rectifier or voltage doubler in a-c - d-c receivers.

BOTTOM VIEW OF SOCKET

#### VOLTAGE DOUBLER


T W-3 ()	0.5	
Heater Voltage (a-c or d-c)	25	volts
Heater Current	0.3	amp
Maximum A-C Voltage per Plate (RMS)	125	volts
Maximum Peak Plate Current	500	ma.
Maximum D-C Output Current	100	ma

#### HALF-WAVE RECTIFIER

	MICHORD	WILL	
	Series Resistor	Series Resi	stor*
Heater Voltage (a-c or d-c)	25	25	volts
Heater Current	0.3	0.3	amp
Maximum A-C Voltage per Plate (RMS)	125	250	volts
Maximum Peak Current per Plate	500	500	ma.
Maximum D-C Output Current per Plate	85	85	ma

As a half-wave rectifier, the two sections may be used either separately or connected in parallel.

\*A-C plate voltages greater than 125 volts require the use of a 100 ohm series resistor in each plate lead or a 100 ohm series resistor common to both plates. The latter connection gives somewhat poorer regulation.



RAYTHEON ENGINEERING SERVICE

# 25Z6 25Z6G

# **RAYTHEON**

# 25Z6 25Z6G

2536 MT38 BULB WEB ATTO TO THE MT38 BULB WEB ATTO THE MT38 BULB WEB

TWIN DIODE
HIGH VACUUM RECTIFIER
VOLTAGE DOUBLER
Heater Type
Wetal Bulb-25Z6 Glass Bulb-25Z6G

The 25Z6 is a high vacuum type rectifier tube designed for service as a half-wave rectifier or voltage doubler in a-c - d-o receivers.



BOTTOM VIEW OF SOCKET 2536G-NO CONNECTION TO #1 PIN

With

# 25266 ST 12-0 808.8

7 PRONG SMALL OCTAL BASE

Heater Voltage (a-c or d-c)	25	volts
Heater Current	0.3	amp
Maximum A-C Voltage per Plate (RMS)	125	volts
Maximum Peak Plate Current	500	ma
Maximum D-C Output Current	85	ma

HALF WAVE RECTIFIER


VOLTAGE DOUBLER

	Series	Series	
	Resistor	Resistor	*
Heater Voltage(a-c or d-c)	25	25	volts
Heater Current	0.3	0.3	amp
Max. A-C Voltage per Plate (RMS)	125	250	volts
Max. Peak Plate Current per Plate	500	500	ma
Max. D-C Output Current per Plate	85	85	ma.

Without

As a half-wave rectifier, the two sections may be used either separately or connected in parallel.

\*A-C plate voltages greater than 125 volts require the use of a 100 ohm series resistor in each plate lead or a 100 ohm series resistor common to both plates. The latter connection gives somewhat poorer regulation.





#### TRIODE AMPLIFIER

Filament Type Glass Bulb

The 26 is a triode type amplifier tube designed for service in a-c operated receivers.



BOTTOM VIEW OF SOCKET

RATINGS	
---------	--

Filament Voltage (a-c or d-c)	1.5	volts
Filament Current	1.05	amp
Maximum Plate Voltage	180	volts

# DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	8.1	μμ£
Input	3.5	uu£
Output	2.2	<u> ս</u> աք

#### AMPLIFIER - CLASS A

Plate Voltage	90	135	180	volts
Grid Biast	<b>-</b> 7	-10	-14.5	volts
Amplification Factor	8 <b>.3</b>	8.3	8.3	
Plate Resistance	8900	7600	7300	ohms
Transconductance	935	1100	1150	umhos
Plate Current	2.9	5.5	6.2	ma.

†Grid Bias measured from mid-point of a-c operated filament.

volts

volts

TRIODE DETECTOR OR AMPLIFIER Heater Type Glass Bulb

ST 12-D BULB XHM MAX

The 27 is a triode type amplifier tube designed for service as a detector or amplifier in a-c operated receivers.

G (2 P (K 4)

3

BOTTOM VIEW OF SOCKET

2.5 1.75 volts amr 250 volts

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage

DIRECT INTERELECTRODE CAPACITANCES

3.3 3.5 3.0 Grid to Plate սաք Input μμ**f** Output μμ1

AMPLIFIER - CLASS A

RATINGS

Plate Voltage Grid Bias Amplification Factor Plate Resistance 135 90 180 250 volts -6 -9 -13.5 -21 volts ğ 9 9 9 11000 9000 9000 9250 ohms Transconductance 820 1000 1000 975 umhos Plate Current 2.7 4.5 5.0 5.2 ma

If a grid resistor is used. its value should not exceed 1 megoinm

DETECTOR - BIASED TYPE


Plate Voltage Grid Bias (approximate) Plate Current; 275 max. 250 -30 -33 Adjusted to 0.2 ma. with no signal

DETECTOR - GRID LEAK TYPE

Plate Voltage volts Grid Grid Leak Resistance Return to Cathode 1 to 5 megohms 0.00025 Grid Condenser иf

The voltage between heater and catho where they are not directly connected. and cathode should be kept as low as possible

‡With normal maximum signal the average d-c plate current should not exceed 5 ma.



RAYTHEON ENGINEERING SERVICE

4 PRONG

TRIODE DETECTOR OR AMPLIFIER Filament Type Glass Bulb ST :2-D BULB The 30 is a tricde type amplifier tube designed for service as a detector or amplifier in battery operated receivers. The ratings and electrical characteristics are identical with those of the 43 "MAX tics are type 1H4G. RATTUGS



BOTTOM VIEW OF SOCKET

Heater Voltage 2.0 d-c volts Heater Current 0.060 Maximum Plate Voltage 180

DIRECT INTERELECTRODE CAPACITANCES Grid to Plate 6.0 uuf 3.7 2.1 Input  $\mu\mu \mathbf{f}$ Output Huf

AMPLIFIER - CLASS A
---------------------

Plate Voltage	90	135	180	volts
Grid Bias	-4.5	-9	-13.5	volts
Amplification Factor	9.3	9.3	9.3	
Plate Resistance	11000	10300	10300	ohms
Transconductance	850	900	900	umhos
Plate Current	2.5	3.0	3.1	ma

If a grid resistor is used, its value should not exceed 2 megohms.

AMPLIFIER - CLASS B - TWO TUBES

Maximum Plate Voltage	180	volts
Maximum Peak Plate Current (per tube)	50	ma.
Maximum No-Signal Plate Current (per tube)	1.5	ma
Typical Operation:		
Plate Voltage	157.5	volts
Grid Bias	<b>-1</b> 5	volts
No-Signal Plate Current (per tube)	0.5	m <b>a</b>
Load Resistance (plate to plate)	3000	ohm <b>s</b>
Power Outputt	2.1	watts
(With average power input = 260 mw. grid to grid)		

DETECTOR - BIASED TYPE


Plate Voltage Grid Bias (approximate) Plate Current; 90 135 1.80 volts -18 -9 -13.5 -18 volts Adjusted to 0.2 ma, with no signal

DETECTOR - GRID LEAK TYPE

45 max. volts
Returned to positive filament
1 to 5 megohms Plate Voltage Grid Grid Leak Resistance megohms μſ Grid Condenser 0.00025 †With one type 30 as driver operated at plate voltage of 157.5 volts, grid bias of -11.3 volts, plate load of approximately 18000 ohms, and input transformer ratio, primary to 1/2 secondary, of 1.165. Total distortion is 6% to 7%.

twith normal maximum signal the average d-c plate current should 2 ma.

For additional curves refer to the type 1H4G.



ST 12-D BULB 4 PRONG SMALL BAS

#### TRIODE POWER AMPLIFIER Filament Type G

Glass Bulb

The 31 is a triode type power amplifier tube designed for service in the output stage of battery operated receivers.



RATINGS

Filament Voltage Filament Current Maximum Plate Voltage


2.0 d-c	volts
0.13	amp
180	volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	5.7	1 դդ
Input	3.5	1 դդդ
Output	2.7	1 դդ

#### AMPLIFIER - CLASS A

Plate Voltage	135	180	volts
Grid Blas	-22.5	-30	volts
Amplification Factor Plate Resistance	3.8 4100	3.8 3600	ohms
Transconductance	925	1050	ma
Plate Current	8	12.3	ma
Load Resistance	<b>7</b> 000	5 <b>7</b> 00	ohme
Power Output (5% second harmonic)	<b>1</b> 85	<b>375</b>	mw



# STIA BULB

TETRODE

DETECTOR OR AMPLIFIER
Filament Type Glass Bulb

The 32 is a tetrode type amplifier tube designed for service as a detector or amplifier in battery operated receivers.



32

BOTTOM VIEW OF SOCKET

RATINGS

Filament Voltage Filament Current Maximum Plate Voltage Maximum Soreen Voltage 2.0 d-c volts 0.060 amp 180 volts 67.5 volts

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate Input Output 0.015 max.\* μμf 5.3 μμf 10.5 μμf

AMPLIFIER - CLASS A

Plate Voltage 135 180 volts Screen Voltage 67.5 67.5 volts Grid Bias -3 3 volts 610 780 Amplification Factor Plate Resistance 0.95 6**4**0 1.2 megohm 650 Transconductance umhoa Plate Current 1.7 1.7 ma. Screen Current 0.4 0.4

If a grid resistor is used, its value should not exceed 2 megohms.


DETECTOR - BIASED TYPE

Plate Supply Voltage 135 180 volts Screen Voltage 45 67.5 volts Grid Bias (approximate) -4.5 -6 volts Plate Load C.1 megohm or equivalent impedance Plate Current Adjusted to 0.2 ma. with no signal

DETECTOR - GRID LEAK TYPE

Plate Voltage Screen Voltage Grid Plate Load Grid Leak Resistance Grid Condenser 135 volts
Up to 45 volts
Return to positive filament
0.1 megohm or equivalent impedance
1 to 5 megohm
0.00025 µf

\*With tube shield.



# PENTODE POWER AMPLIFIER Filament Type Glass Bulb

The 33 is a pentode type power amplifier tube designed for service in the output stage of battery operated receivers.

Filament Voltage Filament Current Maximum Plate Voltage Maximum Soreen Voltage




#### BOTTOM VIEW OF SOCKET

2.0 d-c	volts
0.26	amp
180	volts
180	volts

#### AMPLIFIER - CLASS A

Plate Voltage Soreen Voltage Grid Bias Amplification Factor	135 135 -13,5 70	180 180 -18 90	volts volts volts
Plate Resistance Transconductance Plate Current	50000	55000	ohms
	1450	1700	µmhos
	14.5	22	ma
Screen Current	3	5	ma
Load Resistance	7000	6000	ohms
Power Output (7% total distortion)	0,7	1.4	watts



RAYTHEON ENGINEERING SERVICE

STI4 BULB

PENTODE
REMOTE CUTOFF AMPLIFIER
Filament Type Glass Bulb

The 34 is a pentode type amplifier tube with remote cutoff characteristics designed for service as a high frequency amplifier or mixer in battery operated receivers.



BOTTOM VIEW OF SOCKET

RATINGS

Filament Voltage Filament Current Maximum Plate Voltage Maximum Soreen Voltage

2.0		volts
0.06	0	amp
180		volts
67.5		volts

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate Input Output

		_
0.015	max.*	μμΙ
6		$\mu\mu\mathbf{f}$
11.5		μμ <b>f</b>


AMPLIFIER - CLASS A

Plate Voltage	67.5	135	180	volts
Screen Voltage	67.5	67.5	67.5	volts
Grid Bias	-3	-3	<b>-</b> 3	volts
Amplification Factor	224	360	620	
Plate Resistance	0.4	0.6	1	megohm
Transconductance	560	600	620	μmhos
Plate Current	2.7	2.8	2.8	ma.
Screen Current	1.1	1.0	1.0	me.
Transconductance	15	15	15	μmhos
(At -22.5 volts bias)				•

MIXER - SUPERHETERODYNE CIRCUIT


Plate Voltage	67.5	135	180	volts
Screen Voltage	67.5	135	180	volts
Grid Bias (approximate)†	~5	<b>-</b> 5	<b>-</b> 5	volts

†The grid bias shown is minimum for an oscillator peak voltage of 4 volts \*With tube shield.



RAYTHEON ENGINEERING SERVICE

TETRODE



REMOTE CUTOFF AMPLIFIER
Heater Type Glass Bulb

The 35/51 is a tetrode type amplifier tube with remote cutoff characteristics designed for service as a high frequency amplifier or mixer in a-c operated receivers.

2P KP

BOTTOM YIEW OF SOCKET

RATINGS

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage Maximum Soreen Voltage 2.5 volts 1.75 amp 250 volts 90 volts

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate Input Output 0.007 max.\* μμf 5 μμf 10.5 μμf

AMPLIFIER - CLASS A

Plate Voltage Soreen Voltage 180 250 volts 90 90 Grid Bias -3 min. -3 min. volts Amplification Factor 305 420 0.3 0.4 1050 Plate Resistance megohm Transconductance umhos Plate Current 6.3 6.5 ma Screen Current 2.5 2.5 ma Transconductance umhos (At -42.5 volts bias)

MIXER - SUPERHETERODYNE CIRCUIT

 Plate Voltage
 250
 volts


 Soreen Voltage
 90
 volts

 Grid Bias (approximate)
 -7
 volts

The grid bias is not critical with an oscillator peak voltage 1 volt less the grid bias.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*With tube shield.



ST 12-D RUI R

5 PRONG

#### TETRODE

DETECTOR OR AMPLIFIER Heater Type Glass Dulb

The 36 is a tetrode type amplifier tube designed for service as a high or audio frequency amplifier or detector in storage battery or a-c operated receivers.



RATINGS

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage Maximum Screen Voltage

BOTTOM VIEW OF SOCKET 6.3 0.3 250 volts amp volts volts

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate Input Output

0.007\* 3.7 9.2 μμf unf uuf

#### AMPLITETER - CLASS A

Plate Voltage	1.00	135	180	250	volts
Screen Voltage	55	67.5	90	90	volts
Grid Bias	-1.5	-1.5	<b>-</b> 3	<b>-</b> 3	volts
Amplification Factor	470	475	525	595	
Plate Resistance	0.55	0.475	0.50	0.55	megehm
Transconductance	850	1000	1050	1000	prihos
Plate Current	1.8	2.8	3.1	3.2	ma
Soreen Current				1.7 max.	ra <b>a</b> .

#### DETECTOR - BIASED TYPE


Plate Supply Voltage	100	180	250	volts
Screen Voltage	55	67.5	90	volts
Grid Blas (approximate)	-5	-6	-8	volts
Plate Load	0.25	0.25	0.25	megohm
Plate Current	Adjusted	1 to 0.1	ma. with	no signal

#### DETECTOR - GRID LEAK TYPE

Plate Supply Voltage Screen Voltage 135 volts Up to 45 volts Return to Cathode Grid Plate Load Grid Leak Resistance Grid Condenser 0.25 2 to 5 meColum megolum 0.00025 μf


The voltage between heater and catho where they are not directly connected. cathode should be kept as low as possible

\*With tube shield



RAYTHEON ENGINEERING SERVICE

TRIODE
DETECTOR OR AMPLIFIER Heater Type Glass Bulb



The 37 is a triode type amplifier tube designed for service as a detector or amplifier in storage battery or a-c operated receivers.

#### RATINGS

	Voltage Current	(a-c	or	<b>d-c</b> )
Maximum	n Plate V	/oltas	ze	



BOTTOM VIEW OF SOCKET volts 0.3 amp volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	2.0	μμ <b>f</b>
Input	3.5	դր <b>ք</b>
Output	2.2	րևք
_		

#### AMPLIFIER - CLASS A

Plate Voltage Grid Bias Amplification Factor	90 -6 9.2	135 -9 9.2	180 -13.5 9.2	250 -18 9.2	volts volts
Plate Resistance	11500	10000	10200	8400	ohms
Transconductance	800	925	900	1100	µmhos
Plate Current	2.5	<b>4.</b> 1	4,3	7.5	ma

If a grid resistor is used, its value should not exceed 1 megohm.


#### DETECTOR - BIASED TYPE

Plate Voltage	90	125	180	250	volts
	-10		-20	00	volts
Grid Bias (approximate)	-10	-15	-20	-28	AOTER
Plate Current		Adjust	ed to 0.2	ma. with	no signal


#### DETECTOR - GRID LEAK TYPE

Plate Voltage	45	volts
Grid	Return to	Cathode
Grid Leak Resistance	1 to 5	megohms
Grid Condenser	0.00025	μf

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.




RAYTHEON ENGINEERING SERVICE



The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

\*The d-c resistance in the grid circuit should not exceed 1 megohm.



RAYTHEON ENGINEERING SERVICE

5 PRONG

#### PENTODE

REMOTE CUTOFF AMPLIFIER
Heater Type Glass Bulb

The 39/44 is a pentode type amplifier tube with remote cutoff characteristics designed for service as a high frequency amplifier or mixer in storage battery or a-o operated receivers.



RATINGS

36

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage Maximum Soreen Voltage BOTTOM VIEW OF SOCKET

6.3 volts
0.3 amp
250 volts

volts

90

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate 0.007 max\* μμ1 Input 3.5 μμ1 0utput 10 μμ1

AMPLIFIER - CLASS A

Plate Voltage 90 180 250 volts 90 Screen Voltage 90 90 volts Grid Bias Amplification Factor Plate Resistance -3 3 3 360 750 1050 0.75 0.375 1.0 megohm Transconductance 960 umhos Plate Current 5.6 5.8 5.8 ma Screen Current 1.6 1.4 ma 2 Transconductance (At -42.5 volts bias) umhos

MIXER - SUPERHEPERODYNE CIRCUIT

Plate Voltage	90	180	250	volts
Screen Voltage	90	90	90	volts
Grid Bias (approximate)†	-7	-7	<b>-7</b>	volts

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

The grid bias is not critical with the oscillator peak voltage 1 volt less than the grid bias.


\*With tube shield.

AVERAGE PLATE CHARACTERISTICS 39/44 AVERAGE CHARACTERISTICS Ep= 6.3<sup>V</sup> Ep= 250<sup>V</sup> Eg = 6.37 E30 = 90 Eg=0 1125 a -1.5 , TRANSCOMBUCTANCE 8 Z CURREN Ž CURRENT-SCREEN 6.0Y 3 PLATE 8 2 M SCREET SENSON =--12.0V , 125 Aples STI4 BULB

4 PRONG MED. BRSE

TRIODE AMPLIFIER

Filament Type





RΑ		

Filament Voltage Filament Current	5.0 d-c 0.25	amp
Maximum Plate Voltage	180	volts

#### DIRECT INTERELECTRODE CAPACITANCES

8.8	դրդ
3.4	1
1.5	1441
	3.4

#### AMPLIFIER - CLASS A

135	180	volts
-1.5	-3	volts
0.25	0.25	megohm
30	30	Ü
0.15	0.15	megohm
200	200	µmhos
0.2	0.2	me.
	•	
	-1.5 0.25 30 0.15 200	-1.5 -3 0.25 0.25 30 30 0.15 0.15 200 200

#### DEFECTOR - BIASED TYPE


Plate Supply Voltage	135	180	volts
Grid Bias	-3	-4.5	volts
Plate Resistor	0.25	0.25	megohm

#### DETECTOR - GRID LEAK TYPE

Plate Supply Voltage Grid Plate Resistor Grid Leak Resistance Grid Condenser	135 to 180 Return to Positive 0.25 2 to 5 0.00025	volts Filament megohm megohms µf
--	---	--

## PENTODE POWER AMPLIFIER Heater Type Glass Bulb

The 41 is a pentode type power amplifier tube designed for service in the output stage of storage battery or a-c operated receivers. The ratings and
electrical characteristics are identical with those of the type 6K6G.



BOTTOM VIEW OF SOCKET

RATINGS
---------

6.3	volts
0.4	amp
250	volts
250	volts
	0.4 250

#### AMPLIFIER - CLASS A


Plate Voltage	100	135	180	250	volts
Screen Voltage	100	135	180	250	volts
Grid Bias	-7	-10	-13.5	-18 <b>†</b>	volts
Amplification Factor (approx.)	150	<b>1</b> 50	<b>1</b> 50	150	
Plate Resistance (approx.)	103500	94000	81000	68000	ohms
Transconductance	1450	1600	1850	2200	μ <b>mhos</b>
Plate Current	9	12.5	18.5	32	ma
Screen Current	1.6	2.2	3	5.5	ma
Load Resistance	12000	10400	9000	7600	ohms
Total Harmonic Distortion	10	10	10	10	percent
Power Output	0.33	0.75	1.5	3.4	watts

Transformer or impedance input coupling devices are recommended. If resistance coupling is used, the d-c resistance in the grid circuit should not exceed 1 megohm with self-bias, or 0.1 megohm with fixed-bias.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

†A bias of -16.5 volts and a load resistance of 7000 ohms will give power output of 3.2 watts with 7% total harmonic distortion.

For additional curves refer to the type 6K6G.



RAYTHEON ENGINEERING SERVICE


STI4 BULB

6 PRONG MEQ BASE

#### PENTODE

POWER AMPLIFIER Glass Bulb Heater Type

The 42 is a pentode type power amplifier tube designed for service in the output stage of storage battery or a-o operated receivers. The ratings and electrical characteristics are identical with those of the types 6F6 and 6F6G.



RATINGS

45

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage 6.3 0.7 315 woll ta amp volts Maximum Screen Voltage 31.5 volts

AMPLIFIER - CLASS A

P	entode Co	nnection	Triode Cor	mection
Plate Voltage	250	<b>31</b> 5	250 max.	volts
Screen Voltage	250	315		volts
Grid Bias	-16.5	-22	<b>-2</b> 0	volts
Amplification Factor	200‡	200‡	7	
Plate Resistance	80000	75000‡	2600	ohma
Transconductance	2500	2650	2700	μ <b>mhos</b>
Plate Current	34	42	31	ma
Screen Current	6.5	8		ma
Load Resistance	7000	7000	4000	ohms
Total Harmonic Dist.	7	7	5	percent
Power Output	3	5	0.85	watts


AMPLIFIER - CLASS AB - TWO TUBES . Markada (tampaakiland


Pentode (	onnection	Triode C	ounse or rout	
Fixed-Bias	Self-Bias	Fixed-Bias	Self-Bias	I
375 max.	375 max.	350 max.	350 max.	volts
250 max.	250 max.			volts
-26 min.		<b>-3</b> 8		volts
	340 min.		730 min.	ohm <b>s</b>
82	94	123	132	volts
34	54	<b>4</b> 5	50	me.
5 5	8			ma
10000	10000	6000	10000	ohms
5	5	7	7	percent
19*	194	18**	1 <i>4</i> ₹	watts
	Fixed-Bias 375 max. 250 max. -26 min. 82 34 55 10000 5	375 max, 250 max, 250 max, 250 max, 250 max, 250 max, 340 min, 94 34 54 54 55 8 10000 10000 5 5 5	Fixed-Bias Self-Bias 350 max. 375 max. 250 max. 250 max26 min. 340 min. 982 94 123 45 5 8 10000 10000 6000 7	Fixed-Bias Self-Bias 350 max. 375 max. 250 max. 250 max. 250 max. 250 max. 360 min. 340 min. 350 min.

#With one 42 triode connected as driver operated at plate voltage of 250 volts grid bias of -20 volts and plate load of approximately 10000 ohms.

\*Input transformer ratio, primary to 1/2 secondary = 3.32 Almput transformer ratio, primary to 1/2 secondary = 2.5 \*\*Input transformer ratio, primary to 1/2 secondary = 1.67 ¶Input transformer ratio, primary to 1/2 secondary = 1.29 †Screen connected to plate. †Approximate

For additional curves refer to the type 6F6G.





PENTODE
POWER AMPLIFIER
Heater Type Glass Bulb

The 43 is a pentode type power amplifier tube designed for service in the output stage of a-c - d-c receivers. The ratings and electrical characteristics are identical with those of the types 25A6 and 25A6G.



BOTTOM VIEW OF SOCKET

RATINGS


| Heater Voltage (a-c or d-c) | 25 | volts | Heater Current | 0.3 | amp | Haximum Flate Voltage | 180 | volts | Haximum Screen Voltage | 135 | volts |

AMPLIFIER - CLASS A

Plate Voltage	95	135	180	volts
Screen Voltage	95	135	135	volts
Grid Bias	-15	-20	-20	volts
Amplification Factor (approximate)	90	85	100	
Plate Resistance (approximate)	45000	35000	40000	ohms
Transconductance	2000	2450	2500	μ <b>mhos</b>
Plate Current	20	37	<b>3</b> 8	ma.
Screen Current	4	8	7.5	ma.
Load Resistance	4500	4000	5000	ohms
Total Harmonic Distortion	11	9	10	percent
Power Output	0.9	2	2.75	watts
-				

Heater to cathode bias should not exceed 90 volts d-c, as measured between the negative heater terminal and the cathode.

For additional curves refer to the type 25A6G.



volts amo volts

Maximum	Plate	Voltage	

DIRECT	INTERELECTRODE	CAPACITANCES		
Grid Input Outpu			7 4 3	րաք բաք դու


#### AMPLIFIER - CLASS A

Plate Voltage	180	250	275	volts
Grid Biast	-31.5	-50	<b>-</b> 56	volts
Amplification Factor	3.5	3.5	3.5	
Plate Resistance	1650	1610	1700	ohms
Transconductance	2125	2175	2050	undhos
Plate Current	31	34	36	me
Load Resistance	2700	3900	4600	ohms
Power Output (5% second harmonic)	0.825	1.6	2	watts

#### AMPLIFIER - PUSH-PULL - CLASS AB - TWO TUBES

	xed-Bias	Self-Bias	
Plate Voltage	275	275	volts
Grid Biast	-68		volt <b>s</b>
Self-Bias Resistor		775	olnna <b>s</b>
No-Signal Plate Current (per tube)	14	36	m <b>a</b> .
MaxSignal Plate Current (per tube)	69	45	ma
Load Resistance (plate to plate)	3200	5060	ohm <b>s</b>
Total Harmonic Distortion	5	5	percent
Power Output	18	12	watts
Average Power Input (grid to grid)	656	461	mV

†Grid Bias measured from mid-point of a-c operated filament.




RAYTHEON ENGINEERING SERVICE

amp



DUAL GRID TRIODE POWER AMPLIFIER Filament Type Glass Bulb

The 46 is a dual grid type power am- ZP plifier tube designed for service in the output stage of a-c operated receivers.



RATINGS

BOTTOM YIEW OF SOCKET 2.5 1.75 volts

Filament Voltage (a-c or d-c)
Filament Current

AMPLIFIER - CLASS B - TWO TUBES
Grid #1 Connected to Grid #2

Maximum Plate Voltage 400
Maximum Peak Plate Current (pertube) 200
Maximum Average Plate Diss. (pertube) 10 volts

Typical Operation:


Plate Voltage	300	400	volts
Grid Biast	Ö	ō	volts
No-Signal Plate Current (per tube)	4	6	ma
Load Resistance (plate to plate)	5200	5800	ohms
Power Output (approximate)	16	20	watts
Average Power Input (grid to grid)	950	650	mw

#### AMPLIFIER - CLASS A Grid #2 Connected to Plate

Plate Voltage	250 max.	volts
Grid Biast	~33	volts
Amplification Factor	5.6	
Plate Resistance	2380	ohms
Transconductance	2350	µmhos
Plate Current	22	ma
Load Resistance	6400‡	ohma
Power Output (5% second harmonic)	1.25	watts

+Grid bias measured from mid-point of a-c operated filament.

fapproximately twice this value is recommended when the tube is used as a driver for a Class B stage.



RAYTHEON ENGINEERING SERVICE


ST 16 BULB

5 PRONG MED BASE

#### PENTODE

POWER AMPLIFIER Filament Type Gl. Glass Bulb

The 47 is a pentode type power amplifier tube designed for service in the output stage of a-c operated receivers.



#### RATINGS

Filament Voltage (a-c or d-c) Filament Current Maximum Plate Voltage Maximum Screen Voltage


	• • • •	 000/12/
2.	5	volt:

1.75 250 250 amp volts volts

AMPLIFIER - OLASS A

Plate Voltage	250	volts
Soreen Voltage	250	volts
Grid Biast	<b>⊸16.5</b>	volts
Amplification Factor	150	
Plate Resistance	60000	ohms
Transconductance	2500	μmhos
Plate Current	31	ma
Screen Current	6	ma.
Load Resistance	7000	ohms
Total Harmonic Distortion	6	percent
Power Output	2.7	watts

\*Grid bias measured from mid-point of a-c operated filament.



RAYTHEON ENGINEERING SERVICE

ST 16 BULB

2 1 OR

Plate Voltage Screen Voltage

Plate Resistance

Transconductance

Plate Current

Amplification Factor

Soreen Current
Load Resistance
Total Harmonic Dist.
Power Output

Grid Biasi

PENTODE

POWER AMPLIFIER Heater Type Glass Bulb

(2 P The 48 is a pentode type power amplifier tube designed for service in the output stage of d-o receivers.



RATINGS

, de

BOTTOM YIEW OF SOCKET Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage 30 volts amp volts 125 Maximum Screen Voltage 100 volts

AMPLIFIER - CLASS A

Pentode Connection Triode Connection 96 125 80 125 volts 96 100 volts -20 -32.5 2.5 675 -19 -20 volts 2.5 760 Subject to . Variation Considerable 3800 ohms 3900 3300 3700 umhos 52 56 52 ma

9.5 1500 q ma 1500 ohms 9 g percent 2.5 watts


AMPLIFIER - CLASS A - PUSH-PULL - TWO TUBES

Pentode Connection Triode Connectiont

Plate Voltage Screen Voltage	125 100	125 volts volts
Grid Bias	-20	-32.5 volts
No-Signal Plate Current (per tube)	56	52 ma
Load Resistance (plate to plate)	3000	<b>1250</b> ohm <b>s</b>
Total Harmonic Distortion	9	2 percent
Power Output	5	2.1 watts

The voltage between heater and they are not directly connected. and cathode should not exceed 90 volts where

The d-c resistance in the grid circuit should not exceed 10000 ohms. Screen Grid connected to plate



DUAL GRID TRIODE POWER AMPLIFIER Filament Type Glass Bulb

STI4 BULB RATINGS MED BASE

The 49 is a dual grid type power amplifier tube designed for service in the output stage of battery operated receivers.



BOTTOM VIEW OF SOCKET

Filament Voltage Filament Current Maximum Plate Voltage 2.0 d-c volts 0.12 volte


AMPLIFIER - CLASS B - TWO TUBES
Grid #1 connected to Grid #2

Maximum Plate Voltage Maximum Peak Plate Current (per tube) Typical Operation:		180 50	volts ma
Plate Voltage Grid (#1 and #2) Bias No-Signal Plate Current (per tube) Load Resistance (plate to plate) Power Output (approximate)	135	180	volts
	0	0	volts
	1.3	2	ma
	8000	12000	ohms
	2.3	3.5	watts

AMPLIFIER - CLASS A
Grid #2 connected to plate

Plate Voltage	135 max.	volts
Grid (#1) Bias	-20	volts
Amplification Factor	4.7	
Plate Resistance	4175	ohms
Transconductance	1125	ohm <b>s</b>
Plate Current	6	ma
Load Resistance	1 <b>1</b> 000*	ohms
Power Output (approximate)	0.17	watts

\*Approximately twice this value is recommended when the tube is used as a driver for a Class B stage.



#### TRIODE POWER AMPLIFIER ment Type Glass Bulb Filament Type



The 50 is a triode type power amplifier tube designed for service in the output stage of radio receivers.

BOTTOM VIEW OF SOCKET

#### RATINGS

5 <b>volts</b> 25 <b>amp</b> 0 <b>volts</b>
1


#### AMPLIFIER - CLASS A

Plate Voltage Grid Biast	300 -54	350 -63	400 -70	450 -84	volts volts
Amp. Factor	3.8	3.8	3.8	3.8	
Plate Resistance	2000	1900	1800	1800	ohm <b>s</b>
Transconductance	1900	2000	2100	2100	umhos
Plate Current	35	<b>4</b> 5	55	55	ma.
Load Resistance	4600	<b>41</b> 00	3670	4350	ohm <b>a</b>
Power Output	1.6	2.4	3.4	4.6	watts
(5% second harm	onic)				

Self-Bias is recommended for all operating conditions.

The d-c resistance in the grid circuit should not exceed 10000 ohms.

†Grid Bias measured from mid-point of a-c operated filament.




RAYTHEON ENGINEERING SERVICE

STI4 BULB

*5 PRONG* MED BASE DUAL GRID TRIODE
POWER AMPLIFIER
Filament Type Glass Bulb

The 52 is a dual grid type power amplifier tube designed for service in the output stage of storage battery operated receivers.



RATINGS

**79**0

Filament Voltage (a-c or d-c) Filament Current Maximum Plate Voltage

BOTTOM	VIEW OF SOCKET
6.3	v <b>olt</b> s
0.3	amp
180	volts


AMPLIFIER - CLASS B - TWO TUBES Grid #1 connected to Grid #2

Maximum Plate Voltage Maximum Peak Plate Current (per tube) Typical Operation:	180 75	volts ma
Plate Voltage Grid (#1 and #2) Bias No-Signal Plate Current (per tube) Load Resistance (plate to plate) Power Output	180 0 1.5 10000 5	volts volts ma ohms watts

AMPLIFIER - CLASS A
Grid #2 connected to plate

Plate Voltage Grid (#1) Bias	100	110 max. O	volts volts
Amplification Factor	5.2	5.2	
Plate Resistance	1900	1750	ohins
Transconductance	2700	3000	μmhos
Plate Current	37	43	ma
Load Resistance	2000	2000	ohms
Power Output*	1.2	1.5	watts

\*Driving power will be required in either single tube or push-pull operation. One type 6A4/IA is recommended as a driver tube. An input transformer ratio, primary to 1/2 secondary, of 3.0, with a 3000 ohm resistor connected across each half of the secondary is recommended.



STI4 BULB

TWIN TRIODE
POWER AMPLIFIER
Heater Type Glass Bulb

The 53 is a twin triode type amplifier tube designed for service as a Class B amplifier in the output stage of a-o operated receivers.



RATINGS BOTTOM VIEW OF SOCKET

Heater Voltage (a-c or d-c)	2.5	volts
Heater Current	2.0	amp
Maximum Plate Voltage	300	volts
Maximum Peak Plate Current (perplate)	125	m <b>a</b> .
Maximum Average Plate Dissipation	10	watts

AMPLIFIER - CLASS b

Plate Voltage Grid Bias No-Signal Flate Current (per plate) Load Resistance (plate to plate)	250 0 14 8000	300 0 17.5 10000	volts volts ma ohms
Power Output (approximate)	. 8	10	watts
(With average nower input = 350 mw. grid :	to grid)		

AMPLIFIER - CLASS A DRIVER - TRIODES CONNECTED IN PARALLEL


Plate Voltage		250	294	volts
Grid Bias†		-5	<b>-</b> 6	volts
Amplification Factor		35	35	
Plate Resistance		11300	11000	ohms
Transconductance		3100	3200	μmhos
Plate Current		6	7	ma.
		of the following		amplifier.
Usually b	between 20000	and 40000 ohms.		
Power Output			400	mw.
10mor oaspas			400	щи

†The d-c resistance in the grid circuit should not exceed 0.5 megohm with self-bias or 0.1 megohm with fixed-bias.

For characteristic curves refer to the types 6A6 and 6N7G. The characteristics of the 53 are the same as those of the 6A6 and the 6N7G except for the heater rating.

DUO-DIODE TRIODE
DETECTOR AMPLIFIER

Heater Type Glass Bulb





BOTTOM VIEW OF SOCKET

RATINGS	RA	T	ĽΝ	GS
---------	----	---	----	----

Heater Voltage (a-c or d-c)	2.5	volts
Heater Current	1.0	amp
Maximum Plate Voltage	250	volts

#### DIRECT INTERELECTRODE CAPACITANCES - TRIODE SECTION

1.7	<b>ը, և ը</b>
2.0	μμ£
3.5	$\mu\mu \mathbf{f}$
	2.0

#### AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage Grid Bias	135 -10.5	180 -13.5	250 -20	volts volts
Amplification Factor	8.3	8.3	8.3	
Plate Resistance	11000	8500	7500	ohms
Transconductance	750	975	1100	μmho <b>s</b>
Plate Current	3.7	6	8	ma.
Load Resistance	25000	20000	20000	ohms
Power Output	75	160	300	mw

#### DIODE SECTION

The two diode units are independent of each other and of the triode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection and the other diode used as a rectifier to obtain delayed AVC voltage.

For characteristic curves refer to the type 85. The characteristics of the 55 are the same as those of the 85 except for the heater rating.


ST 12-D BULB

TRIODE

DETECTOR OR AMPLIFIER
Heater Type Glas

LIFIER Glass Bulb

The 56 is a triode type amplifier tube designed for service as a detector or amplifier in a-c operated receivers.



RATINGS

Heater Voltage (a-c or d-c) Heater Current Maximum Plate Voltage BOTTOM VIEW OF SOCKET

2.5 volts
1.0 amp
250 volts

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate 3.2 μμf Input 3.2 μμf Output 2.2 μμf

AMPLIFIER - CLASS A

 Plate Voltage
 100
 250
 volts

 Grid Bias†
 -5
 -13.5
 volts

 Amplification Factor
 13.8
 13.8

 Plate Resistance
 12000
 9500
 ohms

 Transconductance
 1150
 1450
 µmhos

 Plate Current
 2.5
 5
 ma

DETECTOR - BIASED TYPE

Plate Voltage 100 250 volts
Grid Bias (approximate) -8 -20 volts
Plate Current Adjusted to 0.2 ma. with no signal

DETECTOR - GRID LEAK TYPE

 Plate Voltage
 45
 volts

 Grid
 Return to Cathode

 Grid Leak Resistance
 1 to 5
 megohms

 Grid Condenser
 0,00025
 µf

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

†The d-c resistance in the grid circuit should not exceed 1 megohm.

For characteristic curves refer to the type 76. The characteristics of the 56 are the same as those of the 76 except for the heater rating.

ST 12-C BIJLB

PENTRODE

DETECTOR OR AMPLIFIER Heater Type Glass Bulb

The 57 is a pentode type amplifier tube designed for service as a detector or high frequency amplifier in a-c operated receivers.



Heater Voltage (a-c or d-c) 2.5 volts
Heater Current 1.0 amp
Maximum Plate Voltage 250 volts Maximum Screen Voltage 100 volts

BOTTOM VIEW OF SOCKET

Mariada Connections

(2P)

DIRECT INTERELECTRODE CAPACITANCES

Pentode Connection

Grid to Plate 0.007 max.\*

Triode Connection 2.0 μμε Input 5.0 3.0 10.5 uuſ Output 6.5 muf

AMPLIFIER - CLASS A ntode Connection

	rentode connection	Trione commection	
Plate Voltage	<b>1</b> 00 <b>250</b>	250 volts	
Screen Voltage	<b>10</b> 0 <b>10</b> 0	volts	
Grid Bias	<b>~</b> 3 <b>~</b> 3	-8 volts	
Suppressor	Connected to Cathode at Socke	et e	
Amplification Factor	1185 1500 min.	20 approx.	
Plate Resistance	1 1.5 min.	0.0105 megohm	
Transconductance	1185 1225	1900 µmhos	
Plate Current	2 2	6.5 ma	
Screen Current	0.5 0.5	me.	
Grid Bias (approximate)	-7 <b>-</b> 7	volts	
(For asthade aurrent out	off)		


#### DETECTOR - BIASED TYPE

Plate Supply Voltage	100	100	250	250	volts
Screen Voltage	12	30	5 <b>0</b>	100	volts
Grid Bias	-1.16	-1.83	-1.95	-4.3	volts
Cathode Resistor	18000	10000	3000	10000	volts
Suppressor		Conn	ected to	Cathode at	Socket
Cathode Current (no sig.)	0,063	0.183	0.65	0,43	ma
Plate Resistor	1.0	0.25	0.25	0.5	megohm
Blocking Condenser	0.01	0.01	0.03	0.03	μf
Grid Resistor (for following tube)	1.0	0.5	0.25	0.25	megohm
R-F Signal Voltage (RMS)	1.05	1.6	1.18	1.37	volts
Output Peak Voltage	17	17	17	17	volts
	7		0001		

(At grid of following tube with signal modulated 20%)
The voltage between heater and cathode should be kept as low as possible where they are not directly connected.
The shield in the dome of the tube is connected internally to the cathode.

\*With tube shield †Grids #2 and #3 connected to plate

For characteristic curves refer to the type 6J7G. The characteristics of the 57 are the same as those of the 6J7G except for the heater rating.



### PENTODE REMOTE CUTOFF AMPLIFIER Heater Type Glass Bulb

The 58 is a pentode type amplifier tube with remote outoff characteristics designed for service as a high frequency amplifier or mixer in a-coperated receivers.



#### BOTTOM VIEW OF SOCKET

Heater Voltage (a-c or d-c)	2.5	volts
		VOLUB
Heater Current	1.0	amp
Maximum Plate Voltage	250	volts
Haximum Screen Voltage	100	volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	0.007 max*	μμſ
Input	5.0	μμf
Output	6.5	μμf

#### AMPLIFIER - CLASS A

Plate Voltage	100	250	volt <b>s</b>
Screen Voltage	100	100	volts
Grid Bias	-3	-3	volts
Suppressor	Connected t	o Cathode	at Socket
Amplification Factor	375	1280	
Plate Resistance	0.25	0.8	megohm
Transconductance	1500	1600	umho <b>s</b>
Plate Current	8	8.2	ma
Screen Current	2.2	2	ma
Grid Bias for Transconductance = 2 mmhos	<b>-</b> 50	-50	volts

#### MIXER - SUPERHETERODYNE CIRCUIT

Plate Voltage	100	250	volts
Screen Voltage	100	100	volts
Grid Bias †	-10	-10	volts
Suppressor	Connected	to Cathode	at Socket

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

The shield in the dome of the tube is connected internally to the cathode.

†The grid bias is not critical with an oscillator peak voltage | lvoltless than the grid bias.


\*With tube shield.

For characteristic curves refer to the types 6D6 and 6U7G. The characteristics of the 58 are the same as those of the 6D6 and the 6U7G.

# ST 16 BULB ZE MAX "MAX. T PRONG MER BASE .855 DIA. PI CIRCLE

#### PENTODE TRIPLE GRID POWER AMPLIFIER Heater Type Glass Bulb

The 59 is a triple grid type power amplifier tube designed for service as a Class A tricde, Class A pentode or Class B triode power amplifier in the output stage of a-c operated receivers.



RATINGS	DUTTOM VIEW OF SUCKET	
Heater Voltage (a-c or d-c) Heater Current	2.5 volta 2.0 am	_
Maximum Plate Voltage - Class A	250 volt	s
Maximum Plate Voltage - Class B	400 volt:	s
Maximum Screen Voltage	250 volts	s

AMPLIFIER - CLASS A Triode Connection Pentode Connection

Plate Voltage	250	250	volta
Screen (Grid #2) Voltage		250	volts
Grid (#1) Bias	-28	-18	volts
Amplification Factor	6	100	_
Plate Resistance	2300	40000	ohms
Transconductance	2600	2500	µmhos
Plate Current	26	35	me.
Screen Current		9	ma.
Load Resistance	5000*	6000	ohms
Total Harmonics	5	7	percent
Power Output	1.25	3	watts


AMPLIFIER - CLASS B - TWO TUBES Grid #1 connected to grid #2 Grid #3 connected to plate

Maximum Flate Voltage Maximum Peak Flate Current (per tube) Maximum Average Flate Dissipation (per tube) Maximum Average Grid (#l and #2) Dissipation (per Typical Operation:	tube)	400 200 10 1.5	volts ma watts watts
Plate Voltage Grid (#1 and #2) Bias No-Signal Plate Current (per tube) Load Resistance (plate to plate) Power Output (approximate)	300	400	volts
	0	0	volts
	10	13	ma
	4600	6000	ohms
	15	20	watts

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.


tGrids #2 and #3 connected to plate. tGrid #3 connected to cathode.

\*Approximately twice this value is recommended when the tube driver for a Class B stage. used as



RAYTHEON ENGINEERING SERVICE

#### TRIODE POWER AMPLIFIER



POWER AMPLIFIER
Filament Type Glass Bulb

The 71-A is a triode type power amplifier tube designed for service in the output stage of storage battery operated reseavers.



BOTTOM VIEW OF SOCKET

R	A٦	·Τ	N	38

Filament Voltage (a-c or d-c)	5	volts
Filament Current	0.25	amp
Maximum Plate Voltage	180	volts

AMPLIFIER - CLASS A

Plate Voltage Grid Bias† Amplification Factor	90 -16,5 3	135 -27 3	180 -40.5 3	volts volts
Plate Resistance Transconductance Plate Current Load Resistance Total Harmonic Distortion Power Output(6% second harmonic)	2170	1820	1750	ohms
	1400	1650	1700	µmhos
	10	17.3	20	ma
	3000	3000	4800	ohms
	5	5	5	percent
	125	400	790	mw

†Grid bias measured from negative end of d-o operated filament. If a grid resistor is used, its value should not exceed 0.5 megohm.

# DUO-DIODE TRIODE DETECTOR AMPLIFIER Heater Type Glass Bulb

ST 12-0 BULB

ST 12-0 BULB

JB 100

JB 100

ST 100

ST

The 75 is a duo-diode triode type amplifier tube designed for service as a combined clode detector, AVC rectifier and resistance coupled audio frequency amplifier in storage batteryora-c operated receivers. The ratings and electrical characteristics are identical with those of the type 6BCG.



BOTTOM VIEW OF SOCKET

#### RATINGS

Heater Voltage (a-c or d-c)	6.3	volts
Moster Current	0.3	amp
Max. Plate Voltage	250	volts

#### DIRECT INTERELECTRODE CAPACITANCES

Gr1d to Plate	1.7	uu <b>f</b>
Input	2.0	μμ£
Output	3.5	µµ <b>£</b>


#### AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage	250	volts
Grid Bias	-2	volts
Amplification Factor	100	
Plate Resistance	91000	ohms
Transconductance	1100	μmhc <b>s</b>
Plate Current	1.	ma

#### DIODE SECTION

The two fiedes are independent of each other and of the triode section except for the common cathode. The diedes may be used as a half wave or as a full wave rectifier; or one diede may be used as a half wave rectifier for detection and the other diede used as a rectifier to obtain delayed. AVC voltage.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



RAYTHEON ENGINEERING SERVICE

ST 12-D BULB

9 00 16 MP

5 PRONG SMALL BASE TRIODE

DETECTOR OR AMPLIFIER
Heater Type Glass Bulb

The 76 is a triode type amplifier tube designed for service as a detector or amplifier in storage battery or a-c operated receivers.



INGS BOTTOM VIEW OF SOCKET

Heater Voltage (a-c or d-o) 6.3 volts
Heater Current 0.3 amp
Haximum Plate Voltage 250 volts

DIRECT INTERELECTRODE CAPACITANCES

 Grid to Plate
 2.8
 μμf

 Input
 3.5
 μμf

 Output
 2.5
 μμf

AMPLIFIER - CLASS A

Plate Voltage Grid Biast 100 250 volts -5 13.8 12000 -13.5 13.8 volts Amplification Factor Plate Resistance 9500 ohms Transconductance Plate Current 1150 1450 umhos 2.5 me

DETECTOR - BIASED TYPE

Plate Voltage 100 250 volts
Grid Bias (approximate) -3 -20 volts
Plate Current Adjusted to 0.2 ma, with no signal

DETECTOR - GRID LEAK TYPE

 Plate Voltage
 45
 voltage


 Grid
 Return to Cathode

 Grid Leak Resistance
 1 to 5
 megohms

 Grid Condenser
 0,00025
 µf

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

The d-c resistance in the grid circuit should not exceed I megohm.



RAYTHEON ENGINEERING SERVICE

ST 12-D BUILD

#### PENTODE

DETECTOR OR AMPLIFIER Heater Type Glass Bulb

The 77 is a pentode type amplifier tube designed for service as a detector or high frequency amplifier in storage battery or a-c operated receivers.

RATINGS

Heater Voltage (a-o or d-o) 6.3 Heater Current 0.3 Max. Plate Voltage 250 Max. Sereen Voltage 100 volts amp volts volts

BOTTOM VIEW OF SOCKET

DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate Input Output

0.007 max.\* 4.0 μμΙ μμ1 μμ1

#### AMPLIFIER - CLASS A

Plate Voltage	100	250	volts
Screen Voltage	60	100	volts
Grid Bias	-1.5	-3	volts
Suppressor	Connected	to Cathode	at Socket
Amplification Factor	715	1500	
Plate Resistance (approx.)	0.65	1.5	megohma
Transconductance	1100	1250	umhos
Plate Current	1.7	2.3	me.
Screen Current	0.4	0.6	ma.
Grid Bias (approx.)	-5.5	<del>-</del> 7.5	volts
(For cathode current cutoff)			

#### DETECTOR - BIASED TYPE


Plate Supply Voltage	100	250	250	volts
Screen Voltage	36	50	100	volts
Grid Bias	-1.95	-1.95	-4.3	volts
Cathode Resistor	12500	3000	10000	ohm <b>s</b>
Suppressor		Connected	to Cathode	at Socket
Cathode Current (no signal)	0.155	0.65	0.43	ma.
Plate Resistor	0.25	0.25	0.5	megohm
Blocking Condenser	0.01	0.03	0.03	u <b>.f</b>
Grid Resistor (for following tube	0.25	0.25	0.25	megohm
R-F Signal Voltage (RMS)	1.88	1.18	1.37	volts
Output Peak Voltage	14	17	17	volts
(At grid of following tube with	signal r	(%0S betalubor		

When a resistor is used in the grid circuit, its value should not exceed 1 megohm.

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

The internal shield is connected to the screen grid within the tube.

\*With tube shield



RAYTHEON ENGINEERING SERVICE

ST 12-D BULB

9 OR

6 PRONG SMALL BAS

#### PENTODE

REMOTE CUTOFF AMPLIFIER
Heater Type Glass Bulb

The 78 is a pentode type amplifier tube with remote outoff characteristics designed for service as a high frequency amplifier or mixer in storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the types 6K7 & 6K7G.



BOTTOM VIEW OF SOCKET

RATINGS

MRX 47 MA.

212

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Maximum Plate Voltage	250	volts
Maximum Screen Voltage	125	volts

#### DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate	0.007 max.* µ	u <b>r</b>
Input		μ£
Output	11 µ	μſ

#### AMPLIFIER - CLASS A

Plate Voltage Screen Voltage Grid Bias	90 90 <b>-3</b>	180 75 <b>-3</b>	250 100 -3	250 125 -3	volts volts min.volts
Suppressor		Conn	ested to	Cathode	at Socket
Amplification Factor	400	1100	1160	990	
Plate Resistance	0.315	1.0	0.8	0.6	megohm
Transconductance	1275	1100	1450	1650	umhos
Plate Current	5.4	4	7	10.5	ma.
Screen Current	1.3	1	1.7	2.6	ma.
Grid Bias	-38.5	-32.5	-42.5	-52.5	volts
(For transconductance = 2 umhos)	. •			2.5	. 02.0

#### MIXER - SUPERHETERODYNE CIRCUIT

Plate Voltage			250		volts
Soreen Voltage			100		volts
Grid Biast			-10		volts
Suppressor	Connected	to	Cathode	at	Socket


The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

The internal shield is connected to the cathode within the tube.

†The grid bias is not critical with an oscillator peak voltage 1 volt less than the grid bias.

\*With tube shield.

For additional curves refer to the type 6K7G.




RAYTHEON ENGINEERING SERVICE

ST 12-D RUI A

6 PRONG

TWIN TRIODE
POWER AMPLIFIER
tor Type

The 79 is a twin tricde type power amplifier tube designed for service as a Class B amplifier in the cutput stage of storage battery or a-c operated receivers. The ratings and electrical characteristics are identical with those of the type 6Y7G.



BOTTOM VIEW OF SOCKET

RATINGS

Heater

Heater Voltage (a-c or d-c) 6.3 volts
Heater Current 0.6 amp
Haximum Plate Voltage 250 volts
aximum Peak Flate Current (rer plate) 90 ma
Haximum Avorage Plate Dissipation 11.5 watts


Glass Bulb

AMPLIFIER - CLASS B

Plate Voltage	180	250	volts
Grid Bias	0	0	volts
No-Signal Plate Current (per plate)	3.8	5.3	ma
Load Resistance (plate to plate)	7000	14000	ohm:s
Power Output (approximate)	5.5	8	watts
(With average power input = 380 mw. grid to	grid)		

The voltage between heater and cathode should be kept as low as possible where they are not directly connected.

For additional curves refer to the type 6Y7G.



RAYTHEON ENGINEERING SERVICE

TWIN DIODE FULL WAVE HIGH VACUUM RECTIFIER
Filement Type Glass Bulb

STI4 BULB The 80 is a full wave high vacuum type rectifier tube designed for service in power supplies for a-c operated receivers. The ratings and characteristics are sidentical with those of types 5736 and 5Y4G. 4 PROMO MED. BASE



BOTTOM VIEW OF SOCKET

FULL WAVE RECTIFIER - CONDENSER INPUT FILTER


Filament Voltage Filament Current		5 a-c	volts amp
Maximum A-C Voltage per Plate	(RMS)350	400	volts
Maximum Inverse Peak Voltage	1000	1100	volts
Maximum Peak Plate Current	400	350	ma
Maximum D-G Output Current	125	110	ma.
•			

FULL WAVE RECTIFIER - CHOKE INPUT FILTER \*

Filament Voltage	5 a-c	volts
Filament Current	2	amp
Maximum A-C Voltage per Plate (RMS)	550	volts
Maximum Inverse Peak Voltage	1500	volts
Maximum Peak Plate Current	300	ma.
	135	
Maximum D-C Output Current	100	ma

AVERAGE TUBE VOLTAGE DROP (At 135 ma. output current per plate) 60 volts

\*Input Choke must be at least 20 henrys. An Input Condenser of not more than 0.1  $\mu f$  may be used.



RAYTHEON ENGINEERING SERVICE

DIODE

ST 16 BULB

HALF WAVE HIGH VACUUM RECTIFIER
Filament Type Glass Bulb

The 81 is a high vacuum type half wave rectifier tube designed for service in high voltage power supplies.



BOTTOM VIEW OF SOCKET


HALF WAVE RECTIFIER Condenser or Choke Input Filter

Filament Voltage	7.5 a-c	volta
Filament Current	1.25	amp
Maximum A-C Plate Voltage (RMS)	700	volta
Maximum D-C Output Current	85	ma

FULL WAVE RECTIFIER - TWO TUBES Condenser or Choke Input Filter

Filament Voltage Filament Current per Tube	7.5 a-c 1.25	volts
Maximum A-C Voltage per Plate (RMS) Maximum D-C Output Current	700	volts
maximum D-c output current	170	ma

AVERAGE TUBE	VOT TACE DROP	91	volts
WATTINGE TODG	VODIAGE DROF	9.1	ACTOR
(At 170 ma.	output current)		



RAYTHEON ENGINEERING SERVICE

STIA BULB

FULL WAVE MERCURY VAFOR RECTIFIER Filament Type Glass Bulb

The 82 is a full wave mercury vapor rectifier tube designed for service in power supplies for a-c operated receivers.



BOTTOM VIEW OF SOCKET


FULL WA	VE RE	CTIFIER
---------	-------	---------

Filament Voltage Filament Current Maximum A-C Voltage per Flate (RMS) Maximum Inverse Feak Voltage Maximum Feak Flate Current Maximum D-C Output Current	2.5 a-c 3 500 1400 400 125	volts amp volts volts ma ma
Tube Voltage Drop (approximate) (Independent of output current)	15	volts


Shielding of this tube, particularly in sensitive receivers, may be necessary to eliminate objectionable noise.

Radio frequency chokes (1 mh. or more) connected in series with each plate lead and placed within the shielding, if used, are usually necessary in receivers having high sensitivity.

Full plate load should not be applied to this tube until the filaments have reached their normal operating temperature. Under normal operating conditions the filaments heat quickly when the set is turned on and are ready to supply full load current before the tubes in the receiver require it.



RAYTHEON ENGINEERING SERVICE



TWIN DIODE FULL WAVE MERCURY VAPOR RECTIFIER Filament Type Glass Bulb

The 83 is a full wave mercury vapor rectifier tube designed for service in power supplies for a-c operated receivers.



BOTTOM VIEW OF SOCKET


FULL WAVE RECTIFIER

Filament Voltage	5 a-c	volts
Filament Current	3	emp
Maximum A-C Voltage per Plate (RMS)	500	voltš
Maximum Inverse Peak Voltage	1400	volts
Maximum Peak Plate Current	800	me.
Maximum D-C Output Current	250	ma
Tube Voltage Drop (approximate)	15	volts
(Independent of output current)		

Shielding of this tube, particularly in sensitive receivers, may be necessary to eliminate objectionable noise.

Radio frequency chokes (1 mh. or more) connected in series with each plate lead and placed within the shielding, if used, are usually necessary in receivers having high sensitivity.

Full plate load should not be applied to this tube until the filaments have reached their normal operating temperature. Under normal operating conditions, the filaments heat quickly when the set is turned on and are ready to supply full load current before the tubes in the receiver require it.



STI4 BULB

IS MAX

4 PRONG MED. BASE TWIN DIODE
FULL WAVE HIGH VACUUM RECTIFIER
Heater Type Glass Bulb

The 83-V is a full wave high vacuum type rectifier tube having a low voltage drop designed for service in power supplies delivering high output currents. The ratings and characteristics are identical with those of type 5V4G.




BOTTOM VIEW OF SOCKET

FULL WAVE RECTIFIER - CONDENSER OR CHOKE IMPUT FILTER

Heater Voltage	5 a <b>-c</b>	volts
Heater Current	2	amp
Maximum A-C Voltage per Plate (RMS)	400	volts
Maximum Inverse Peak Voltage	1100	volts
Maximum Peak Plate Current	700	ma
Maximum D-C Output Current	200	ma.
•		

AVERAGE TUBE VOLTAGE DROP 25 volts (At 200 ma. output current per plate)

The cathode is connected within the tube to the center of the heater.



RAYTHEON ENGINEERING SERVICE

TWIN DIODE FULL WAVE HIGH VACUUM RECTIFIER Heater Type Glass Bulb

ST 12-0 BULB 5 PRONG SMALL BASE


The 84/624 is a full wave high vacuum type rectifier tube designed for service in power supplies for storage battery or a-c operated receivers.



BOTTOM VIEW OF SOCKET

Condenser or Choke Input Filter		
Heater Voltage (a-c or d c) Heater Current Haximum A-C Voltage per Plate (RHS)	6.3 0.5 350	volts amp volts
Haximum Inverse Peak Voltage Haximum D-C Output Current Haximum D-C Voltage between	1000 60	volts ma
Heater and Cathode	500	volts
HALF WAVE RECTIFIER (Plates in Parallel) Condenser or Choke Input Filter		
Heater Voltage	6.3	volts
Heater Current	0.5	amp
Maximum A-C Plate Voltage (RMS)	350	volts
Maximum Inverse Peak Voltage Maximum D-C Output Current	1000 75	volts ma
Maximum D-C Voltage between	7.5	niec
Heater and Cathode	500	volts

AVERAGE TUBE VOLTAGE DROP (At 75 ma. output current per plate) 22 volts



RATIFIEO

DUO-DIODE TRIODE
DETECTOR AMPLIFIER
Heater Type Glass Bulb

The 85 is a duo-diode triode type amplifier tube designed for service as a combined diode detector, AVO rectifier, and audio frequency amplifier in storage audio frequency amplifier in storage ratings and electrical characteristics are identical with those of the type 8V70.



BOTTOM VIEW OF SOCKET

#### RATINGS

ST 12-0 BULB

6 PRONG SMALL BAS

Heater Voltage (a-c or d-c)	6.3	volts
Heater Current	0.3	amp
Haximum Plate Voltage	<b>25</b> 0	volts

#### DIRECT INTERELECTRODE CAPACITANCES - TRIODE SECTION

Grid to Plate	1.7	$\mu\mu f$
Input	2.0	μμΩ
Output	3.5	$\mu\mu$ f


#### AMPLIFIER - CLASS A - TRIODE SECTION

Plate Voltage Grid Bias Amplification Factor	135 -10.5 8.3	180 -13.5 8.3	250 -20 8.3	volts volts
Plate Resistance Transconductance Plate Current	11000	8500	7500	ohms
	750	975	1100	µmhos
	3.7	6	8	ma
Load Resistance	25000	20000	20000	ohms
Power Output	75	160	350	mw

#### DIODE SECTION

The two diode units are independent of each other and of the triode section except for the common cathode. The diodes may be used as a half wave or as a full wave rectifier; or one diode may be used as a half wave rectifier for detection, and the other diode used as a rectifier to obtain delayed AVC voltage.


The voltage between heater and cathode should be kept as low as possible where they are not directly connected.



RAYTHEON ENGINEERING SERVICE

89	RAYTHE	ON
360-00	PENTODE TRIPLE GRID POWER Neater Type	
57 12-0 BULB XBW, 17 b	The 19 is a triple gri plifier tube designed Class A triode, Class A B triode power amplif stage of storage batte ed receivers.	for service as a pentode or Class ier in the output
TO MAX TO STATE	RATINGS	

6 PRONG SMALL BASI



BOTTOM VIEW OF SOCKET

is used as a

	orreade(a⊸c o	r a-c/0.5	AOTER
Heater 0	urrent	0.4	amp
Maximum	Plate Voltage	250	volts
Haximum	Screen Voltag	ge 250	volts
AMPLIETER	- OT.ASS A - 7	TOD STOOTS	DIECTION

Vol 160 180 250 volts -20 -31 Grid (#1) -22.5 4.7 Bias volts Amplification Factor Plate Resistance 4.7 4.7 3000 2600 ohms Transconductance 1425 1550 1800 umhos Plate Current Load Resistance\* Power Output (5% second harmonic) 77 20 32 ma 7000 6500 5500 oluns 0.3 0.9 watts 0.4 AMPLIFIER - CLASS A - PENTODE COMMECTION

Grids #2 and #3 connected to plate

	Grid #3	connected	to cathode		
Plate Voltage	100	135	130	250	volts
Screen (Grid #2) Voltage	100	135	180	250	volts
Grid (#1) Bias	-10	-13.5	-18	-25	volts
Amplification Factor	125	125	125	125	
Plate Resistance	104000	92500	80000	70000	ohms
Transconductance	1200	1350	1550	1800	μmho <b>s</b>
Plate Current	9.5	14	20	32	ma.
Screen Current	1.6	2.2	3.0	5.5	ma
Load Resistance	10700	9200	8000	6750	ohms
Total Harmonics	9	9	9	9	percent
Power Output	0.33	0.75	1.5	3.4	watts


AMPLIFIER - CLASS B - TWO TUBES Grid #1 connected to Grid #2 Grid #3 connected to plate

Haximum Plate Voltage Haximum Peak Plate Current (per tube) Haximum Average Grid (#1 and #2) Dissipation (per tube) Typical Operation:	250 90 0.35	volts ma watts
Plate Voltage Grid (#1 and #2) Bias Vossimel Plate Current (per tube)	180 0	volts

Power Output (approximate)
The voltage bat Load Resistance (plate to 13600 9400 ohms 2.5 3.5 wette The voltage between heater and cathode should be kept as low as possible where they are not directly connected.
\*Approximately twice this value is recommended when the tube driver for a Class B stage.

AVERAGE PLATE CHARACTERISTICS AVERAGE PLATE CHARACTERISTICS 89 RHGE PLATE
TRIODE - CLASS A
GRIDS #2143 CONNECTED TO PLATE
Ez=6.3 TRIODE -CLASS B E++6.34 GRID #1 CONNECTED TO GRID #2 GRID #3 CONNECTED TO PLATE m 50 55 45 20 ATE 10 2 10 120 160 21 PLATE YOLTAGE AVERAGE PLATE CHARACTERISTICS
PENTODE CONNECTED TO
SPIP SCONNECTED TO
COMPOSE
CHAPODE
F. 6.3 \*\* CUPPENT 70 ₩ £ E36 = 250\* ATE 25 =-30 PLATE -40 504 n 0 25 125 150 350 PLATE VOLTAGE - VOLTS

# PENTODE



PENTODE
POWER AMPLIFIER
Filament Type Glass Bulb

The 050 is a pentode type power amplifier tube designed for service in the output stage of battery operated receivers. The ratings and electrical characteristics are identical with those of the type 1J5G.




BOTTOM YIEW OF SOCKET

#### RATINGS

Filament Voltage	2.0 d-c	volts
Filament Current	0.12	amp
Haximum Plate Voltage	135	volts
Haximum Soreen Voltage	135	volts
Maximum Soreen Voltage	135	volts

#### AMPLIFIER - CLASS A

Plate Voltage	135	volts
Screen Voltage	135	volts
Grid Bias	-16.5	volts
Amplification Factor	100	
Plate Resistance	0.1	megohm
Transconductance	1000	umhos
Plate Current	7	ma
Screen Current	2	ma.
Load Resistance	13500	ohms
Power Output	450	mw
Maximum Signal Voltage (RMS)	11.7	volts



# **WD-11** WX-12

WD-II


WX-12 TIO-BULB

- 17° QD. 18 MAX.

BRYONET 4 PROMG MEQ BRSE

## **RAYTHEON**

# WD-11 WX-12



W.

TRIODE DETECTOR OR AMPLIFIER

Filament Type Glass Bulb

The WD-11 and WD-12 are triode type amplifier tubes designed for service in battery operated receivers. Their ratings and electrical characteristics are identical.



RATINGS

Filament Voltage 1.1 d-o Filament Current 0.25 Maximum Plate Voltage 135 volts amp volts



DIRECT INTERELECTRODE CAPACITANCES

Grid to Plate μμΩ 2.5 Input μμ£ Output uu£



AMPLIFIER - CLASS A

Plate Voltage Grid Bias Amplification Factor 135 90 volts -10.5 6.6 15000 440 -4.5 6.6 volts Plate Resistance 15500 ohms Transconductance 425 umhos Plate Current 2.5

DETECTOR - BIASED TYPE

Plate Voltage Grid Bias (approximate) Plate Current 90 135 volts -10.5 -18 volts
Adjusted to 0.2 ma. with no signal


DETECTOR - GRID LEAK TYPE

Plate Voltage Grid 45 volts Return to positive filament 0.25 to 5 megohms 0.00025 µf Grid Leak Resistance Grid Condenser

# **V99 X99**

## **RAYTHEON**

# **V99 X99**



79 BULR

#### TRIODE DETECTOR OR AMPLIFIER Filament Type Glass Bulb

The V-99 and X-99 are triode type amplifier tubes designed for service in battery operated receivers. Their ratings and electrical characteristics are identical.



#### RATINGS

Fil. Voltage 3.0 3.3 d-c volts Fil. Current 0.060 0.063 amp Max. Plate Voltage 90 volts



# DIRECT INTERELECTRODE GAPACITANCES

Grid to Plate Ղպդ Ղպդ Ղպպ Input Output



## AMPLIFIER - CLASS A

Plate Voltage Grid Bias Amplification Factor	90 -4.5 6.6	volts volts
Plate Resistance	15500	ohma
Transconductance	425	µmhos
Plate Current	2,5	ma


#### DETECTOR - BIASED TYPE

Plate Voltage Grid Bias (approximate) Plate Current volts -10.5 volts
Adjusted to 0.2 ma. with no signal

#### DETECTOR - GRID LEAK TYPE

Plate Voltage	45	volts
Grid	Re	eturn to positive filament
Grid Leak Resist	ance 0.2	5 to 5 megohms
Grid Condenser	0.0	0025 uf

TWIN DIODE
GAS FILLED FULL WAVE RECTIFIER
Cold Cathode Type Glass Dulb



The BA is a gas filled full wave rectifier tube of the cold cathode type requiring no heater supply voltage. It is designed particularly for service in B battery eliminators for radio receivers.



BOTTOM VIEW OF SOCKET

#### FULL WAVE RECTIFIER

	A-C Voltage per Plate	(RUS)	350	volts
	D-C Output Current		<b>3</b> 50	
Maximum	Peak Plate Current		1000	ma.
	Inverse Peak Voltage		1000	volts
Minimum	Starting Peak Voltage		400	volts
Average	Dynamic Voltage Drop		80	volts

The type BA tube was developed primarily for use in 2 battery eliminators for radio receivers. It has the typical characteristics of all gas filled rectifiers as regards a constant voltage drop and shillty to handle high peak currents, Any tendency of the tube to generate r-f noise may be eliminated by proper shielding and filtering.

The BA is filled with a permanent gas rather than a vapor filling. The tube characteristics are independent of the surrounding temperature.

## **RAYTHEON**

BH

TWIN DIODE
GAS FILLED FULL WAVE RECTIFIER
Cold Cathode Type Glass Eulb



The BH is a gas filled full wave rectifier tube of the cold cathode type requiring no heater supply voltage. It is designed particularly for service in B battery eliminators for radio receivers.



BOTTOM VIEW OF SOCKET

FULL WAVE RECTIFIER

Maximum A-C Voltage per Plate (RMS)	350	volts
Maximum D-C Output Current	125	ma.
Maximum Peak Plate Current	400	ma
Maximum Inverse Peak Voltage	1000	volts
Minimum Starting Peak Voltage	350	volts
Average Dynamic Voltage Drop	90	volts


The type EH tube was developed primarily for use in B battery eliminators for radio receivers. It has the typical characteristics of all gas filled rectifiers as regards a constant voltage drop and ability to handle high peak currents. Any tendency of the tube to generate r-f noise may be eliminated by proper shielding and filtering.

The BH is filled with a permanent gas rather than a vapor filling. The tube characteristics are independent of the surrounding temperature.

## **RAYTHEON**

BR

DIODE
GAS FILLED HALF WAVE RECTIFIER
Cold Cathode Type Glass Bulb



The BR is a gas filled half wave rectifier tube of the cold cathode type requiring no heater supply voltage. It is designed for service where it is desirable to use a half-wave rectifier.




BOTTOM VIEW OF SOCKET

#### HALF WAVE RECTIFIER

Maximum A-C Plate Voltage (RMS)	300	volts
Maximum D-C Output Current	50	ma.
Maximum Peak Plate Current	200	ma
Maximum Inverse Peak Voltage	850	volts
Minimum Starting Peak Voltage	300	volts
Average Dynamic Voltage Drop	60	volts


The type BR tube was developed primarily for use in vibrator type B supply units for automobile receivers. It has the typical characteristics of all gas filled rectifiers as regards a constant voltage drop and ability to handle high peak currents. Any tendency of the tube to generate r-f noise may be eliminated by proper filtering and shielding. The shielding and filtering commonly used to eliminate vibrator noise will usually be sufficient.

The BR is filled with a permanent gas rather than a vapor filling. The tube characteristics are independent of the surrounding temperature.



RESISTANCE TUBES FOR BATTERY OPERATED TWO VOLT THRE RECEIVERS Octal Base Glass Bulb


The series of resistance tubes, NB-1 to NB-8, is designed for two volt tube receivers having filament current drains of 300 to 720 milliamperes, in steps of NB-1 to 60 milliamperes.



HATINGS	Fila	ment
Туре		rent.
NB-1	300	ma.
NB-2	360	ma
NB-3	420	ma
NB-4	480	ma
NB-5	540	ma
NB-6	600	ma
NTD_17	660	mo

720


NB-8



The NB tubes have one common tap; one short circuiting tap, for use with a 2 volt storage battery; one resistor tap, for use with an air cell; and one ballast resistor tap, for use with a 3 volt dry cell pack. The curve on the accompanying sheet shows the typical relation between filament voltage and applied voltage, using the tap for dry cell pack.

The resistors in the NB tubes are operated in air, in a sealed container and The resistors in the NE tubes are operated in air, in a sealed container mine the moderate ballasting action obtained when the tap for dry cell pack is used is due only to the change of resistance with temperature of the wire used. These resistors operate at a relatively low temperature and their resistance characteristics are permanent if the rated nominal current is not exceeded, so that the NE tube should not need replacement because of change exceeded, so that the NB tube s in characteristics during life.

The NB tubes are stamped with locating arrows marked "Storage Battery", "Air Cell" and "Dry Pack" on the base of the tube, as shown in Fig. 1. If a reference mark is placed on the chassis mid-way between pins #1 and #8 and the scoket wired, as shown in Fig. 2, a special scoket with three keyways or a special scoket with three keyways or a special scoket with the keyway drilled out may be used to connect the battery to the proper tap. In either of the above cases the arrow corresponding to the type of battery used should be lined up with the reference mark. A terminal strip may also be provided for connecting the filament battery, to the proper tap of the NB tube. In the latter case, the tube is left fixed and the filament battery is wired to the proper point on the terminal strip. tube is leit POS.C TYPE OF BATTERY PLACE LOCATING



2 volt storage Air Cell 3 volt Dry Cell Pack Position C

KEY IN Position Position B

BOTTOM OF SPECIAL SOCKET

TYPICAL BALLASTING CHARACTERISTIC CURVE NB RESISTANCE TUBE 3 VOLT DRY CELL CONNECTION State of the Control 24 2.3 ZZ 2.1 \$ , e , 1.8 1.6 Ø17 1.8 49 2.7 2.8 2.9 3.1 32 BATTERY VOLTAGE -VOLTS

# **K49C-B**

5" OR MAX

MAX.

## **RAYTHEON**

# **K49C-B**

RESISTANCE TUBE FOR A-C - D-C RECEIVERS Hetal Bulb Octal Bese



The K49C-B is a resistance tube designtor in the filament circuit of a-c -c-c receivers. A ballast resistor tap provides voltage for one or two 6.5 volt pilot lamps.

BOTTOM VIEW OF SOCKET CONNECT PILOT LAMPS BETWEEN PINS #78#8

volts

RATINGS

Voltage Drop at 300 ma. 49 volts Voltage Drop at 300 mm.
Supplies correct filament voltage to:
3-6.3 volt 300 mm. tubes and
2-25 volt 300 mm. tubes in series
Pilot Lamp Voltage at 300 mm.
2-6.3 volt 150 mm. lamps in series
1-6.3 volt 200 mm. lamp
1-6.3 volt 250 mm. lamp 10 volts 6.6 4.8 volts


When the pilot lamp voltage in an a-c - d-c receiver is taken from a tap on the filament voltage dropping resistor, which usually has no ballasting action, the peak voltage applied to the pilot lamps at the instant the line switch is closed may be several times the rated voltage of the lamps, due to the high initial current drawn by the tubes in the set. In order to limit this peak voltage to a reasonable value, the resistance of the pilot lamp section of a straight resistance tube must be considerably lower than that required to operate the lamps at their rated voltage with the tubes hot. Thus, with a straight resistance tube, the life of the pilot lamps is shortened by the high peak voltage and the final brilliancy is reduced by the low operating voltage.

In the K49C-B the pilot lamp section is a ballast resistor which changes from a low value of resistance with the tube cold to several times its initial value as the tube heats. This limits the peak voltage applied to the pilot lamps to a value within their voltage rating, and operates the lamps at a higher voltage than with a straight resistance tube, increasing the life and final brilliancy of the lamps. The ballasting action also makes it possible to use several different types of pilot lamps with satisfactory results.

The characteristic curves show the relation between pilot lamp voltage and thee for a typical K49C-B tube and a typical straight resistance tube with similar ratings.

The resistors in the K490-B are operated in air and the ballasting action obtained in the part shunted across the pilot lamps is due to the heat of the total winding. The resistors operate at relatively low temperature and their resistance characteristics are permanent if the normal rated current is not exceeded.

Resistance tubes with other ratings may also be made. There is considerable power available for ballasting action so that the total voltage drop may be changed to fit other tube combinations requiring either more or less voltage drop.



# RAYTHEON