

EQ/140

## Schematic

B I A M P<sup>®</sup>

---

S Y S T E M S

10074 SW Arctic Drive

Beaverton, OR 97005    503-641-7287

EQ/140 - TEST PROCEDURE

EQUIPMENT REQUIRED:

Oscilloscope: Tektronix 922 or Equivalent  
Generator: Tektronix FG507 or Equivalent  
A C Voltmeter: Tektronix DC502 or Equivalent  
Frequency Counter: Heath SM-4100 or Equivalent

NOTE: Complete testing requires use of a log sweep generator

SET UP AND TEST PROCEDURE

+ 10 DBv 1500 cycle generator source. All frequency controls MAX counter clockwise.

Range #1 X1/X10 Switch IN, IN/OUT Switch OUT  
"Q" to MAX clockwise position, -dB+ centered.

Range #2 X1/X10 Switch IN, IN/OUT Switch OUT  
"Q" to MAX clockwise position, -dB+ centered.

Range #3 X1/X10 Switch IN, IN/OUT Switch OUT  
"Q" to MAX clockwise position, -dB+ centered.

Range #4 X1/X10 Switch OUT, IN/OUT Switch OUT  
"Q" to MAX clockwise position, -dB+ centered.

MASTER IN/OUT Switch OUT.

MASTER Level MIN at its counter clockwise position.

Connect the OUTPUT JACK to an A.C. Voltmeter and Oscilloscope.

The OUTPUT Level should be -10.5 DBv

Rotate the MASTER Level control to its MAX clockwise position.

The OUTPUT Level should be +12.2 DBv and the MASTER L.E.D. should be ON.

Rotate the MASTER Level Control until the +10 L.E.D. just comes ON. The knob should be pointing towards #7 on the scale.

Switch the MASTER IN/OUT Switch IN.

Set up and test procedure...continued

Reset the generator OUTPUT Level to "0" DBv.

Push the Range #1 IN/OUT Switch IN and rotate the -dB+ control to its MAX clockwise position.

Rotate the FREQ Control to where the OUTPUT Signal Level PEAKS. The reading should be about 150 (X10).

The PEAK OUTPUT Level should be about 17 DBv ( $\pm 1$ DBv). The RED L.E.D. should come ON at about +10DBv. Rotate the -dB+ Control to its MAX counter clockwise position. The OUTPUT Level should be -17DBv( $\pm 1$ DBv). Return the -dB+ Control to "0" center and push the IN/OUT Switch OUT.

Push Range #2 IN/OUT Switch IN and rotate the -dB+ Control to its MAX clockwise position. Rotate the FREQ Control until the OUTPUT Signal Level PEAKS. The reading should be 150(X10). OUTPUT Level should be +17DBv( $\pm 1$ DBv). The +10DB L.E.D. should come ON at about +10DBv. Rotate the -dB+ Control to its MAX counter clockwise position BEFORE the Switch clicks. The OUTPUT Level should be -17DBv( $\pm 1$ DBv). Advance the -dB+ Control counter clockwise to "INFINITY". Carefully adjust the FREQUENCY CONTROL for MAXIMUM SIGNAL CUT. The attenuation should be -40DBv or GREATER. Return the -dB+ Control to "0" Center and push the IN/OUT Switch OUT.

Push the Range #3 IN/OUT Switch IN and rotate the -dB+ Control to its MAX Clockwise position. Rotate the FREQ Control for a PEAK in the OUTPUT Signal Level. The OUTPUT Level should be +17DBv( $\pm 1$ DBv). The reading should be 150 (X10) and the RED +10 L.E.D. should come on at about +10DBv. Rotate the -dB+ Control to its MAX counter clockwise Position BEFORE the Switch clicks. The OUTPUT Level should be -17DBv ( $\pm 1$ DBv).

Set up and test procedure...continued

The OUTPUT attenuation should be -40DBv or GREATER.

Return the -dB+ Control to "0" Center and push the IN/OUT Switch OUT.

Push the RAne #4 IN/OUT Switch IN and rotate the -dB+ Control to its MAX clockwise position. Rotate the FREQ Control until the OUTPUT Level PEAKS. The reading should be about 1500 (X1). The OUTPUT Level should be +17DBv ( $\pm 1$ DBv). The RED L.E.D. should come on at about +10DBv. Rotate the -dB+ Control to its MAX counter clockwise position. The OUTPUT Level should -17DBv( $\pm 1$ DBv). Return the -dB+ Control to "0" Center and push the IN/OUT Switch OUT.

#### "Q"ADJUST AND SHELVING TEST

Log Sweep Generator, "0" DB Level from 20 HZ to 20KHZ.

##### First Filter: 20HZ to 2KHZ

Push the IN/OUT Switch IN, X1/X10 Switch OUT. Rotate the FREQUENCY Control full clockwise.

Set the -dB+ Control to its MAX clockwise position. Rotate the "Q" Control from MAX clockwise to MAX counter clockwise position. The bandwidth will spread out and the OUTPUT Level may increase. Return the "Q" Control to its clockwise position. Depress the X1/X10 Switch and the PEAK should shift position to the right on the scope display. Rotate the "Q" Control to "SHELF". The scope pattern should be HIGH on the LEFT SIDE of the scope display and taper down towards the RIGHT SIDE of the screen. Rotate the FREQ Control counter clockwise and the taper will level off closer to the LEFT side of the screen. Return -dB+ Control to "0" Center.

"Q" Adjust and Shelving Test...continued

Second Filter: 50HZ to 5KHZ

Repeat the First Filter procedure EXCEPT there is NO SHELF TEST.

Third Filter: 100 HA to 10KHZ

Repeat Second Filter procedure.

Fourth Filter: 200 HZ to 20KHZ

Repeat the procedure for the First Filter. The only difference being the Shelf Display will TAPER DOWN from the RIGHT, NOT the LEFT.

#### BALANCED OUTPUT

Transformer couple the output to the A C Voltmeter.  
Adjust the output Level to "0" DBv.

Short separately Pin 2(T) and Pin 3(R) of the XLR OUTPUT connector to GROUND. The Output Level should NOT change.

Connect a balanced INPUT source to the INPUT SLR connector and note NORMAL OUTPUT.

#### NOISE MEASUREMENT

All Filter and Master IN/OUT Switches OUT. Master Level set at "7" on scale. Measure noise at 80 DBv below "0" reference.

All Filter Frequency, "Q", and -dB+ Controls set at center of rotation. Push all Filter and Master IN/OUT Switches IN. All range Switches OUT (X1).

NOISE should be 80DBv below "0" reference.

Noise Measurement...continued

All -dB+ Control to +16 clockwise and all Filter IN/OUT Switches OUT. Depress each Filter IN/OUT Switches IN INDIVIDUALLY. Noise should be at least 78 DBv below "0" reference.


Note: Lowest noise will be obtained with the top and bottom covers on the unit. BEWARE of excessive RADIATION from nearby equipment.

CHANGE DATE BY  
REV. E.C.O. 102-83 DELETED SWITCH, +15V CAP  
MOVED TO COMP. SIDE 6-83 MVR  
C 101-83 ADD C14, C15, D15, C60 9-83 MVR


J1 PIN ASSIGNMENT	
PIN	DESCRIPTION
1	- INPUT
2	+ INPUT
3	INPUT GROUND
4	N.C.
5	OUTPUT
6	POWER SUPPLY GRID
7	+15V DC REG
8	-15V DC REG

THIS DRAWING IS THE PROPERTY OF ONE LAW INSTITUTE INC. AND MUST NOT BE REPRODUCED.  
THE RECIPIENT IT MAY NOT BE PROTECTED AGAINST DISCLIAINE TO ANYONE EXCEPT  
THOSE EMPLOYEES WHO RECDUE IT FOR THE WORK ON THE RECEIPT AND  
IT IS LOVED THAT IT NOT BE USED FOR ANY OTHER PURPOSE.  
IT IS THE PROPERTY OF ONE LAW INSTITUTE INC. AND NOT MAKE UNAUTHORIZED USE.


ASSEMBLE TO SUB-UNIT BEFORE MOUNTING TO BOARD




SUB-ASSEMBLY PARTS	
DESCRIPTION	P/N QTY
1. MACHINE SCREW 440-7/8"	522-0002-00 1
2. SHOULDER WASHER #4 SW PLASTIC T721-TPPS	540-0012 2
3. NEG. REGULATOR LM7815T (-15V)	260-0021-00 1
4. MICRO INSULATOR TO-220 CASE	270-0012-00 2
5. HEATSINK	350-0084-00 2
6. POS. REGULATOR LM7805T (+15V)	260-0020-00 1
7. 1/4-20 HEX NUT	525-0012-00 1
8. TERMACOTE	505-0005-00



REV	ECO	CHANGE	DATE
B	02	CHANGED CIRCUIT	6-23 MIAZ
C	181-83	ADD C4/C5 CHG'D R8, R11	9-23 MIAZ





## PIN ASSIGNMENTS

PIN	FUNCTION
1	- INPUT
2	+ INPUT
3	ZN GND
4	N.C.
5	OUTPUT
6	PZ GND
7	+ 15V REG
8	- 15V REG

WAVELENGTH REFERENCE DISK  
R946 C60

BIAMP SYSTEMS INC.	
COMPONENT ASSEMBLY	PCB
EQ 140	DATE
MA	LOCATION
04-01-2002-00	TIME
Serial No. 2X	Part No. 1

H

G

F


E


D


C

B

A







BLAMP SYSTEMS INC.  
SCHEMATIC ASSEMBLY  
FILTER PCB EQ 140  
B41-0002-00  
REV C

DRAWN RC 2-83  
CHECKED JD 2-83  
APPROVED DMR 1-93  
PAGE 2 OF 3

REV.	E.C.D.	CHANGE	DATE	BY
------	--------	--------	------	----