
## FILEMENT 2 0 3

BOTTOM VIEW OF BASE



## GRID CONTROL RECTIFIER TUBE

## TANTALUM ANODE AND XENON GAS FILLING

Maximum Rated Anode Current	
D-c. Meter Value-Continuous	6.4 amps
D-c. Meter Value-Overload less than 3 s	
Averaging Time	6 secs
Oscillograph Peak-Continuously recurri	ng 77 amps
Max. Instantaneous Short Circuit Curren	t (0.1 sec.) 770 amps
Peak Forward Voltage (Max. Instantaneous	1000 volts
Peak Inverse Voltage (Max. Instantaneous	•
Max. Commutation Factor (V/usec x A/us at a maximum initial inverse voltage of	
Filament	
Voltage	2.5 volts
Current	21 <u>+</u> 2 amps
Heating Time (minimum)	60 secs
Average Arc Drop	
Average Tube	9 volts
Highest Tube at end of life	12 volts
Anode Starting Voltage (D. C.) @ +4V d-c. grid voltage	
Average Tube	40 volts
Highest Tube	75 volts
Grid Characteristics	
Critical Grid Voltage @ 1000 p.f.v.	-4.6 <u>+</u> 1.6 volts
Critical Grid Current	Less than 10 uamps
Grid-Anode Capacitance	approx. 4 uuf
Grid-Filament Capacitance	approx.21 uuf
Maximum Negative Grid Voltage	100 volts
Deionization Time	Less than 1000 usecs
Ambient Temperature Limits	-55° to +75° C
Overall Dimensions	$2-1/32'' \times 9-1/2'' \text{ Max.}$
Weight	7 ozs.
Compostions	

Connections

Filament and Grid Metal industrial base A4-81
Anode C1-5 cap (0.56" dia.) with ceramic insulator.

The filament must be lit before drawing d-c. load current.

The anode is designed to operate at red heat when under full load. All of the above values are for returns to the filament transformer center tap. Filament pin #2 should be negative with respect to pin #3 during the anode conduction period.

The Engineering Manual contains additional information which should be considered in the circuit design.

ELECTRONS, INCORPORATED 127 Sussex Avenue Newark 3, New Jersey